



ALBANIAN ROAD AUTHORITY
SOUTHERN REGION DIRECTORATE - GJIROKASTRA

LIMIT FUND BILL OF QUANTITIES

OBJECT: "PERFORMANCE-BASED WINTER AND ROUTINE MAINTENANCE, KORCE - ERSEKE ROAD + ERSEKE RING ROAD - ERSEKE ROAD + K/BOBOSHTICE - DARDHE ROAD 54,5 KM"

PERIOD: 48 months

DRAFTING PERIOD: MAY 2020

SUMMARY OF BILL OF QUANTITIES

Road No.	Index	Road name	Length (km)	Period (month)	Price (ALL/km/month)	Amount (ALL)
			a	b	c	(a*b*c)
		ROUTINE MAINTENANCE				
SH-75	1/1	Korce - Erseke	38.8	48		
SH-75	1/2	Erseke Ring Road - Erseke	2.1	48		
SH-90	1/3	K/Boboshtice - Dardhe	13.6	48		
	1	ROUTINE MAINTENANCE SUM	54.5			
	2	EMERGENCY WORKS	(3% of routine works)			
	3	PERIODIC WORKS	(carried from periodic works bill of quantities)			
		SUM 1+2+3				
		20% VAT				
		TOTAL				

Note: With regards to routine maintenance bid price the economic operators should refer to technical specifications, analyses of work processes for this item, as well as technical description of each road segment.

ROUTINE MAINTENANCE BILL OF QUANTITIES

OBJECT: "PERFORMANCE-BASED WINTER AND ROUTINE MAINTENANCE, KORCE - ERSEKE ROAD + ERSEKE RING ROAD - ERSEKE ROAD + K/BOBOSHTICE - DARDHE ROAD 54,5 KM"

PERIOD: 48 months

DRAFTING PERIOD: MAY 2020

TABLE 1/1 (ROUTINE MAINTENANCE, KORCE - ERSEKE ROAD AXIS 38.8 KM)

Item No.	Description	Unit	Price (ALL/km/month)
A	ROUTINE MAINTENANCE		asphalt road
1	Cleaning of roadside ditches and gutters	month	
2	Cleaning of existing circular and box culverts	month	

3	Filling and leveling of shoulders	month	
4	Removal of vegetation	month	
5	Cleaning of carriageway from alluvium and other materials	month	
6	Repair of asphalt potholes	month	
7	Filling and profiling of subgrades in asphalt roads	month	
8	Repair and upgrade of horizontal road signs	month	
9	Repair and upgrade of vertical road signs and road safety (guardrails) and lighting devices	month	
10	Routine maintenance of art works	month	
	TOTAL PRICE OF ROUTINE MAINTENANCE (ALL/km/month)	SUM A	
	WINTER MAINTENANCE (ALL/km/month)	SUM B	
	TOTAL PRICE OF WINTER AND ROUTINE MAINTENANCE (ALL/km/month)	SUM A+B	

TABLE 1/2 (WINTER AND ROUTINE MAINTENANCE, ERSEKE RING ROAD - ERSEKE ROAD 2.1 KM)

Item No.	Description	Unit	Price (ALL/km/month)
A	ROUTINE MAINTENANCE		asphalt road
1	Cleaning of roadside ditches and gutters	month	
2	Cleaning of existing circular and box culverts	month	
3	Filling and leveling of shoulders	month	
4	Removal of vegetation	month	
5	Cleaning of carriageway from alluvium and other materials	month	
6	Repair of asphalt potholes	month	
7	Filling and profiling of subgrades in asphalt roads	month	
8	Repair and upgrade of horizontal road signs	month	
9	Repair and upgrade of vertical road signs and road safety (guardrails) and lighting devices	month	
10	Routine maintenance of art works	month	
	TOTAL PRICE OF ROUTINE MAINTENANCE (ALL/km/month)	SUM A	
	WINTER MAINTENANCE (ALL/km/month)	SUM B	
	TOTAL PRICE OF WINTER AND ROUTINE MAINTENANCE (ALL/km/month)	SUM A+B	

TABLE 1/3 (ROUTINE MAINTENANCE, K/BOBOSHTICE - DARDHE ROAD AXIS 13.6 KM)

Item No.	Description	Unit	Price (ALL/km/month)
A	ROUTINE MAINTENANCE		asphalt road
1	Cleaning of roadside ditches and gutters	month	
2	Cleaning of existing circular and box culverts	month	
3	Filling and leveling of shoulders	month	
4	Removal of vegetation	month	
5	Cleaning of carriageway from alluvium and other materials	month	
6	Repair of asphalt potholes	month	
7	Filling and profiling of subgrades in asphalt roads	month	
8	Repair and upgrade of horizontal road signs	month	
9	Repair and upgrade of vertical road signs and road safety (guardrails) and lighting devices	month	
10	Routine maintenance of art works	month	
	TOTAL PRICE OF ROUTINE MAINTENANCE (ALL/km/month)	SUM A	
	WINTER MAINTENANCE (ALL/km/month)	SUM B	
	TOTAL PRICE OF WINTER AND ROUTINE MAINTENANCE (ALL/km/month)	SUM A+B	

BILL OF QUANTITIES FOR PERIODIC/REHABILITATION WORKS

OBJECT: "PERFORMANCE-BASED WINTER AND ROUTINE MAINTENANCE, KORCE - ERSEKE ROAD + ERSEKE RING ROAD - ERSEKE ROAD + K/BOBOSHTICE - DARDHE ROAD 54,5 KM"

PERIOD: 48 months

DRAFTING PERIOD: MAY 2020

TABLE 3 (BILL OF QUANTITIES FOR PERIODIC/REHABILITATION WORKS 61.6 KM)

No.	No.	WORKS DESCRIPTION	UNIT	QUANTITY	PRICE	AMOUNT
		EXCAVATION WORKS				
1	3.89/a	Soil excavation by wheeled excavators 0.25 m ³ , in ditches with a width up to 2 m, ordinary soil, category III, unloaded in vehicles	m3	200		
2	3.158/3a	Soil transportation by trucks in a distance up to 3.0 km	m3	1000		
3	3,161/2	Leveling of escarpments through excavation, excavator 0.25m ³	m2	1000		
4	An.124/3a	Free section rock excavation by the use small mines and excavator 1m ³ + transportation	m3	100		
5	An.164/1a	Filling of road track with gravel and quarry stones, spread and compacted by machines	m3	200		
		LAYER WORKS				
6	3.212/c	Stabilizing layer t=15cm	m2	1200		
7	3.212/d	Stabilizing layer t=20cm	m2	1200		
8	An	Scarifying of asphalt layers by machines	m2	1200		
		ASPHALT WORKS				

9	3.222/2	Binder layer with crushed stones and quarry stones, 6cm, by machines	m2	1200		
10	3.226/1	Asphalt concrete layer with crushed stones and quarry stones, 4cm, by machines	m2	12000		
		CONCRETE AND REINFORCED CONCRETE WORKS				
11	3.235	Monolithic b/concrete construction C 12/15 with 20% stone	m3	100		
12	3.245/1	Thin monolithic concrete structures C 25/30	m3	20		
13	3.246	Monolithic concrete structures with gravel C 20/25	m3	100		
14	3.268	Supply and installation of rectangular culverts b/a C 16/20	m3	20		
		REINFORCED CONCRETE WORKS				
15	3.287	Supply and installation of common rebars \varnothing 6 ~ 10mm	tons	1		
16	3.288	Supply and installation of common rebars \varnothing > 12mm	tons	1		
		CONSTRUCTION OF ART WORKS				
17	3.323	Stone retaining wall, M50 cement mortar	m3	50		
18	3.332	Gabion walls with galvanized wire mesh, crushed stone 1x1x1.5 m	m3	50		
19	3.352	Filling with quarry stones	m3	100		
20	3.366	Culverts with concrete pipes \varnothing 800, above the concrete layer	m	20		
21	3.367	Culverts with concrete pipes \varnothing 1000, above the concrete layer	m	20		
22	An-8	Filling the walls with gravel	m3	100		
		DIFFERENT WORKS				
23	3.618	Supply and installation of concrete kerbs 20x35 cm	m	50		
24	3.636	Precast metal bridge parapets	tons	1		
		ROAD SIGNS WORKS				
25	An4	H1 W3 single-sided guardrail with 2 wave beams + accessories (road)	ml	2000		
26	An35	Single-sided concrete parapet (\varnothing 60) + accessories (bridge)	ml	20		
27	An106	Common triangular sign board with A = 90	pcs	2		
28	An116	Common side road marking lines with two senses (red + white)	pcs	1500		
29	An118	(Single) turn dotted marking lines	pcs	10		
30	An119	(Double) turn dotted marking lines	pcs	30		
31	An120	Mild or sharp (T-shaped) turn marking lines	pcs	10		
32	An151	Road marking lines with bicomponent paint	m2	12560		
33	An147	Audible lines (with gel bicomponent paint + beads 5 kg/m2)	m2	100		
34	An156	Supply and installation of road indication sign boards 150x40cm	pcs	20		
35	An158	Supply and installation of different road sign boards D=60cm	pcs	350		
		TOTAL				

