

Objekti : “HARTIM PROJEKTI PER RIKONSTRUKSIONIN E GODINES SE POLIKLINIKES QENDRORE” KRYESORE DURRES ”

ANALIZA CMIMESH - PUNIME PRISHJEJE DHE CMONTIMI

FAZA PROJEKT ZBATIMI

AUTORITETI KONTRAKTOR : SPITALI RAJONAL DURRES

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefte	T*km	çmimi	Vlefte	o.p	çmimi	Vlefte	Sasia	çmimi	Vlefte				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 1	Prerje Solete ekzistuese	m3																
	Sp + p	op	3,0	185	555													
	Sigurime shoqerore 16.7%	leke	555,3145	0,167	93													
	Makine prerese - sharre betoni	op							3,00	4800	14400							
	Shuma:				648			0			14400			0	15048	1204	1505	17757

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefte	T*km	çmimi	Vlefte	o.p	çmimi	Vlefte	Sasia	çmimi	Vlefte				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An -2	Heqje ndricuesa ekzistues	cope																
	Sp + p	op	2,35	185	435													
	Sigurime shoqerore 16.7%	leke	435,49	0,167	73													
	Shuma:				508			0			0			0	508	41	51	600

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefte	T*km	çmimi	Vlefte	o.p	çmimi	Vlefte	Sasia	çmimi	Vlefte				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 3	Heqje dritare/ vetrate d/alumini fasade pa i demtuar ato	m2																
	Sp + p	op	4,0	185	743													
	Sigurime shoqerore 16.7%	leke	742,775	0,167	124													
	Skele inventari	m2										0,50	130	65				
	Shuma:				867			0			0			65	932	75	93	1100

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 4	Heqje dyer te brendshme e te jashtme pa i demtuar ato	m2																
	Sp + p	op	3,14	185	581													
	Sigurime shoqerore 16.7%	leke	581,27	0,167	97													
	Shuma:				678			0						0	678	54	68	800

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 5	Heqje mermeri i shkalleve dhe parvazet e dritareve	m2																
	Sp + p	op	2,36	185	436													
	Sigurime shoqerore 16.7%	leke	436,045	0,167	73													
	Shuma:				509			0			0			0	509	41	51	600

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An-6	Heqje shtrese pllaka (ambiente + tualete) dhe veshje tualeti	m2																
	Sp + p	op	1,38	185	254													
	Sigurime shoqerore 16.7%	leke	254,375	0,167	42													
	Shuma:				297			0			0			0	297	24	30	350

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An-7	Heqje paisje hidrosanitare (komplet)	cope																
	Sp + p	op	5,9	185	1089													
	Sigurime shoqerore 16.7%	leke	1089,465	0,167	182													
	Shuma:				1271			0			0			0	1271	102	127	1500

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An-8	Heqje e sistemit te ujit sanitar	cope																
	Sp + p	op	25,5	185	4723													
	Sigurime shoqerore 16.7%	leke	4723,05	0,167	789													
	Makineri per cmontim	op							8	900	7200							
	Shuma:				5512			0			7200			0	12712	1017	1271	15.000

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 9	Heqje e sistemit elektrik, celsa priza panel etj	cope																
	Sp + p	op	28,8	185	5337													
	Sigurime shoqerore 16.7%	leke	5337,1205	0,167	891													
	Makineri per cmontim	op							18	900	16200							
	Skele inventari	m2										10,00	130	1300				
	Shuma:				6228			0			16200			1300	23728	1898	2373	28.000

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An-10	Heqje e shtresave ekzistuese ne tarrace	m ²																
	Sp + p	op	2,1	185	389													
	Sigurime shoqerore 16.7%	leke	389,425	0,167	65													
	Vinc	m2							1	53	53							
	Skele inventari	m2										0,01	130	1				
	Shuma:				454			0			53			1	509	41	51	600

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 11	Prishje suvatim nga jashte fasada	m2																
	Sp + p	op	1,7	185	311													
	Sigurime shoqerore 16.7%	leke	311	0,167	52													
	Skele inventari	m2										0,60	130	78				
	Shuma:				363			0			0			78	441	35	44	520

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefte	T*km	çmimi	Vlefte	o.p	çmimi	Vlefte	Sasia	çmimi	Vlefte				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 12	Prishje suvatim nga brenda ne solete	m2																
	Sp + p	op	1,41	185	260													
	Sigurime shoqerore 16.7%	leke	260,11	0,167	43													
	Skele inventari	m2										0,6	130	78				
	Shuma:				304			0			0			78	382	31	38	450

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefte	T*km	çmimi	Vlefte	o.p	çmimi	Vlefte	Sasia	çmimi	Vlefte				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 13	Prishje suvatim nga brenda mure	m2																
	Sp + p	op	1,1	185	210													
	Sigurime shoqerore 16.7%	leke	210	0,167	35													
	Skele inventari	m2										0,40	130	52				
	Shuma:				245									52	297	24	30	350

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefte	T*km	çmimi	Vlefte	o.p	çmimi	Vlefte	Sasia	çmimi	Vlefte				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 14	Prishje suvatim dhe pastrim te lageshtires nga brenda mure podrumi	m2																
	Sp + p	op	1,74	185	322													
	Sigurime shoqerore 16.7%	leke	322	0,167	54													
	Skele inventari	m2										0,40	130	52				
	Shuma:				376									52	428	34	43	505

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 15	Prishje suvatim dhe pastrim te lageshtires nga brenda tavan podrumi	m2																
	Sp + p	op	2,00	185	370													
	Sigurime shoqerore 16.7%	leke	370	0,167	62													
	Skele inventari	m2										0,6	130	78				
	Shuma:				432			0			0			78	510	41	51	602

Nr. Kodi	E M E R T I M I	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefta	T*km	çmimi	Vlefta	o.p	çmimi	Vlefta	Sasia	çmimi	Vlefta				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An - 16	Transport vertikal i mbeturinave te ndertimit	m3																
	Sp + p	op	1,17	185	216													
	Sigurime shoqerore 16.7%	leke			0													
	Vinc	m2							0,6	53	31,8							
	Shuma:				216			0			31,8			0	247	20	25	292

Projektues : ARKONSTUDIO sh.p.k

