

PREVENTIV

Objekti: "Zevendesim i kolektoreve te puseve te Grupeve 5,6,8,9,15,17 Q.P.N Gorisht"

Nr	Analiza	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
I.Grupi Nr.6						
1	An(4.60)	F.V tubo celiku pa tegel Ø219.1mmx7.1, 20.4 ml	ton	0.76		
2	An(4.59)	F.V tubo celiku pa tegel Ø168.3mmx7.1, 20.4 ml	ton	0.577		
3	An(4.59)	F.V tubo celiku pa tegel Ø88.9mmx7.1 per ypsilonet, 50ml	ton	0.717		
4	An(4.59)	F.V.tubo celiku pa tegel Ø88.9mmx7.1, per shtese te linjave hyrese te puseve, 50ml	ton	0.717		
5	An	Demontim i saraqineskave hyrese te vjetra te puseve	cope	50		
6	An	Takimi kokash tubo Ø88.9mmx7.1 mm	cope	25		
7	4.121/4	F.V Saraqineska çeliku me fllanxha Ø100, Pn 25bar	cope	50		
8	4.121/8	F.V Saraqineska çeliku me fllanxha Ø200, Pn 25bar	cope	1		
9	4.121/10	F.V Saraqineska çeliku me fllanxha Ø300, Pn 25bar	cope	1		
10	4.115/4	F.V. fllanxha inox cift Pn÷25, Ø100	çift	50		
11	4.115/7	F.V. fllanxha inox cift Pn÷25, Ø200	çift	3		
12	4.115/9	F.V. fllanxha inox cift Pn÷25, Ø300	çift	3		
13	4.112/a	Bojatisje 1 dore minio, 2 duar boje vaji i linjave teknologjike	m ²	54		
14	3.205/2	Shtrese zhavor lumi t=20cm, perhapur e ngjeshur me makineri	m ²	51		
15	3-240	Bazamente betoni C12/15	m ³	1.9		
16	3-240	Shtrese betoni C12/15, t=10 cm	m ³	5.1		
SHUMA I						
1	An(4.59)	F.V tubo celiku pa tegel Ø88.9mmx7.1mm, per 3 ypsilone, 6ml	ton	0.086		
2	An	Takimi kokash tubo Ø88.9mmx7.1	cope	3		
3	4.112/a	Bojatisje 1 dore minio, 2 duar boje vaji i linjave teknologjike	m ²	14		
SHUMA II						
1	An	Demontim i saraqineskave hyrese te vjetra te puseve	cope	2		
2	4.121/4	F.V Saraqineska çeliku me fllanxha Ø100, Pn 25bar	cope	2		
3	4.115/4	F.V. fllanxha inox cift Pn÷25, Ø100	çift	2		
4	4.112/a	Bojatisje 1 dore minio, 2 duar boje vaji i linjave teknologjike	m ²	4		
SHUMA III						
1	An(4.60)	F.V tubo celiku pa tegel Ø219.1mmx7.1, 10.8 ml	ton	0.402		
2	An(4.59)	F.V tubo celiku pa tegel Ø168.3mmx7.1, 10.8 ml	ton	0.305		
3	An(4.59)	F.V tubo celiku pa tegel Ø88.9mmx7.1 per ypsilonet , 26 ml	ton	0.373		
4	An(4.59)	F.V.tubo celiku pa tegel Ø88.9mmx7.1, per shtese te linjave hyrese te puseve, 26ml	ton	0.373		
5	An	Demontim i saraqineskave hyrese te vjetra te puseve	cope	13		
6	An	Takimi kokash tubo Ø88.9mmx7.1	cope	13		
7	4.121/4	F.V Saraqineska çeliku me fllanxha Ø100, Pn 25bar	cope	26		
8	4.121/8	F.V Saraqineska çeliku me fllanxha Ø200, Pn 25bar	cope	1		
9	4.121/10	F.V Saraqineska çeliku me fllanxha Ø300, Pn 25bar	cope	1		
10	4.115/4	F.V. fllanxha inox cift Pn÷25, Ø100	cope	26		
11	4.115/7	F.V. fllanxha inox cift Pn÷25, Ø200	çift	3		
12	4.115/9	F.V. fllanxha inox cift Pn÷25, Ø300	çift	3		

13	4.112/a	Bojatisje 1 dore minio, 2 duar boje vaji i linjave teknologjike	m ²	28		
14	3.205/2	Shtrese zhavor lumi t=20 cm, perhapur e ngjeshur me makineri	m ²	27		
15	3-240	Bazamente betoni C12/15	m ³	1.1		
16	3-240	Shtrese betoni C12/15, t=10 cm	m ³	2.7		
		SHUMA IV				
1	An	Demontim i saraqineskave hyrese te vjetra te puseve	cope	11		
2	4.121/4	F.V Saraqineska çeliku me fllanxha Ø100, Pn 25bar	cope	11		
3	4.115/4	F.V. fllanxha inox cift Pn÷25, Ø100	cope	11		
4	4.112/a	Bojatisje 1 dore minio, 2 duar boje vaji i linjave teknologjike	m ²	20		
		SHUMA V				
1	An	Demontim i saraqineskave hyrese te vjetra te puseve	cope	5		
2	4.121/4	F.V Saraqineska çeliku me fllanxha Ø100, Pn 25bar	cope	5		
3	4.115/4	F.V. fllanxha inox cift Pn÷25, Ø100	cope	5		
4	4.112/a	Bojatisje 1 dore minio, 2 duar boje vaji i linjave teknologjike	m ²	23		
		SHUMA VI				
		SHUMA I+II+III+IV+V+VI				
		TVSH 20%				
		SHUMA TOTALE				

