

PREVENTIV

Objekti: "Ndertim i RVM-ve ne Sek. Cakran-Mollaj"

A. RVM 60 m³ ne Qendrat 25, 29, 35, 38

Nr	Analiza	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
1	2	3	4	5	6	7
1	An	Heqja e RVM 60 m ³ te demtuar	cope	1		
2	4.13	FV RVM 60 m ³	ton	4.7		
3	4.4/p	FV shkalle marinari	ton	0.153		
4	4.13	FV rrethimi mbrojtjes i mbuleses	ton	0.094		
5	4.3	Fv konstruksion per nivelmates	ton	0.036		
6	4.167/1	F.V.Tokezime e mbrojtje atmosferike ne rezervuar	ton	0.083		
7	4.113/8	FV bokaporte per marrje kampioni Dn200, Pn25	cope	1		
8	4.113/14	Fv bokaporte ndricimi/ajrimi Dn500, Pn25	cope	1		
9	4.113/14	Fv bokaporte sherbimi Dn500, Pn25	cope	1		
10	4.128/6	FV valvol kunder zjarrit Dn200, Pn25	cope	1		
11	4.125/2	Fv ventila kontrolli Ø=1" me flanaxha	cope	5		
12	4.113/2	Flanaxha per ventilat Dn25, Pn25 bar	cifte	5		
13	An(4.59)	Fv tubo celiku Ø=1" x3.2 mm, 10 ml (per marrje kampioni)	ton	0.02		
14	4.3	F.V. govata per marrje mostrash	ton	0.07		
15	4.112/a	Bojatisje mbi metal me nje dore minio e dy duar boje vaji, RVM	m ²	80		
16	4.112	Bojatisje mbi metal 1m2, me nje dore minio e dy duar boje vaji, konstruksione me profile (shkalle, parmake rrethimi,etj.)	m ²	25		
17	An	Takim me linjat ekzistuese	cope	3		
Shuma per 1 RVM						
Shuma per 4 RVM						

B. RVM 60 m³ ne Qendren 59

Nr	Analiza	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
1	2	3	4	5	6	7
1	4.13	FV RVM 60 m ³	ton	4.7		
2	4.4/p	FV shkalle marinari	ton	0.153		
3	4.13	FV rrethimi mbrojtjes i mbuleses	ton	0.094		
4	4.3	Fv konstruksion per nivelmates	ton	0.036		
5	4.167/1	F.V.Tokezime e mbrojtje atmosferike ne rezervuar	ton	0.083		
6	4.113/8	FV bokaporte per marrje kampioni Dn200, Pn25	cope	1		
7	4.113/14	Fv bokaporte ndricimi/ajrimi Dn500, Pn25	cope	1		
8	4.113/14	Fv bokaporte sherbimi Dn500, Pn25	cope	1		
9	4.128/6	FV valvol kunder zjarrit Dn200, Pn25	cope	1		
10	4.125/2	Fv ventila kontrolli Ø=1" me flanaxha	cope	5		
11	4.113/2	Flanaxha per ventilat Dn25, Pn25	cifte	5		
12	An(4.59)	Fv tubo celiku Ø=1"x 3.2 mm, 10 ml (per marrje kampioni)	ton	0.02		
13	4.3	F.V. govata per marrje mostrash	ton	0.07		
14	4.112/a	Bojatisje mbi metal me nje dore minio e dy duar boje vaji, RVM	m ²	80		
15	4.112	Bojatisje mbi metal 1m2, me nje dore minio e dy duar boje vaji, konstruksione me profile (shkalle, parmake rrethimi,etj.)	m ²	25		
16	An(4.59)	Fv tubo celiku Ø=4" x 7.1, L=40 ml (linja e hyrjes)	ton	0.752		

17	An(4.59)	Fv tubo celiku Ø=6" x 7.1, L=10 ml (linja e pompes)	ton	0.267		
18	An(4.59)	Fv tubo celiku Ø=4" x 7.1, L=4 ml (linja e shkarkimit te ujit)	ton	0.075		
19	4.121/4	FV saracineske celiku me fllanxha Dn100, Pn25	cope	5		
20	4.121/8	FV saracineske celiku me fllanxha Dn200, Pn25	cope	2		
21	4.115/4	F.V. fllanxha inox cift Dn100, Pn25	çift	5		
22	4.115/7	F.V. fllanxha inox cift Dn200, Pn25	çift	2		
23	3.223	Shtrese asfaltobetoni me granil guri kave, 2cm, me krah	m²	20		
24	An	Takim me linjat ekzistuese	cope	3		
Shuma per 5 RVM pa TVSH						
TVSH 20%						
Shuma me TVSH						