

PREVENTIV
OBJEKTI: RIKONSTRUKSION RRUGA "ALI KURTI"

Nr	Nr.AN	ZERAT E PUNIMEVE	NJESIA	SASIA	ÇMIMI	VLERA
1	3.89/b	Germim dheu me eskavator goma 0.25m ³ ne kanale gjeresi >2 m kat III me shk ne mjet. (per trupin e rruges)+ transport	m ³	120		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	15		
3	3.212	Shtrese çakelli t=15cm, makadam, perhapur e ngjeshur makineri.	m ²	1100		
4	3.212/b	Shtrese stabilizanti t = 10 cm	m ²	1100		
5	An	Shtrese binderi me zall lavatrice,6cm,me makineri	m ²	1100		
6	An	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m ²	1100		
7	An.164/1b	Mbushje me cakell, perhapur e ngjeshur me makineri (t=15cm) per rrugen dhe bankinat	m ³	165		
		SHUMA 1				

		T.V.SH 20%				-
		TOTALI ME TVSH				-