



BASHKIA VAU DEJËS

MIRATOHET
KRYETAR
Z. MARK BABANI

PREVENTIVI I PUNIMEVE

Objekti: Rikonstruksioni i rrugeve te Lagjes Lisen

Nr.	Nr. An.	Emertimi i Punimeve	Njësia	Sasia	Cmimi	Vlera
1	Punime dheu dhe shtresash					
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	353		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	353		
3	3.198	Cilindrim kasonete me rrul	m2	565		
4	An.164/1 b (M-3)	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri t=20cm (mbushje dhe shtresa)	m3	140		
5	3.212/b	Shtrese stabilizant t=10cm	m2	565		
7	3.229/1	Shtrese binderi me zall lavatrice t=5cm me makineri	m2	565		
8	3.231/1	Shtrese asfaltbetoni me zall lavatrice t=3cm me makineri	m2	565		
		Shuma	1			
2	Punime per trotuarin					
1	3.620	Trotuar, me 6 cm beton, me pllaka	m2	545.00		
2	2.261	Shtrese rere 4 cm	m ³	22.00		
3	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m2	545.00		
4	3.616	F V bordura betoni 12x25 cm (rruge + trotuar)	ml	550.00		
5	2.262/3	Shtrese betoni C 12/15 per fiksimin e bordurave	m ³	12.20		
8	An-49 (M-3)	Prishje struktura ekzistuese betoni	m ³	0.50		
9	2.426/2	Prishje mure blloqesh betoni (mure rrethues)	m ³	0.50		
		Shuma	2			
3	Punime per K.U.Z					
1	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	1,009		
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	1,009		
3	2.261	Shtrese rere 10 cm	m ³	203		
4	An-8 (M-3)	Mbushje me cakell	m3	742		
5	3.An/1t (M-3)	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	620		
6	3.An/2t (M-3)	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	70		
7	An - 19 (M-2)	Pusete shkarkimi b/a, 80 x 80 cm, h = 100 cm	cope	21		
8	2.575	Pusete 1x1x1.5m	cope	2		
		Shuma	3			

4		Punime per K.U.B					
1	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	745.200			
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	745.200			
3	2.261	Shtrese rere 10 cm	m ³	203.9			
4	An-8 (M-3)	Mbushje me cakell	m ³	531			
5	AN	F V tuba te brinjezuar HDPE SN8 d=250 mm	ml	615			
6	3.An/1t (M-3)	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	75			
7	An - 22 (M-2)	Pusete b/a shiu 40 x 40 cm, h = 100 cm, me kapak zga	cope	26			
Shuma			4				
5		Punime per sinjalistiken					
1	An123 (M-3)	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikomponente (paste)	m	1,070.00			
2	An155 (M-3)	F V tabela rrugore te ndryshme D=90cm	cope	4.00			
Shuma			5				
		Shuma					-
		Fond Rezerve	5%				-
		Shuma me Fond Rezerve					-
		TVSH 20 %	20%				-
		SHUMA TOTALE ME TVSH					-

PREVENTIVOI
 LENI-ING shpk
 Ing.Nikoll PALUCA