



MIRATOHET
KRYETAR
Z. MARK BABANI

BASHKIA VAU DEJËS
PREVENTIVI I PUNIMEVE

Objekti: Rikonstruksioni i Rrugeve te Lagjes Mlloje

Nr.	Nr. An.	Emertimi i Punimeve	Njësia	Sasia	Cmimi	Vlera
1	Punime dheu dhe shtresash					
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	1,010.00		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,010.00		
3	3.198	Cilindrim kasonete me rrul	m2	2,950.00		
4	An.164/1b (M-3)	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri t=20cm (mbushje dhe shtresa)	m3	670.00		
5	3.212/b	Shtrese stabilizant t=10cm	m2	2,400.00		
7	3.229/1	Shtrese binderi me zall lavatrice t=5cm me makineri	m2	2,400.00		
8	3.231/1	Shtrese asfaltobetoni me zall lavatrice t=3cm me makineri	m2	2,400.00		
		Shuma	1			
2	Punime per trotuarin					
1	3.620	Trotuar, me 6 cm beton, me pllaka	m2	344.00		
2	2.261	Shtrese rere 4 cm	m ³	13.80		
3	3.210	Shtrese çakem mbeturme kave t=15cm, perhapur e ngjeshur me makineri	m2	344.00		
4	3.616	F V bordura betoni 12x25 cm (rruge + trotuar)	m1	1,376.00		
5	2.262/3	Shtrese betoni C 12/15 per fiksimin e bordurave	m ³	30.30		
7	3.244	Struktura monolite betoni C 20/25 (per kuneten anesore)	m ³	46.50		
8	An-49 (M-3)	Prishje struktura ekzistuese betoni	m ³	0.50		
9	2.426/2	Prishje mure blloqesh betoni (mure rrethues)	m ³	0.50		

		Shuma	2			
3	Punime per K.U.B					
1	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	670.00		
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	670.00		
3	2.261	Shtrese rere 10 cm	m ³	183.00		
4	An-8 (M-3)	Mbushje me cakell	m ³	478.00		
5	AN	F V tuba te brinjezuar HDPE SN8 d=250 mm	ml	570.00		
6	3.An/1t (M-3)	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	50.00		
7	An - 22 (M-2)	Pusete b/a shiu 40 x 40 cm, h = 100 cm, me kapak zgare hekuri	cope	22.00		
		Shuma	3			
4	Punime per K.U.Z					
1	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	936.00		
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	936.00		
3	2.261	Shtrese rere 10 cm	m ³	189.00		
4	An-8 (M-3)	Mbushje me cakell	m ³	688.00		
5	3.An/1t (M-3)	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	570.00		
6	3.An/2t (M-3)	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	70.00		
7	An - 19 (M-2)	Pusete shkarkimi b/a, 80 x 80 cm, h = 100 cm	cope	18.00		
8	2.575	Pusete 1x1x1.5m	cope	2.00		
		Shuma	4			
5	Punime e instalimeve elektrike per ndricimin rrugor, puseta dhe tubacione elektrike					
		A. Instalimet elektrike per ndricim rrugor ne trotuar				
1	3.497/a	Germim dheu gropa per shtylla ndricimi toke mes. kat III sip. ~1.5m (0.075m ³ /cope)	m ³	2		
2	3.44/1	Germim kanale ne toke te bute me krah me seksion deri 0.75m ² S-0.15m ²	m ³	73.7		
3	3.44/1	Germim kanale ne toke te bute me krah me seksion deri 0.75m ² S-0.3m ²	m ⁴	9.30		

4	3.182/b	Shtrese rere natyrore t=15cm (Rere e imet per mbulim tubacioni seksioni 1T-0.4ml)	m2	209		
5	An11E(P)	Mbulim kanali me material qe sistemohet lehte S-0.09m2	m3	44.2		
6	An11E(P)	Mbulim kanali me material qe sistemohet lehte S-0.175m3	m3	5.50		
7	An12E(P)	F.V. Shirit plastik me shenimin "kabllo elektrik"	ml	522		
8	2.114/1	Beton C-16/20 per bazament e fiksim trup ndriçesi rrugor (0.175m3/cope)	m3	2.4		
9	2.114/1	Beton C-16/20 per bazament BOX-TU Nr1-Nr10, ndricim rrugor (0.16m3/cope)	m3	-		
10	2.114/1	Beton C-16/20 per mbrojtje tub plastik d-50/42mm, kalim rruge (0.22m3/cope)	m3	1		
11	An8E(P)	F.V. Rajzer zinkato per mbrojtje kabell TU+aksesore	copë	-		
12	An13E(P)	F.V. Kabell elektrik bakri FG16OR 3x1.5mm ²	ml	139.50		
13	An14E(P)	F.V. Kabell elektrik bakri FG16OR 4x1.5mm ²	ml	-		
14	An15E(P)	F.V. Kabell elektrik bakri FG16OR 2x4.0mm ²	ml	70.5		
15	An16E(P)	F.V. Kabell elektrik bakri FG16OR 2x6.0mm ²	ml	-		
16	An17E(P)	F.V. Kabell elektrik bakri FG16OR 4x4.0mm ²	ml	350		
17	An18E(P)	F.V. Kabell elektrik bakri FG16OR 4x6.0mm ²	ml	300.0		
18	An19E(P)	F.V. Kabell elektrik bakri FG16OR 4x10mm ²	ml	185.00		
19	An20E(P)	F.V. Panel elektrik metalik hermetik 60x40x100cm, per ndriçim rrugor	copë	-		
20	An21E(P)	F.V. Automat 4P/4M-20A 6kA magnetik termik	copë	-		
21	An22E(P)	F.V. Automat 1P+N/1M-20A 6kA magnetik termik	copë	3.00		
22	An23E(P)	F.V. Automat 1P+N/1M-16A 6kA magnetik termik	copë	-		
23	An24E(P)	F.V. Sinjalizues tensioni 220V-0.5W	copë	-		
24	An25E(P)	F.V. Siguresa te ndryshme 230V/1A, 2A sipas skemes	copë	-		

25	An26E(P)	F.V. Fotoelement komandim leshues 3F-20A	copë	-		
26	An27E(P)	F.V. Leshues tensioni komandim ndriçimi 3Fazor-20A	copë	-		
27	An28E(P)	F.V. Tub PVC flexibel i forte z.d D=50/42mm	ml	620.00		
28	An29E(P)	F.V. Tub PVC rigid i forte z.d D=110mm/s-2mm ne bazament betoni	ml	14		
29	An30E(P)	F.V. Shtylle metalike zinkato per ndriçues rrugor L-4.5m	copë	23.0		
1	An41E(P)	Furnizim ndriçues rrugor led 1x40w 6000° K, IP-67	copë	23.00		
30	An32E(P)	F.V. Kasete metalike IP-67 me automat 10A ne shtylle ndriçimi	copë	23.00		
31	An33E(P)	Montim ndriçues rrugor led 1x40w 6000° K, IP-67 ne shtylle 4.5m+detaj montimi	copë	23		
32	An35E(P)	F.V. Kapak metalik me mentesha 20x20cm puseta ndriçim rruge	copë	30.0		
33	An36E(P)	F.V. Kapak metalik me mentesha 40x40cm puseta ndriçim rruge	copë	3.00		
34	An37E(P)	F.V. Puntalina per percjelles 1.5, 2.5	copë	138		
35	An38E(P)	F.V. Puntalina per percjelles 4, 6, 10	copë	138.0		
		Shuma A	leke			
		B. Instalimet e sistemit rrufeprites, tokezime				
1	2.481/4	F.V. Percjelles bakri izolim PVC N07V-K 6 mm ²	ml	23.0		
2	2.480/4	F.V. Tub PVC flexibel i forte z.d D=32mm	ml	11.50		
3	2.a-73	F.V. Elektroda tokezimi 5x5x0.5 L=150	copë	23		
4	An39E(P)	F.V. Kapikorda per percjelles tokezimi Ø6	copë	46.0		
5	An40E(P)	F.V. Shkeputes per matje tokezimi panel metalik	copë	-		
		Shuma B	leke			
		C. Punime civile per shtrirje Fiber Optike per komunitetin e zones				
1	3.497/a	Germim dheu gropa per puseta betoni mes. kat III sip. ~1.5m (0.2m ³ /cope)	m ³	0.2		
2	An28E(P)	F.V. Tub PVC flexibel i forte z.d D=50/42mm	ml	510.00		

3	An12E(P)	F.V. Shirit plastik me shenimin "kablo elektrik"	ml	19		
4	2.114/1	Beton C-16/20 per pusete betoni kapak metalik 50x50x60cm (0.2m3/cope)	m3	0.2		
5	2.114/1	Beton C-16/20 per mbrojtje tub plastik d-50/42mm, kalim rruge (0.22m3/)	m3	0.5		
6	An36E(P)	F.V. Kapak metalik me mentesha 40x40cm puseta ndriçim rruge	copë	1.0		
		Shuma C				
		Shuma	5			
6	Punime per sinjalistiken					
1	An123 (M-3)	vitezimi shirit gjatesor dhe anesor me gjeresi 12 cm. Bikomponente (manta)	m	1,376.00		
2	An155 (M-3)	F V tabela rrugore te ndryshme D=90cm	cope	6.00		
		Shuma	6			
		Shuma				
		Fond Rezerve	5%			
		Shuma me Fond Rezerve				
		TVSH 20 %	20%			
		SHUMA TOTALE ME TVSH				

PREVENTIVOI
 LENI-ING shpk
 Ing.Nikoll PALUCA

