

OBJEKTI : Ndertim Rruga "Ahtisari+Vaqarr+Vllazerimi " " Bathore2**OBJEKTI : Ndertim Rruga "Ahtisari" Bathore2****(L =410 ml, B =6m, basf= 4.4m, 0.4 kunete+ trotuar 1.2m njeran ane)**

A	An.	Emertimi i Punimeve	Njesia	Sasia
I	PUNIME NE RRUGE			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	180.4
2	3.158/5a	Transport dheu me auto 5km	m ³	180.4
3	An. 8	Mbushje me çakell shkembor	m ³	180.4
4	3.211	Shtrese çakelli T=20cm	m ²	1804
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1804
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1804
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1804
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	139.4
9	2.167	F V hekur betoni periodik Ø > 10 mm	ton	4
10	An.	Spostim shtyllash	cope	3
11	2/426/2	Prishje mure me blloqe + transport	m ³	328
12	An.152	Vizime me boje bikomponente 15cm(per kembesoret bardhe + kuq)	ml	860
13	An.96	Tabele sinjalistike 60-90cm	cope	2
SHUMA I				
II	PUNIME NE KUN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	246
2	3.158/5a	Transport çakelli me auto 5km	m ³	246
3	3 An. 8	Mbushje me çakell shkembor	m ³	201.1
4	3.158/5a	Transport çakelli me auto 5km	m ³	201.1
5	3.An/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	404
6	An /20 Man 2	Pusete Shkarkimi b/a 80x80 cm , h deri 1.5 m me kapak gize	cope	8
SHUMA II				
III	PUNIME NE KUB			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	143.5
2	3.158/5a	Transport çakelli me auto 5km	m ³	143.5
3	3 An. 8	Mbushje me çakell shkembor	m ³	100.7
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	402
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	13
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	14
SHUMA III				
III	PUNIME TROTUAR NJERA ANE(1x1.2 m)			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	49.2
2	3.158/5a	Transport dheu me auto 5km	m ³	49.2
3	3 An. 8	Mbushje me çakell shkembor	m ³	49.2
4	3.208	Shtrese çakelli T=10cm	m ²	348.5
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	348.5
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	410
7	2/262/4	Beton per fiksime bordure C16/20	m ³	12.3
8	2.109/2	Shtrese betoni trotuari	m ³	10.85
SHUMA IV				
IV	PUNIME PER NDRICIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	410
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	410
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	12

DITE PUNE120

4	3.139	Germime dheu me ekskavator me goma	m ³	82
5	3.158/5a	Transport dheu me auto 5km	m ³	82
6	2.261	Mbushje me rere	m ³	49.2
7	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	32.8
SHUMA IV				
V PUNIME PER GJELBERIMIN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	An	F.V. Bordura betoni 0.6 x 0.2 x 0.8 ml	ml	143.5
SHUMA V				
SHUMA A				
OBJEKTI : Ndertim Rruga "L1Vaqarr + L2+L3pingulet me Vaqarrin" Bathore4				
(L1 =200 ml, B =7m, basf= 4.2m 0.4*2kunete , trotuar 1m dy anet)				
(L2+L3 =120 ml +265ml, B=6m, basf= 5m, 0.5m bankine ne dy anet)				
B	An.	Emertimi i Punimeve	Njesia	Sasia
I PUNIME NE RRUGE - L1				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	84
2	3.158/5a	Transport dheu me auto 5km	m ³	84
3	An. 8	Mbushje me çakell shkembor	m ³	84
4	3.211	Shtrese çakelli T=20cm	m ²	840
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	840
6	3.222/2	Shtrese binderi 1x6 cm	m ²	840
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	840
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	88
9	2.167	F V hekur betoni periodik Ø > 10 mm	ton	3.08
10	An.	Spostim shtyllash	cope	4
11	2/426/2	Prishje mure me blloqe + transport	m ³	160
12	An.152	Vizime me boje bikomponente 15cm(per kembesoret bardhe + kuq)	ml	440
13	An.96	Tabele sinjalistike 60-90cm	cope	2
SHUMA I				
II PUNIME NE KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	128
2	3.158/5a	Transport çakelli me auto 5km	m ³	128
3	3 An. 8	Mbushje me çakell shkembor	m ³	112
4	3.158/5a	Transport çakelli me auto 5km	m ³	112
5	3.An/1t	F.V. tuba te Brinjezuar SN-8 d=400 mm (perfshire reren per mbrojtjen e tubit)	ml	197
6	An /20 Man 2	Pusete Shkarkimi b/a 80x80 cm , h deri 1.5 m me kapak gize	cope	4
SHUMA II				
III PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	67.2
2	3.158/5a	Transport çakelli me auto 5km	m ³	67.2
3	3 An. 8	Mbushje me çakell shkembor	m ³	25
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	392
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	15.8
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	13
SHUMA III				
III PUNIME TROTUAR DY ANET(1 m)				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	32
2	3.158/5a	Transport dheu me auto 5km	m ³	32
3	3 An. 8	Mbushje me çakell shkembor	m ³	32
4	3.208	Shtrese çakelli T=10cm	m ²	260
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	260

6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	400
7	2/262/4	Beton per fiksime bordure C16/20	m ³	12
8	2.109/2	Shtrese betoni trotuari	m ³	26
SHUMA IV				
IV	PUNIME PER NDRICIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	400
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	400
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	6
4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1
5	3.139	Germime dheu me ekskavator me goma	m ³	80
6	3.158/5a	Transport dheu me auto 5km	m ³	80
7	2.261	Mbushje me rere	m ³	60
8	Man3An. 8	Mbushje me cakull shkembor (kanal)	m ³	20
SHUMA V				
V	PUNIME PER GJELBERIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	An	F.V. Bordura betoni 0.6 x 0.2 x 0.8 ml	ml	70

RRUGET PINGUL ME VAQARRIN (L2+L3 =120 ml +265ml, B=6m, basf= 5m, 0.5

An.	Emertimi i Punimeve		Njesia	Sasia
PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	231
2	3.158/5a	Transport dheu me auto 5km	m ³	231
3	An. 8	Mbushje me çakell shkembor	m ³	231
4	3.211	Shtrese çakelli T=20cm+bankine	m ²	2310
5	3.212/b	Shtrese stabilizanti t=10cm+bankine	m ²	2310
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1925
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1925
8	An.	Spostim shtyllash	cope	2
9	An.152	Vizime me boje bikomponente 15cm(per kembesoret bardhe + kuq)	ml	820
10	An.96	Tabele sinjalistike 60-90cm	cope	2
SHUMA I				
SHUMA B				

OBJEKTI : Ndertim Rruga " Vllazerrimi " Bathore 1 , Bashkia Kamez

C	An.	Emertimi i Punimeve	Njesia	Sasia
I	PUNIME NE RRUGE			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	360
2	3.158/5a	Transport dheu me auto 5km	m ³	360
3	An. 8	Mbushje me çakell shkembor	m ³	198
4	3.211	Shtrese çakelli T=20cm	m ²	1800
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1800
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1800
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1800
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	144.00
9	3.288	F.V Hekur betoni i zakonshem O > 10 mm	ton	3.60
10	An.	Ngritje pusete+kapak gize	cope	7
11	An.	Spostim shtyllash	cope	10.00
12	2/426/2	Prishje mure me blloqe + transport	m ³	240
13	An.152	Vizime me boje bikomponente 15cm (per kembesoret bardhe + kuq)	ml	1200
14	An.96	Tabele sinjalistike 60-90cm	cope	4

SHUMA I				
II PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	160
2	3.158/5a	Transport çakelli me auto 5km	m ³	160
3	3 An. 8	Mbushje me çakell shkembor	m ³	80
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	400
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	20
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	11.43
SHUMA II				
II PUNIME KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	260.0
2	3.158/5a	Transport çakelli me auto 5km	m ³	260
3	3 An. 8	Mbushje me çakell shkembor	m ³	130
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	400
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	5.00
SHUMA II				
III PUNIME TROTUARE(2x0.75 m)				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	70.00
2	3.158/5a	Transport dheu me auto 5km	m ³	70.00
3	3 An. 8	Mbushje me çakell shkembor	m ³	105.00
4	3.208	Shtrese çakelli T=10cm	m ²	700.00
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	700.00
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	800
7	2/262/4	Beton per fiksime bordure C16/20	m ³	24
8	2.109/2	Shtrese betoni trotuari	m ³	70
SHUMA III				
6. PUNIME VEPRAT ARTI (MURE MBAJTESE)				
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	80
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	80
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	115
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.46
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.7
SHUMA 6				
IV PUNIME PER NDRICIMIN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	400
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	400
3	An	F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A	cope	1
4	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	11
5	3.139	Germime dheu me ekskavator me goma	m ³	80
6	3.158/5a	Transport dheu me auto 5km	m ³	80
7	2.261	Mbushje me rere	m ³	32
8	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	48.165
SHUMA IV				
V PUNIME PER GJELBERIMIN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	An	F.V. Bordura betoni 0.6 x 0.2 x 0.8 ml	ml	189.0

Preventivues:

Ing. Eglantina Disha