



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI : Ndertim Rruga "Pjeshkore Velipoje + rrugicat" Valias + Sistemim Asfaltim i Rruges "Ballshi "Valias + Rruga "Pingul me Hekuran Deden" Laknas				
OBJEKTI : Ndertim Rruga "Pjeshkore Velipoje + rrugicat" Valias				
(L_{Tot} =170+325+210 ml=705ml, B =7m, basf= 4.2m 0.4kunete dy ane, trotuar 1m dy anet)				
A	An.	Emertimi i Punimeve	Njesia	Sasia
I	PUNIME NE RRUGE - L1			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	296.1
2	3.158/5a	Transport dheu me auto 5km	m ³	296.1
3	3.164/1b	Mbushje me çakell shkembor	m ³	296.1
4	3.211	Shtrese çakelli T=20cm	m ²	2961
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2961
6	3.222/1	Shtrese binderi 1x5 cm	m ²	2961
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri + 3 rampa per ngadalesim	m ²	2961
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	128
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	9.6
10	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	4
11	2.426/2	Prishje mur blloqe betoni	m ³	320
12	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesor + aksi+vije zime kembesoret	ml	1450
13	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	6
		SHUMA I		
II	PUNIME NE KUB			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	338.4
2	3.158/5a	Transport dheu me auto 5km	m ³	338.4
3	3.396	Mbushje me cakell pas mureve	m ³	191
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	1020
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	45.1
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	47
		SHUMA II		
III	PUNIME TROTUAR DY ANET(1 x1 m)			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	112.8
2	3.158/5a	Transport dheu me auto 5km	m ³	112.8
3	3.164/1b	Mbushje me çakell shkembor	m ³	112.8
4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	1128
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	1128
6	3.616/9	FV Bordura betoni 15x25 cm	ml	1410
7	2.262/4	Beton per fiksime bordure C16/20	m ³	42.3
8	2.262/4	Shtrese betoni C16/20 (trotuari)	m ³	141
		SHUMA III		
IV	PUNIME PER NDRICIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	1410
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	1410

94 DITE PUNE

3	3.17	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	23
4	3.139	Germim dheu me eskavator	m ³	493.5
5	3.158/5a	Transport dheu me auto 5km	m ³	493.5
6	2.261	Mbushje me rere	m ³	211.5
7	3.353	Mbushje me shkemb te germuar me pare	m ³	282
		SHUMA IV		
V		PUNIME PER GJELBERIMIN		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
<u>1</u>	3.619/a	FV Bordura betoni 6x20 cm	ml	82
		SHUMA V		
		SHUMA I-IV		

OBJEKTI : Sistemim Asfaltim i Rruges "Ballshi "Valias , Ltot= 610 ml

(L = 610 ml, B =9m, basf= 5m, bankine 2x1 + kanal I mbuluar 4 m)

B	An.	Emertimi i Punimeve	Njesia	Sasia
I		PUNIME NE RRUGE		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	854
2	3.158/5a	Transport dheu me auto 5km	m ³	854
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	915
4	3.211	Shtrese çakelli T=20cm	m ²	3050
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	3050
6	3.222/1	Shtrese binderi 1x5 cm	m ²	3050
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	3050
8	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	5
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	2
10	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesor + aksi+vije zime kembesoret	ml	1220
11	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	4
		SHUMA A		
II		PUNIME NE KUZ		

PUNIME K.U.Z. AksiRruges Ballshi DN 315,& 600

I	An.	Emertimi i Punimeve	Njesia	Sasia
1	2.426/5	Prishje mure betoni	m ³	12
2	3.405/1	Prishje struktura prej betoni (soletat ekzistuese ne rruget e intersektimit)	m ³	38
3	2.88	Mur me blloqe betoni 20cm, deri - 3m, me LL.P. M-15	m ³	12
4	3.139	Germim dheu me eskavator	m ³	3,000
5	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke zak (mbushje me material të selektuar nga gërmimi për tubat e betonit KUZ)	m ³	1,350
6	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	1,650
7	3.164/1t	F.V. tuba te brinjezuar HDPE SN8 d=315 mm	ml	168
10	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	600
11	2.575	Puse kontrolli 1x1x1.5m	cope	13
		SHUMA B		
		SHUMA B		

OBJEKTI : Ndertim Rruga "Pingul me Hekuran Deden" Laknas , Bashkia Kamez

C	An.	Emertimi i Punimeve	Njesia	Sasia
I		PUNIME NE RRUGE		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	180.0
2	3.158/5a	Transport dheu me auto 5km	m ³	180.0
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	93.0
4	3.211	Shtrese çakelli T=20cm	m ²	1200
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1200
6	3.222/1	Shtrese binderi 1x5 cm	m ²	1200
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm	m ²	1200
8	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	2

9	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesor + aksi+vije zime kembesoret	ml	680	
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	4	

Preventivues :

Ing. Eglantina DISHA