

MIRATOI
BASHKIA KLOS
Zj. VALBONA KOLA
KRYETARE

PREVENTIV I PUNIMEVE						
EMRI I PROJEKTIT: "NDËRTIM BOX BETONARME - FSHATI GURRË E MADHE, LAGJA MUSLELA"						
Nr.	An. No.	Pershkrimi i zerit	Njesi	Sasia	Çmimi	Shuma
KATEGORIA 1: PUNIME DHERASH DHE PRISHJE						
1	3.2	Prerje bime te vogla ø-10cm	m ²	350.00		
2	3.110/b	Germim dheu me ekskavator zingjir, 1.0 m ³ , toke zak, kategoria IV, me shk ne mjet	m ³	44.80		
3	3.128/b	Germim shkemb i coptuar me ekskavator 1.0 m ³ , shkemb, ne themele gjeresi >2 m, me shkarkim ne mjet	m ³	38.40		
4	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	418.00		
5	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	83.20		
		SHUMA 1				
KATEGORIA 2 : VEPRAT E ARTIT						
		Box Beton/Arme 4.00x2.00 m				
1	3.396/1	Mbushje me zhavorr (nenshtrese)	m ³	100.00		
2	3.240	Struktura monolite betoni C 12/15, per nenshtrese	m ³	2.60		
3	3.245	Struktura monolite betoni C 25/30, per tombinot katrore	m ³	12.20		
4	3.245	Struktura monolite betoni C 25/30, per anet e BOX-it	m ³	27.20		
5	3.245	Struktura monolite betoni C 25/30, per Bordurat	m ³	3.30		
6	3.289	F V hekur betoni Ç-5 Ø > 12mm	ton	2.78		
7	3.624	H / Izolim me emulsion, 2 duar bitum	m ²	52.00		
		Mure gabioni				
1	3.104/a	Germim dheu me ekskavator zingjir 0.5 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria IV, me shk ne mjet	m ³	23.10		
2	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1 m	m ³	30.00		
3	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	23.10		
		SHUMA 2				
		SHUMA 1+2				
		Fond Rezerve 5%	5%			
		SHUMA PA TVSH				
		T V S H 20%	20%			
		SHUMA TOTALE				

Hartoi
"ERALD-G" sh.p.k

Perfaqeues
Ing. Gezim Islami