

Preventivi pa cmime

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSIA	SASIA	VLEFTA PA TVSH
1	3.607	Çmotim shtylla ekzistuese (perfshi linjen)	cp	10	
2	3.158/5a	Transport dheu me auto deri 5.0 km	m³	6	
3	3.2	Prerje bime te vogla ø ~ 10cm	m2	5049	
4	2.181	F.V. Konstruksiione metalike te perbera	ton	1	
5	3.104/a	Germim dheu me ekskavator 0.5 m³,b > 2 m, toke zak, kategoria IV, me shk ne mjet	m³	12243	
6	3.164/1b	Mbushje me cakell e gur gurore,perhapur e ngjeshur me makineri ne shtresa cdo 20 cm	m³	4897	
7	3.158/5a	Transport dheu me auto deri 5.0 km	m³	12243	
8	3.211	Shtrese çakelli mbeturine kave t=1x20cm, perhapur e ngjeshur makineri	m²	20766	
9	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur me makineri	m2	20766	
10	3.212/c	Shtrese stabilizant t=15cm	m²	20766	
11	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m²	17704	
12	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m²	17704	

13	3.212/b	Shtrese stabilizant t=10cm (Bankine)	m ²	2712	
14	3.104/a	kanale gjeresi deri 2 m, prani uji ~ 2m kategoria IV, me shk ne toke per kanal dhe tubacion	m ³	2557	
15	3.164/2t	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	34	
16	3.164/3t	F V tuba te brinjezuar HDPE SN8 d=500 mm	ml	129	
17	3.164/4t	F V tuba te brinjezuar HDPE SN8 d=600 mm	ml	15	
18	3.164/5t	F V tuba te brinjezuar HDPE SN8 d=800 mm	ml	144	
19	3.164/6t	F V tuba te brinjezuar HDPE SN8 d=1000 mm	ml	64	
20	An	F V tuba te brinjezuar HDPE SN8 d=1200 mm	ml	24	
21	3.369	Tombino me tuba betoni Ø 1500, mbi shtrese betoni	ml	18	
22	3.243	Struktura monolite betoni C 16/20 (per tombino)	m ³	193	
23	2.261	Mbushje me material te germuar	m ³	850	
24	3.396/1	Mbushje me zhavorr pas mureve	m ³	433	
25	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	2	
26	3.244/1	Struktura monolite betoni C 20/25 per veshje kanali (20/25)	m ³	754	

27	3.396/1	Mbushje me zhavorr pas mureve	m ³	2541	
28	3.183/b	Shtrese zhavor lumi t=15cm (shtresa posht kanaleve te betonit)	m ²	1659	
29	3.633	Fugature llac cimento M - 50, t=0.05 cdo 3ml	m ²	855	
30	3.164/1b	ngjeshur me makineri ne shtresa cdo 20 cm (per kanalet e dheut)	m ³	2557	
31	3.244	Struktura monolite betoni C 20/25 kuneta + bordure monolite	m ³	28	
32	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	2557	
33	3.104/b	Germim dheu me ekskavator 0.5 m ³ , b > 2 m, toke zak, kategoria IV, me shk ne mjet per muret	m ³	81	
34	3.396/1	Mbushje me zhavorr pas mureve	m ³	26	
35	3.244	Struktura monolite betoni C 20/25 per muret	m ³	328	
36	2.52	Tub per drenazh pvc Ø 110 mm	ml	10	
37	2.166/1a	F.V. Hekur betoni periodik Ø > 12 mm	ton	1	
38	3.843/3	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm. Termoplastike (sprajt)	ml	9044	
39	3.943/3	Vizime me boje bikomponente (vijzime kembesoresh, shigjeta drejtimi etj)	m ²	31	
40	3.922	Tabele drejtkëndore (tregimi)(AxB) e zvogëluar 40x60 (shenja ure)	cope	2	

41	3.933/1	Tabela terekendore normal me A-B, 90-30 (STOP)	cope	5	
42	3.952	F V tabela rrugore te ndryshme D=90cm	cope	6	
43	3.933	Tabela trekendore e vogel me A = 60	cope	1	
Shuma Analiza					167,403,149
Fondi Rezervë (5.0%)					8,370,157
Shuma Analiza + Fondi Rezervë (5.0%)					175,773,307
Shuma TVSH (20%)					35,154,661
Shuma me TVSH					210,927,968