

## PREVENTIV ZBATIMI

### OBJEKTI:

PROJEKT ZBATIMI SISTEMIM ASFALTIM I RRUGES BLLACES LOTI I PARE , BASHKIA BULQIZE

BASHKIA BULQIZE

Gjatesia L =3576 ml

| Nr.      | Nr. Analize | Emertimi i punimeve  | Njesia         | Sasia  | Cmimi | Vlera |
|----------|-------------|--|----------------|--------|-------|-------|
| <b>1</b> |             | <b>PUNIME NE RRUGE</b>   |                |        |       |       |
| 1        | 3.2         | Prerje bime te vogla deri $\Phi$ 10cm,L=1475m,B=10m  | m <sup>2</sup> | 112    |       | -     |
| 2        | 3.160/a     | Germim e transport dheu kat III-te me skreper, L=100m dhe V=6~6.5m <sup>3</sup>  | m <sup>3</sup> | 1,356  |       | -     |
| 3        | 3.87/a      | Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet | m <sup>3</sup> | 230    |       | -     |
| 4        | An.P1       | Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri                                       | m <sup>3</sup> | 230    |       | -     |
|          |             | <b>Shuma 1</b>   |                |        |       | -     |
| <b>2</b> |             | <b>PUNIME SHTRESASH NE RRUGE</b>   |                |        |       |       |
| 1        | Anp2        | Mbushje me cakell t = 10 cm  | m <sup>3</sup> | 1,252  |       | -     |
| 2        | Anp3        | Shtrese me material rrethanor per bankine t=20cm   | m <sup>3</sup> | 1,068  |       | -     |
| 3        | Anp4        | Shtrese stabilizant t=10cm   | m <sup>2</sup> | 12,516 |       | -     |
| 4        | Anp5        | Shtrese binderi me zall lavatrice,5cm,me makineri  | m <sup>2</sup> | 12,516 |       | -     |
| 5        | An P 6      | Shtrese asfaltbetoni me zall lavatrice,4cm,me makineri   | m <sup>2</sup> | 12,516 |       | -     |
| 6        | An124       | Vijejim shirita gjatesor dhe anesor me gjeresi 12 cm, Akrelike   | ml             | 3,560  |       | -     |
| 7        | An155       | F V tabela rrugore te ndryshme D=90cm  | cope           | 4      |       | -     |
|          |             | <b>Shuma 2</b>   |                |        |       | -     |
| <b>3</b> |             | <b>PUNIMET E VEPRAVE TE ARTIT</b>  |                |        |       |       |
| <b>A</b> |             | <b>Kalim me tub celiku <math>\Phi</math> 355/3.6mm</b>   |                |        |       |       |
| 1        | 3.139       | Germim dheu me ekskavator goma 0.35~0.40m <sup>3</sup> , ne themele, toke zak, kat III, me shkarkim ne toke              | m <sup>3</sup> | 8      |       | -     |
| 2        | 3.243       | Struktura monolite betoni C 16/20 (Beton per Hyrje dalje tub celiku)   | m <sup>3</sup> | 1.2    |       | -     |
| 3        | 2.a60/1     | F.V. Tub celiku $\Phi$ 355.2/3.6 mm (P.s=31.251 kg/ml),L=30 m  | kg             | 938    |       | -     |
| 4        | An-8        | Mbushje me cakell  | m <sup>3</sup> | 1      |       | -     |
| 5        | An3         | Guardrail- N2 anesore me 2 valez. ne 1 ane , W4 + aksesoret  | ml             | 88     |       | -     |
|          |             | <b>Shuma A</b>   |                |        |       | -     |
| <b>B</b> |             | <b>Tombino betoni <math>\Phi</math> 600mm</b>  |                |        |       |       |
| 1        | 3.139       | Germim dheu me ekskavator goma 0.35~0.40m <sup>3</sup> , ne themele, toke zak, kat III, me shkarkim ne toke              | m <sup>3</sup> | 18     |       | -     |
| 2        | 3.243       | Struktura monolite betoni C 16/20 ( per pusete )   | m <sup>3</sup> | 3      |       | -     |
| 3        | 3.237       | Struktura monolite b/betoni C 12/15 me 20% gur ( per portal)   | m <sup>3</sup> | 2      |       | -     |
| 4        | 3.365       | Tombino me tuba betoni $\Phi$ 600, mbi shtrese betoni  | ml             | 7      |       | -     |
| 5        | An-8        | Mbushje me cakell  | m <sup>3</sup> | 3.436  |       | -     |
|          |             | <b>Shuma 1 Cope</b>  |                |        |       | -     |
|          |             | <b>Shuma B</b>   |                |        |       | -     |
|          |             | <b>1 Cope</b>  |                |        |       | -     |
| <b>G</b> |             | <b>Ndertim Mure Butobetoni C 12/15 20% gur</b>   |                |        |       |       |
| 1        | 3.139       | Germim dheu me ekskavator goma 0.35~0.40m <sup>3</sup> , ne themele, toke zak, kat III, me shkarkim ne toke              | m <sup>3</sup> | 75     |       | -     |
| 2        | An.P1       | Mbushje me material te germuar me pare   | m <sup>3</sup> | 27.0   |       | -     |
| 3        | 3.237       | Struktura monolite b/betoni C 12/15 me 20% gur   | m <sup>3</sup> | 58     |       | -     |
| 4        | 2.258       | Nenshtrese zhavori   | m <sup>3</sup> | 5.89   |       | -     |
|          |             | <b>Shuma G</b>   |                |        |       | -     |
|          |             | <b>Shuma 3 (A-G)</b>   |                |        |       | -     |
|          |             | <b>Shuma 1 deri 3</b>  |                |        |       | -     |
| <b>E</b> |             | <b>Tombino betoni <math>\Phi</math> 1500mm</b>   |                |        |       |       |
| 1        | 3.139       | Germim dheu me ekskavator goma 0.35~0.40m <sup>3</sup> , ne themele, toke zak, kat III, me shkarkim ne toke              | m <sup>3</sup> | 36     |       | -     |
| 2        | 3.243       | Struktura monolite betoni C 16/20 (Beton per portale)  | m <sup>3</sup> | 12.0   |       | -     |

|   |       |  |                     |      |  |   |
|---|-------|--|---------------------|------|--|---|
| 3 | 3.369 | Tombino me tuba betoni Ø 1500 , mbi shtrese betoni                                 | ml                  | 6    |  | - |
| 4 | An-8  | Mbushje me cakell  | m <sup>3</sup>      | 42.0 |  | - |
| 5 | An.P1 | Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri | m <sup>3</sup>      | 65.0 |  | - |
|   |       |  | <b>Shuma 1 Cope</b> |      |  | - |
|   |       |  | <b>SHUMA</b>        |      |  | - |
|   |       |  | T.V.SH              | 20%  |  | - |
|   |       |  | <b>SHUMA TOTALE</b> |      |  | - |

V.O . Cmimet jane bere ne baze te vkm 619 date 15.07.2015

**PREVENTIVUES:**  
**Ing.Hajredin MURGU**