



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI : Rikonstruksion Rruga Shkendija , Laknas , Njesia Administrative Vallias , Bashkia Kamez

(L=1450 ml, L1=1000m, B1=11 m, basf= 5 m, 2x0.5 kunete, Trot.=2.5 m,), L2=450 m, B2=6 m, basf=4 m +
0.5kub+trot 1.5 m)

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	450		
2	3.158/5a	Transport dheu me auto 5km	m ³	450		
	3an43	Skarifikim asfalti	m ²	5000		
3	Man 3 An. 8	Mbushje me çakell shkembor	m ³	405		
4	3.211	Shtrese çakelli T=20cm	m ²	2800		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	6800		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	6800		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	6800		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	99		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	4.455		
10	An.	Ngritje pusete+kapak gize	cope	15		
11	An.152	Vizime me boje bikomponente 15cm (bardhe+kuq)	ml	4600		
12	An.96	Tabele sinjalistike 60-90cm	cope	20		
SHUMA I						
II						
PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	563.5		
2	3.158/5a	Transport çakelli me auto 5km	m ³	563.5		
3	Man 3 An. 8	Mbushje me çakell shkembor	m ³	193.2		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	1950		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	122.5		
6	2.An.23+an	Puseta shiu me zgare 40x60 + kapak gize	cope	65		
SHUMA II						
III						
PUNIME TROTUARE(1*2.5m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	152		
2	3.158/5a	Transport dheu me auto 5km	m ³	152		
3	Man 3 An. 8	Mbushje me çakell shkembor t=10 cm	m ³	687.5		
4	3.208	Shtrese çakelli T=10cm	m ²	2717.5		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	2717.5		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25cm	ml	2900		
7	2/262/4	Beton per fiksion bordure C16/20	m ³	87		
8	3.605	Shtrese pllake t=6cm mbi shtrese betoni(30x30,15x15)	m ²	2577.5		
SHUMA III						
IV						
PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	1450		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	1450		
3	An-22/1	F.v puseta betoni me kapak gize 40x40 h=100cm	cope	42		
4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	4		

5	3.139	Germime dheu me ekskavator me goma	m ³	174	
6	3.158/5a	Transport dheu me auto 5km	m ³	174	
7	2.261	Mbushje me rere	m ³	130.5	
8	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	87	
SHUMA IV					
PUNIME PER GJELBERIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	An	F.V. Bordura betoni 0.6 x 0.2 x 0.8 ml	ml	87	
SHUMA V					
SHUMA A					
TVSH 20%					
TVSH TOTALE					

Preventivues:

Ing. Eglantina Disha



Drejtori i Pergjithshem

Z.Elvis Gjika



Drejtori P.I-se

Ing. Flora MUÇA



**MIRATOI
Rakip SULI**



KRYETAR