

Miratohet
Kryetari
Jorgo Goro

PREVENTIVI PUNIMEVE (MEMEC)
Objekti: "Rikonstruksioni segmenteve rrugore rurale Borsh Kuç"

Nr.	Nr. An.	Emertimi punimeve	Njesia	Sasia	Cmimi	Vlera
1	3.1	Skarifikim bari me lopate	m2	627	10	6,270
2	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	1,193	312	372,216
3	3.44/1	Germim kanalesh ne toke te bute, me krahe, me seksion deri 0.75 m ²	m3	230	723	166,290
4	3.48/b	Rrafshim skarpatesh, me krahe, ne germim toke te zakonshme	m2	522	77	40,194
5	3.323	Mur guri mbajtes e themele, llaç çimento M50	m3	198	4,901	970,398
6	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur makineri	m2	7,600	742	5,641,099
		Shuma	Leke			7,196,467
		TVSH	Leke	20%		1,439,293
		SHUMA TOTALE	Leke			8,635,760

Preventivuesi
K&F Consulting shpk
Ing.Bexhet Çobani