



## BASHKIA KAMEZ

Nr \_\_\_\_\_ Prot.

Kamez me \_\_\_\_/\_\_\_\_/2018

## PREVENTIV

**NDERTIM RRUGET : SADO KOSHENKO + Rruga Segment Lidhese Kaci me Rrugen Sali Vranishti**

**OBJEKTI : Segmenti lidhes rruga " Kaci " me " Sali Vranishti "**

**( L = 186 m, B = 5.5 m, b = 5 m, )**

Nr	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
<b>I PUNIME NE RRUGE</b>						
1	3/139	Germim dheu me eskavator me goma	m <sup>3</sup>	594		0
2	3/158/5a	Transport me auto 5 km	m <sup>3</sup>	594		0
3	3/353	Mbushje me çakull per kasonete ( t=35 cm )	m <sup>3</sup>	399.036		0
4	3/158/5a	Transport me auto 5 km	m <sup>3</sup>	399.035		0
5	3/208	Shtese cakulli T=10 cm	m <sup>2</sup>	930		0
6	3/212/b	Shtese stabilizanti T=10 cm	m <sup>2</sup>	930		0
7	3/229/1	Shtese binder T=5 cm	m <sup>2</sup>	840		0
8	3/231/3	Shtese asfalt T=4 cm	m <sup>2</sup>	840		0
9	3/352	Shtrese me gure kave T=30cm	m <sup>3</sup>	193		0
10	3/139	Germim dheu me eskavator per KUN	m <sup>3</sup>	186		0
11	3/158/5a	Transport me auto 5 km	m <sup>3</sup>	186		0
12	3/353	Mbushje me çakull	m <sup>3</sup>	189		0
13	3/An/2	Puste per mbledhjen e ujrave 2.5 x 2.5 m	cope	1		0
14	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	140		0
15	3.363	F.V Tube betoni Ø400	ml	52		0
16	3.617.1	F.V. bordure 15x30 cm	ml	360		0
17	2.262.4	Shtrese betoni per kunete	m <sup>3</sup>	9.3		0
18	2/262/4	Beton per fiksime bordure	m <sup>3</sup>	10.8		0
19	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	60		0
20	2.575	Puse kontrolli 1x1x1.5m	cope	4		0
		SHUMA				0
		<b>TOTAL</b>				<b>0</b>

**OBJEKTI : Rruga "Sado Kosheho"**

**( L = 536 m, B = 6 m, b = 4 m, bankin 1+1 m )**

Nr	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
<b>I PUNIME NE RRUGE</b>						
1	3/139	Germim dheu me eskavator me goma	m <sup>3</sup>	482		0
2	3/158/5a	Transport me auto 5 km	m <sup>3</sup>	482		0
3	3/353	Mbushje me çakull	m <sup>3</sup>	562		0
4	3/158/5a	Transport me auto 5 km	m <sup>3</sup>	562		0
5	3/208	Shtese cakulli T=10 cm	m <sup>2</sup>	2680		0
6	3/212/b	Shtese stabilizanti T=5cm	m <sup>2</sup>	2144		0
7	3/229/1	Shtese binder T=5 cm	m <sup>2</sup>	2144		0
8	3/231/3	Shtese asfalt T=4 cm	m <sup>2</sup>	2144		0
9	2/426/2	Prishje muri me blloqe	m <sup>3</sup>	53		0
				<b>Shuma 1</b>		<b>0</b>
<b>Punime KUN</b>						
1	3.87/a	Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke		772		0
2	3/158/5a	Transport me auto 5 km	m <sup>3</sup>	772		0

3	3/353	Mbushje me çakull	m <sup>3</sup>	460	0
4	3/158/5a	Transport me auto 5 km	m <sup>3</sup>	460	0
5	3.364	Tombino me tuba betoni Ø 500, mbi shtrese betoni	m	445	0
6	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	60	0
7	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	m	12	0
8	2.575	Puse kontrolli 1x1x1.5m	cope	11	0
				<b>Shuma 2</b>	<b>0</b>
<b>SHUMA</b>					<b>0</b>
Shuma 1+ 2					0
T.V.SH 20%					0
<b>TOTAL</b>					<b>0</b>

Shenim : Hartuar ne baze te VKM nr. 629 dt 15.07.2015

**Drejtori D.P.K.ZH.T**

Ark. Arber TOLA

**Preventivues:**

Ing. Hajredin MURGU

Ing. Flora MUÇA

Ing. Elmaz MURATI

**MIRATOI**

**Xhelal MZIU**

**KRYETAR**



#REF!

