



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ

Nr. Prot.

Kamez me / /2018

PREVENTIV

Objekti : Ndertim Rruga " Ibrahim Rugova " Paskuqan 1 , Bashkia Kamez

Nr.	Nr.An.	Emërtimi i procesit të punës	Njësia	Sasia	Çmimi	Vlera - leke
Ndertim Rruga Ibrahim Rugova " Paskuqan1, L= 956 m B= 7.20 m (basft= 4.5 + kunete 1x0.5 m trotuare2x1.0 m)						
Nr	nr.anal	EMERTIMI	njesia	Sasia	Çmimi	Vlera - leke
I. Punime ne rrugen , degezime B= 7.2 m L= 956 m						
B= 7.2 m (basl=4.5 +kunete 1x0.5+Trotuare2x1.0m)						
1	3.An-49	Thyerje betoni t=10 cm	m ³	65.0		-
2	2.426/2	Prishje mure ekzistuese me blloqe	m ³	242.0		-
3	3.114/b	Germim dheu ne trupin e rruges	m ³	669		-
4	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	772		-
5	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	5,258		-
6	3.187	Shtrese stabilizanti 10 cm	m ²	4,302		-
7	3.229/1	Shtrese binderi 5cm + Sperkatje me emulsion	m ²	4,302		-
8	3.226/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	4,302		-
9	3.617/1	F.V bordura betoni 15x30 cm	ml	1,912		0
10	3.183/a	Shtrese zhavor lumi, nen themelin e bordures, t=10cm	m ²	573		0
11	2.262/3	Struktura monolite betoni, C 12/15,+ kundrabortura (10x40)	m ³	76		0
12	2.262/4	Beton C 16/20 per kunete	m ³	60.6		-
13	3.158/5a	Transport dherash me auto 5 km	m ³	669.0		-
14	anal	Heqje dhe Montim Shtylla Elektrike (Kablo+ tela)	cope	19.0		-
15	An96	Tabela normal me A-B, 60-90	cope	4.0		-
Shuma II						0
II. Ndertim Trotuari te Rrugës						
1	3.87/a	Germim dheu per themel te bordures kufizuese te trotuarit	m ³	98		-
2	3.158/5a	Transport dherash me auto 5 km	m ³	98		-
3	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	152		-
Shuma V						0
III Punime per K.U.N , KUB						
1	3.87/a	Germim dheu kanal me makineri	m ³	680		-
2	3.183/c	Mbushje me çakull nen e mbi tuba	m ³	450.00		-
3	3.158/5a	Transport dherash teprice me auto 5 km	m ³	680		-
4	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm per gjithe rrugen ne totale	ml	1,120		-
5	An - 22	Pusetë b/a shiu 40 x 40 cm, h = 100 cm, me kapak zgare hekuri	cope	54		-
6	Analize	Ngritje pusetash ekzistuese	cope	12		-
Shuma VI						0
Shuma (I+ II+ III)						0

Objekti :Ndertim Rruga Mark Tirta +Rr. Mbreti Gent + Rr Medi Frasheri Paskuqan 1, Koder e kuqe , Bashkia Kamez

Nr.	Nr.An.	Emërtimi i procesit të punës	Njësia	Sasia	Çmimi	Vlera - leke
Nr	nr.anal	EMERTIMI	njesia	Sasia	Çmimi	Vlera - leke
I. Punime ne rrugen , degezime B=7.2m Lt=780 m						
L 1 = 150 m , B= 7.2 m (basl= 5 + kunete 1x0.5 + bankine 2x 0.75m)						
1	3.An-49	Thyerje betoni t=10 cm	m ³	2.0		-
2	2.426/2	Prishje mure ekzistuese me blloqe	m ³	10.0		-
3	3.114/b	Germim dheu ne trupin e rruges	m ³	200		-
4	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	260		-
5	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	825		-
6	3.187	Shtrese stabilizanti 10 cm	m ²	750		-
7	3.229/1	Shtrese binderi 5cm + Sperkatje me emulsion	m ²	750		-

8	3.226/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	750		-
9	3.617/1	F.V bordura betoni 15x30 cm	ml	300		0
10	3.183/a	Shtrese zhavor lumi, nen themelin e bordures, t=10cm	m ²	90		0
11	2.262/3	Struktura monolite betoni, C 12/15,+ kundrabordura (10x40)	m ³	25		0
13	3.158/5a	Transport dherash me auto 5 km	m ³	200.0		-
14	anal	Heqje dhe Montim Shtylla Elektriqe (Kablo+ tela)	cope	2.0		-
15	An96	Tabela Rruge normal , 60-90	cope	2.0		-
16	2.262/4	Beton C 16/20 per kunete	m ³	7.5		-
		Shuma II				0
		II. Ndertim Bankine				
1	3.87/a	Germim dheu	m ³	23		-
2	3.158/5a	Transport dherash me auto 5 km	m ³	23		-
3	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	25		-
		Shuma V				0
		III Punime per K.U.N , KUB				
1	3.87/a	Germim dheu kanal me makineri	m ³	90		-
2	3.183/c	Mbushje me çakull nen e mbi tuba	m ³	100.0		-
3	3.158/5a	Transport dherash teprice me auto 5 km	m ³	90		-
4	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm ne rruge	ml	150		-
5	An - 19	Puseteshkarkimi b/a, 80 x 80 cm, h = 100 cm	cope	2		-
6	Analize	Ngritje pusetash ekzistuese	cope	3		-
		Shuma VI				0
		Shuma (I+ II+ III)				0
		I. Punime ne rrugen , degezime B=7.2m Lt=780 m				
		L 2= 630 B= 5 m (basl= 4 + bankine 2x0.4 m)				
1	3.An-49	Thyerje betoni t=10 cm	m ³	85.0		-
2	2.426/2	Prishje mure ekzistuese me blloqe	m ³	378.0		-
3	3.114/b	Germim dheu ne trupin e rruges	m ³	911		-
4	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	982		-
5	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	3,150		-
6	3.187	Shtrese stabilizanti 10 cm	m ²	2,520		-
7	3.229/1	Shtrese binderi 5cm + Sperkatje me emulsion	m ²	2,520		-
8	3.226/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	2,520		-
9	3.617/1	F.V bordura betoni 15x30 cm	ml	25		0
10	3.183/a	Shtrese zhavor lumi, nen themelin e bordures, t=10cm	m ²	9		0
11	2.262/3	Struktura monolite betoni, C 12/15,+ kundrabordura (10x40) + kunete	m ³	112		0
13	3.158/5a	Transport dherash me auto 5 km	m ³	910.8		-
14	anal	Heqje dhe Montim Shtylla Elektriqe (Kablo+ tela)	cope	11.0		-
		Shuma II				0
		II. Ndertim Bankine				
1	3.87/a	Germim dheu	m ³	101		-
2	3.158/5a	Transport dherash me auto 5 km	m ³	101		-
3	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	76		-
		Shuma V				0
		III Punime per K.U.N , KUB				
6	Analize	Ngritje pusetash ekzistuese	cope	6		-
		Shuma VI				0
		Shuma (I+ II+ III)				0
		SHUMA A + B				0

Objekti :Ndertim Rruga Mitat Frasheri Koder e kuqe , Bashkia Kamez

Nr	nr.anal	EMERTIMI	njesia	Sasia	Çmimi	Vlera - leke
		<i>A. Punime ne rrugen , degezime B=7.2 m Lt= 176m</i>				
		<i>L 1 = 176 m , B= 7 m (basl= 4 + Kunete 2x0.5 + bankine 2x1.0 m)</i>				
1	2.426/2	Prishje mure ekzistuese me blloqe	m ³	12.0		-
2	3.114/b	Germim dheu ne trupin e rruges	m ³	170		-
3	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	120.8		-
4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	880		-
5	3.212/a	Shtrese stabilizanti 5 cm	m ²	704		-
6	3.229/1	Shtrese binderi 5cm + Sperkatje me emulsion	m ²	704		-
7	3.226/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	704		-
8	3.158/5a	Transport dherash me auto 5 km	m ³	170.0		-
9	anal	Heqje dhe Montim Shtylla Elektrike (Kablo+ tela)	cope	3.0		-
10	3.617/1	F.V bordura betoni 15x30 cm	ml	320		0
11	3.183/a	Shtrese zhavor lumi, nen themelin e bordures, t=10cm	m ²	102		0
12	2.262/4	Beton C 16/20 per kunete	m ³	17.0		-
13	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm ne rruge	ml	46		-
14	An-23	Puseteshiu 40x60 h=10 cm me kapak gize	cope	4		-
		Shuma I				0
		II. Ndertim Trotuari (Bankine)				
1	3.87/a	Germim dheu	m ³	89		-
2	3.158/5a	Transport dherash me auto 5 km	m ³	89		-
3	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	38		-
		Shuma II				0
		III Punime per K.U.N , KUB				
1	Analize	Ngritje pusetash ekzistuese	cope	2		-
		Shuma III				0
		Shuma (I+ II+ III)				0
						0
		T.V.SH 20%				0
		Shuma Totale				0

Shenim : Hartuar ne baze te VKM nr. 629 dt 15.07.2021

Preventivues:

Ing. Hajredin MURGU

Ing. Elmaz MURATI

Ing. Flora MUÇA

Procurement
Albania

Drejtori D.P.K.ZH.T
Ark. Arber TOLA

MIRATOI
Xhelal MZIU

K R Y E T A R



0
0



