

**PREVENTIVI I PUNIMEVE**

Objekti: "Sistemim asfaltim rruga nacionale Pika Ada-By Pass - Dobraq, NJA Rrethina"

nr	nr.Anal.	Pershkrimi I punimeve	njesia	Sasia	Cmimi	Vlefte
<b>1.Punime germimi</b>						
1	3.2	Prerje bime te vogla Ø-10 cm	m2	830.0		-
2	3.87/a	Germim dheu me eks,me goma 0.25, kanal b:2m,toke zak.,kat.III,shkarkim ne toke(KUB Ø 315 mm)	m3	205.0		-
3	3.98/b	Germim dheu ,eks. 0.25,b>2m, toke e zak.,kat.III,shkarkim ne mjet,(deri 0.2 m)	m3	125.0		-
4	An-49	Prishje strukture betoni	m3	35.0		-
5	3.158/5a	Transport dheu 5 km	m3	365.0		-
<b>Shuma 1</b>						<b>-</b>
<b>2.Punime shtresash</b>						
1	An-9	Mbushje me zhavor e kanaleve te KUB	m3	85.0		-
2	An164/1b	Mbushje me çakell e gur gurore ne trupin e rruges perhapur e ngjeshur me makineri	m3	415.0		-
3	3.212/b	Stabilizant 5-20 mm, t=10 cm,perhapur dhe ngjeshur me makineri	m2	1,700.0		-
4	3.243	Struktura bet monolite C16/20(kuneta,bk=(2x50)cm,t=15cm)	m3	52.5		-
5	3.183.a	Shtrese zhavori lumi 10 cm nen kunete	m2	350.0		-
6	3.229/1	Shtrese binderi me zall lavatrice ,t=5cm,makineri	m2	1,700.0		-
7	3.231/1	Shtrese asfaltobeton me zall lavatrice,t=3cm,me makineri	m2	1,700.0		-
<b>Shuma 2</b>						<b>-</b>
<b>3.Punime ndertimi</b>						
1	3.An/1t	Tab I brinjzuar HDPE SN8 Ø315 mm	ml	285.0		-
2	2.576	Pusetekontrolli 1.5x1.5x1.5 m,b/a C 20/25,kapak gize	cp	8.0		-
3	An 23	Pusete shiu, 0.6x0.4x1.0m,b/a C 20/25,kapak gize	cp	32.0		-
4	2.584	Pusetekontrolli 2x2x1.5 m,b/a C 20/25,kapak gize	cp	1.0		-
5	3.617	F.V.Bordura betoni 15x25x100 cm	ml	700.0		-
6	3.616	F.V.Bordura betoni 12x25x100 cm	ml	350.0		-
7	3.242	Shtrese betoni nen bordure t=10 cm,C 12/15	m3	15.0		-
8	3.183.a	Shtrese zhavori lumi t=10 cm(nen bordure)	m2	150.0		-
9	3.243	Strukture monolite betoni C 16/20	m3	73.5		-
10	3.183.a	Shtrese zhavori lumi t=10 cm, ne trotuar	m2	735.0		-
11	3.367	Tombino Ø1000 mm,me shtrese betoni	ml	350.0		-
<b>Shuma 3</b>						<b>-</b>
<b>4.SINJALISTIKA HORIZONTALE RRUGORE</b>						
1	An158.	F.V.Tabela rrugore vertikaleØ60 cm	cope	6.0		-
2	3.242	Beton C 12/15, bazament tabelash	m3	1.0		-
3	An.142	Vizime me boje bikomponente	m2	115.0		-
<b>Shuma4</b>						<b>-</b>
<b>5.GJELBERIMI</b>						
1	An	Dhe vegjetal	m3	185.0		-
2	3.643	Mbjellje bari	m2	950.0		-
3	An.	F.V.peme dekorative(rrap),cdo 6 ml, d=8-12cm,iartesi h=2.5 m	cope	20.0		-
<b>Shuma 5</b>						<b>-</b>
<b>Vlefte 1+2+3+4+5</b>						<b>0</b>
Fond rezerve 3%						0
Shuma						0
Tatimi mbi vleren e shtuar T.V.SH.20%						0
<b>Vlefte e plote</b>						<b>0</b>

Cmimet jane marre nga manuali I MPPRRT,botuar ne fletoren zyrtare nr.125,dt21/7/2015

sipas VKM nr.627,dt.15/07/2015

Per zerat e punimeve qe nuk jane ne manual jane hartuar analizat e cmimeve

**PREVENTIVUES**

ing. Erjon DILAVERI