

Nr	Nr.anal	EMERTIMI I PUNIMEVE	Njesi a	Sasia	Cmimi
		I - Punime ndertimi			
1	3.122/b	Germim shkambi i coptuar me ekskavator 0.5 m ³ , shkemb, ne themele gjeresi >2 m, me shkarkim ne mjet	m3	650	
2	2,37/5a	Transport dheu deri 5 km	m3	650	
3	An	Skarifikim shtrese asfalti me makineri	m2	4400	
4	3.205/2	Shtrese zhavori lumi t=20cm, perhapur e ngjeshur me makineri	m2	1334	
5	3.212/b	Shtrese stabilizant t=10cm	m2	1334	
6	An	Sperkatje me emulsion bituminoz 0.5 l/m2	m2	3802	
7	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m2	1103	
8	3.227/1	Shtrese binderi me zall lavatrice,3cm,me makineri per nivelimin e nje krahu te rruges	m2	2710	
9	3.233/2	Shtrese asfaltbetoni me zall lavatrice,5cm,me mak	m2	4946	
10	2.258	Nenshtrese zhavori nen bordure	m3	25	
11	3.240	Struktura monolite betoni C 12/15 nen bordure	m3	34	
12	3.617/2	F V bordura betoni 15x35 cm	m	1823	
13	2.258	Shhtrese zhavori pas bordurave	m3	153	
14	2.258	Nenshtrese zhavori nen kunete	m3	43	
15	3.240	Struktura monolite betoni C 12/15 nen kunete	m3	39	
16	3.244	Struktura monolite betoni C 20/25 kunete	m3	50.4	
		Shuma - I	leke		
		II-Punime kanalizimet			
1	2An.575	Rikonstruksion i ngritjes pusetave te ujrave te zeza dhe albtelekomit	cope	2	
2	3An.1	F.V.Kapak pusetash te rumbullakta	cope	2	
3	3.98/b	Germim dheu me ekskavator zingjir, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	170	
4	2,37/5a	Transport dheu deri 5 km	m3	170	
5	3.240	Struktura monolite betoni C 12/15 nen tubacione	m3	4.7	
6	3.183/a	Shtrese zhavor lumi 10 cm per kanal	m2	24	
7	2.555	F.V tuba betoni Ø 500 mm	ml	20	
8	An1	Ndertim puseta betoni H=2.5-3m, D=1m + kapak gize	cope	2	
9	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke zak	m3	140	
		Shuma - II	leke		
		III-Punime per ujrane shiut (KUB)			
1	3.98/b	Germim dheu me ekskavator zingjir, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	176	
2	2,37/5a	Transport dheu deri 5 km	m3	176	
3	2.An-22	Puseta b/a shiu 40x40x100 cm me kapak zgare hekuri	cope	32	
4	2.552	F.V tuba betoni Ø 200 mm	ml	880	
		Shuma - III	leke		

		IV-Punime sinjalistike				
1	An158	FV tabela te ndryshme rrugore D=60cm	cope	2		
		Shuma - VI	leke			
		Shuma I deri IV	leke			
		Fondi rezerve 3%	leke			
		Shuma	leke			1
		20 % T.V.SH.	leke			
		SHUMA	leke			