

Preventivi pa cmime

Objekti: Ndertimi kendeve sportive per shkollat: 9-vjecare "Nimetete Progonati" dhe e mesme "Sali Nivica"

NR.	NR. AN	EMERTIMI I PINIMEVE	NJESIA	SASIA	CMIMI	VLERA
Punime te fusha sportive						
1	3.137	Germim dheu me ekskavator goma 0.15 m ³ , ne themele, toke zak, kategoria III, me shkarkim ne toke (fusha)	m ³	126.0		
2	2.25a	ekskavator me goma kova 0.25 m3 shkarkim ne toke	m3	85.0		
3	3.158/5a	Transport dheu me auto 5km	m ³	210.0		
4	2.109/2	Themel e xokol betoni C12/15	m3	40.0		
5	2.114/1	Plinta bazamente b/a monolite deri 20m3 C16/20	m3	20.0		
6	2.116/1	Trare themeli monolit b/a C16/20	m3	31.0		
7	3.241	Shtrese betoni C12/15	m ³	16.0		
8	2.166	F.V hekur periodik 6-10mm	ton	1.0		
9	2.167	F.V hekur periodik >12 mm	ton	5.0		
10	2.182	Konstruksione metalike te thjeshta	ton	23.237		
11	3.208	Shtrese cakulli t=10cm, makadam, perhapur ngjeshur me makinerie	m ²	160.0		
12	3.212/c	Shtrese stabilizant t=15cm	m ²	160.0		
13	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 3 cm, me makineri	m ²	493.0		
14	2.109/2	Themel betoni C12/15 per tabelat	m ³	1.8		
15	3.288	F.V hekur betoni i zakonshem ø > 12 mm	ton	3.0		
16	An.1	F.V shtrese niveluese elastike Mapecoat	m ²	450.0		
17	An.2	F.V tapet rezine sintetike me ngjyra per terrene sportive Mapecoat TNS Finish	m ²	450.0		
18	An.3	Vizime me boje resina acrilica Mapecoat TNS Line d=8cm (me tre	m ²	50.0		
20	An.4	F.V mbulese PVC 900gr/m2	m2	1,000.0		
21	4.112	bojatisje mbi metal, me rreze dore mm e dy duar boje vaji, konstruksione me	m ²	60.0		
22	3.379	F.V. Rere nen dhe mbi tubacione PE + kompakesim	m ³	15.00		
23	An-9 M3	F.V. Zhavorr ne kanale + ngjeshje me shtresa cdo 25cm	m ³	22.0		
24	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	85.0		

25	An.5	Pusete b/a shiu 50 x 70 cm, h = 100 cm, me kapak gize	cope	6.0		
26	3.137	Germim dheu me ekskavator goma 0.15 m ³ , ne themele, toke zak, kategoria III, me shkarkim ne toke (kanalizimet)	m ³	35.0		
27	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	6.0		
28	3.An/57/b	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	6.0		
29	3.An/53	F.V e shtyllave metalike per ndricim me lartesi h = 7 m d=160mm	cope	6.0		
30	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	6.0		
31	An.6	F.V te kuadrit elektrik me automat mgt 4p 32A, automat diferencial 4p 40A 5d=0,3A, 4 automatë mgt 1p 16A 16kA, 4 kontaktorë modular 4p 40A, 4 çelësa seksionues 1p 16A	cope	2.0		
32	An.7	Tub fleksibel Ø 64 mm	ml	160.0		
		SHUMA				
		FONDI REZERVE 5%				
		SHUMA				
		TVSH 20%				
		SHUMA				

Per: C.E.C GROUP shpk
Vangjush MBRICE
Anduen MBRICE