

PREVENTIV

OBJEKTI: " SISTEMIM ASFALTIM I RRUGES SE LAGJES KAPEDANI FAZA E I" QYTETI VAU DEJES

POROSITES: BASHKIA VAU I DEJES

Nr.	Nr. an.	EMERTIMI I PUNUMEVE	NJESIA	SASIA	ÇMIMI	VLERA
		a, PUNIME GERMIMI DHE PRISHJE				
1	3.106/b	Germim dheu me eskavator 0.5 m3, ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet, inerte etj.	m ³	100,00		
2	2.37/5a	Transport dheu me auto deri 5.0 km	m ³	100,00		
		shuma a	leke			
		b, PUNIME NE RRUGE				
1	3.106/b	Germim dheu me eskavator 0.5 m3, ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet	m ³	200,00		
2	2.37/5a	Transport materiale ndertimi, deri 5.0 km	m ³	200,00		
3	3.212/c	Shtrese stabilizanti t=15cm	m ²	3.800,00		
4	3.229/2	Shtrese binderi me zall lavatrice , 6cm, me makineri	m ²	3.500,00		
5	3.231/1	Shtrese asfaltobetoni me zall lavatrice 3cm, me makineri	m ²	3.500,00		
6	3.212/b	Shtrese stabilizant t=10cm (Bankina)	m ²	380,00		
7	2.262/4	Shtrese betoni C 16/20, per kuneta.	m ³	42,00		
		shuma b	leke			
		c, PUNIME NE KUB				
1	An	F V tuba te brinjezuar HDPE SN8 d=250 mm	ml	780,00		
2	An - 23	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak gize	Cope	17,00		
3	3,364	Tombino me tuba betoni Ø 500	ml	58,00		
4	3,367	Tombino me tuba betoni Ø 1000	ml	22,00		
		shuma c	leke			
		d, PUNIME VADITJE				
1	3.106/b	Germim dheu me eskavator 0.5 m3, ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet	m ³	344,00		
2	2.37/5a	Transport materiale ndertimi, deri 5.0 km	m ³	344,00		
3	3,364	Tombino me tuba betoni Ø 500	ml	13,00		
		shuma d	leke			
		e, PUNIME SINJALISTIKA				
1	An22	FV Mbrojteje metalike anesore per ure (Guardrail)	ml	47,00		
		shuma e	Leke			
		SHUMA A-E	Leke			
		TVSH 20%	Leke			
		TOTALI	Leke			

**PREVENTIVOI
SHOQERIA "GOLD CONSTRUCTION" SH.P.K.**