

PREVENTIV

OBJEKTI : SISTEMIM ASFALTIM I RRUGES

HYRESE NE FSHATIN ZVIRINË (Faza I)

L = 340m

VLERA

lek

Nr	Nr.An	EMERTIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
I		PUNIME GERMIMI DHE MBUSHJE NE RRUGE				
1	3.89/b	Germim seksioni I detyruar shkarkim ne mjet	m3	650		
2	An	Heqje soleta b/a	m2	75		
3	2.426/5	Prishje mure betoni	m3	49		
4	3.353	Mbushje me materjal shkembor	m3	700		
5	3.An	Skarifikim shtrese asfalti me makineri	m2	1280		
6	3.158/3a	Transport dheu + mbeturina ndertimi ne distanc 3 km	m3	850		
II		PUNIME BETONESH DHE B/A NE RRUGE				
1	2.264	Shtrese lluster çimento 1:2	m2	50		
2	2.262/4	Beton C - 16 / 20	m3	51		
3	3.244/1	Struktura te holla monolite betoni C-20/25	m3	259		
4	3.243	Struktura monolite betoni C-16/20	m3	34		
5	3.287	Hekur betoni Φ 6-10 mm ²	ton	0.4		
6	3.289	F.V. Hekur betoni periodik $\Phi > 12$ mm ²	ton	23.47		
7	3.620	Shtrese me pllaka veteshternguese t = 6cm	m2	330		
8	3.636	Parmak ure I gatshem metalik me tubo zingato Φ 50mm	ton	0.1		
III		PUNIME SHTRESA NE RRUGE				
1	3.212	Shtrese cakulli makadam t = 25cm	m2	740		
2	3.212/b	Shtrese stabilizanti t = 10cm + sperkatje	m2	1720		
3	3.222/1	Shtrese binderi t = 5cm	m2	1720		
4	3.226/1	Shtrese asfaltobetoni t = 4cm	m2	1720		
IV		PUNIME NE BORDURA DHE KUNETA NE RRUGE				
1	3.617/1	F.V. Bordura rruge e parafabrikuar 15x30 cm	ml	660		
2	3.620	Shtrese me pllaka veteshternguese t = 6cm	m2	890		
3	3.205	Shtrese zhavori t = 10cm	m2	890		
4	3.616	F.V. Bordura trotuari e parafabrikuar 12x25 cm	ml	580		
V		F.V.TUBASH NE KUB.DHE TE SHIUT NE RRUGE				
1	3.44/1	Germim dhe mbulim kanali	m3	91		
2	3.An/3t	F.V. Tuba te brinjezuar HDPE SN d=500mm	ml	25		
3	3.An/1t	F.V. Tuba te brinjezuar HDPE SN d=315mm	ml	80		
4	3.652	F.V. Tuba te brinjezuar HDPE SN d=200mm	ml	184		
5	An	Shtrese materjal I bute rreth tubit t=20cm	m3	68		

VI		PUNIME PUSHTASH NE RRUGE				
1	An-22/1	Ndertim puseta 40x40, h=100cm me zgare gize per ujrata e shiut	cop	16		
VIII		PUNIME ELEKTRIKE				
1	3.25/b	Germim dhe mbulim kanali	m3	112		
2	2.114/1	Beton C 16/20	m3	13.4		
3	An/53	F.Vshtylla metalike per ndricim komplet h= 8 ml	cop	15		
4	An	F.V Ndricesa me llamb led 32 W	cop	15		
5	3.An/pp	F.V puseta elektrike pvc 40*40	cop	15		
6	3.An/el	F.V elektroda togezime	cop	15		
7	4.142/1.29	F.V kabell te vendosur ne toke 4*4 mm2	ml	350		
8	2.482/1	F.V kabell 3*1.5 mm2	ml	135		
9	3.654/1	F.V. tub brinjezuar plastik O 90	ml	350		
10	2.a-112 + a-106	F.V Panel komandimi	cop	1		
11	3.An164	F.V Mbjellje peme dekorative 16-18 cm ne trotuar	cop	82		
IX		PUNIME SINJALISTIKE				
1	3.An 105	Tabela trekendore vogla me A=60	cop	5		
2	3.An 96	Tabela tetekendore vogel me A-B, 60-20	cop	2		
3	3.An 47	Tabela katrore e vogel 40x40	cop	2		
4	3.An 127	Vijezim shirit gjatesor dhe anesor me gjeresi 12cm Bikomponente (sprajt)	ml	990		
5	3.An 149	F.V. Kurize artificiale h=5cm	cop	8		
		SHUMA A				
		T.V.SH.	20%			
		SHUMA				





