

## PREVENTIVI PER NDERTIMIN E TROTUAREVE

Objekti: "Hartimi i projekt-preventivit zbatimit per objektin ndertimi trotuareve  
Qender-Vranisht, Kodra Madhe-Krume, Qender-Letaj, Rrugë malore qëndër fshati Gjinaj-  
Bjeshka(Stanet) Gjinaj" ,Bashkia Has

### NDERTIMI I TROTUAREVE QENDER-VRANISHT, KODRA MADHE-KRUME, QENDER-LETAJ

VLERESUAR SIPAS VKM Nr. 629 Dt.05.11.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
<b>A</b>						
<b>QENDER-VRANISHT</b>						
<b>I PUNIME TROTUARIN</b>						
1	An1	Germim per tupin e rruges	m3	150.00		-
2	2.37/3a	Transport materiale ndertimi, dheu me auto deri 3.0 km	m3	150.00		-
3	3.618	F V bordura betoni 20x35 cm	ml	502.00		-
4	3.240	Struktura monolite betoni C 12/15	m3	15.06		-
5	3.244/1	Struktura te holla monolite betoni C 20/25	m3	85.00		-
6	3.620	Trotuar, me 6 cm beton, me pllaka	m2	347.70		-
7	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	52.00		-
		<b>Shuma I</b>				-
<b>II SINJALISTIKA E SIGURIA</b>						
1	An 158	FV tabela te ndryshme rrugore D=60cm	cope	2.00		-
2	An35	Parapet I njeanshem per beton (ø 60) + aksesoret	ml	8.00		-
		<b>Shuma II</b>				-
		<b>Shuma I+II</b>				-
<b>B</b>						
<b>KODRA MADHE-KRUME</b>						
<b>I PUNIME TROTUARIN</b>						
1	An1	Germim per tupin e rruges	m3	183.00		-
2	2.37/3a	Transport materiale ndertimi, dheu me auto deri 3.0 km	m3	183.00		-
3	3.618	F V bordura betoni 20x35 cm	ml	610.00		-
4	3.240	Struktura monolite betoni C 12/15	m3	18.30		-
5	3.244/1	Struktura te holla monolite betoni C 20/25	m3	95.00		-
6	3.620	Trotuar, me 6 cm beton, me pllaka	m2	396.50		-
7	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	60.00		-
		<b>Shuma I</b>				-
<b>II SINJALISTIKA E SIGURIA</b>						
1	An 158	FV tabela te ndryshme rrugore D=60cm	cope	2.00		-
2	An35	Parapet I njeanshem per beton (ø 60) + aksesoret	ml	24.00		-
		<b>Shuma II</b>				-
		<b>Shuma I+II</b>				-
<b>C</b>						
<b>QENDER-LETAJ</b>						
<b>I PUNIME TROTUARIN</b>						
1	An1	Germim per tupin e rruges	m3	221.00		-
2	2.37/3a	Transport materiale ndertimi, dheu me auto deri 3.0 km	m3	221.00		-
3	3.618	F V bordura betoni 20x35 cm	ml	913.00		-
4	3.240	Struktura monolite betoni C 12/15	m3	27.40		-
5	3.244/1	Struktura te holla monolite betoni C 20/25	m3	152.20		-
6	3.620	Trotuar, me 6 cm beton, me pllaka	m2	593.00		-
7	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	118.00		-
		<b>Shuma I</b>				-

VLERESUAR SIPAS VKM Nr. 629 Dt.05.11.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
II		<b>SINJALISTIKA E SIGURIA</b>				
1	An 158	FV tabela te ndryshme rrugore D=60cm	cope	2.00		-
2	An35	Parapet I njeanshem per beton (ø 60) + aksesoret	ml	68.00		-
		<b>Shuma II</b>				-
		<b>Shuma I+II</b>				-
		<b>SHUMA A+B+C</b>				-
		<b>TVSH</b>	<b>20%</b>			-
		<b>TOTALI</b>				-

Shoqeria "MCE" shpk  
 Administrator  
 Ing.Petrit MUJA

