

# PREVENTIV

**OBJEKTI : SISTEMIM I SHESHEVE DHE RRETHIM I VARREZAVE TE FSHATRAVE RRANXA, HAJMEL,  
POROSITESI : BASHKIA VAU DEJES**

## PREVENTIV 1. SISTEMIM ASFALTIM I RRUGES VARREZAVE HAJMEL DHE NENSHAT

Nr.	Nr.An	Emertimi i punimeve	Njesia	Sasia	Çmimi	Vlera
<b>A.PUNIME NE RRUGE</b>						
1	3.106/b	Germim dheu me ekskavator zingjir 0.5 m <sup>3</sup> , ne kanale gjeresi > 2 m, prani uji ~ 2m, kategoria IV, me shk ne mjet	m <sup>3</sup>	100		
2	3,205	Shtrese zhavori lumi t=10cm perhapur e ngjeshur me makineri	m <sup>2</sup>	1400		
3	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	1.400		
4	3.229/1	Shtrese binderi me zall lavatriçe, 5cm, me makineri	m <sup>2</sup>	1.300		
5	3.231/1	Shtrese asfaltobetoni me zall lavatriçe, 3cm, me makineri	m <sup>2</sup>	1.300		
6	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	100		
<b>SHUMA</b>						<b>leke</b>
<b>TVSH 20%</b>						<b>leke</b>
<b>SHUMA TOTALE</b>						<b>leke</b>

## PREVENTIV 2.SISTEMIM ASFALTIM I RRUGES SE LAGJES KOVAÇ FSHATI HAJMEL

Nr.	Nr.An	Emertimi i punimeve	Njesia	Sasia	Çmimi	Vlera
<b>A.PUNIME NE RRUGE</b>						
1	3.89/b	Germim dheu me ekskavator me goma 0.25 m <sup>3</sup> , ne kanale gjeresi > 2 m kategoria III, me shk ne mjet	m <sup>3</sup>	310		
2	3,243	Struktura monolite betoni C 16/20	m <sup>3</sup>	22		
3	3,211	Shtrese çakelli mbeturine gur kave t=20cm perhapur e ngjeshur me makineri	m <sup>2</sup>	700		
4	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	700		
5	3.229/2	Shtrese binderi me zall lavatriçe, 6cm, me makineri	m <sup>2</sup>	600		
6	2,519	Tub kanalizimi pvcΦ90mm	ml	16		
7	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	310		
<b>SHUMA</b>						<b>leke</b>
<b>TVSH 20%</b>						<b>leke</b>
<b>SHUMA TOTALE</b>						<b>leke</b>

## PREVENTIV 3. SISTEMIM ASFALTIM I RRUGES SE VARREZAVE FSHATI NENSHATE

Nr.	Nr.An	Emertimi i punimeve	Njesia	Sasia	Çmimi	Vlera
<b>A.PUNIME NE RRUGE</b>						
1	3.89/b	Germim dheu me ekskavator me goma 0.25 m <sup>3</sup> , ne kanale gjeresi > 2 m kategoria III, me shk ne mjet	m <sup>3</sup>	240		
2	3,243	Struktura monolite betoni C 16/20	m <sup>3</sup>	5		
3	3,211	Shtrese çakelli mbeturine gur kave t=20cm perhapur e ngjeshur me makineri	m <sup>2</sup>	1200		
4	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	1.200		
5	3.229/2	Shtrese binderi me zall lavatriçe, 6cm, me makineri	m <sup>2</sup>	1.100		
7	2,555	FV tuba betoni Φ500mm	ml	16		
8	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	240		
<b>SHUMA</b>						<b>leke</b>
<b>TVSH 20%</b>						<b>leke</b>
<b>SHUMA TOTALE</b>						<b>leke</b>

**PREVENTIVOI**  
**ing.Gzim LIKAJ**