

PREVENTIV PUNIMESH

Objekti: " Rikonstruksion I rruges " Shyqyri Lakra "
(segmenti I rruges "Abedin Qafoku " deri te rruga "Riza Nebati")

Nr		Emertimi I punes	Njesia	Sasia	cmimi	Vlera
	A	Punime prishjeje				
1	2.426/2	Prishje mure rrethues	m3	100.00		-
2	2.426/4	Prishje struktura betoni dhe B/A	m3	4.00		-
		Shuma A				-
	B	Punime ne rruge				
1	3.104/b	Germim ne trup te rruges	m3	900.00		-
2	3.211 +An	Shtrese cakull guroreje 2x20cm	m2	1,980.00		-
3	3.212/b	Shtrese stabilizanti 10 cm	m2	1,980.00		-
4	3.222/2	Shtrese Binder me granil gur kave me makineri , t= 6cm	m2	1,680.00		-
5	3.226/1	Shtrese Asfaltobeton me granil gur kave t=4cm me makineri	m2	1,680.00		-
6	3.618	F V bordura betoni 20x35 cm	ml	685.00		-
7	2.262/3	Shtrese betoni nen bordure M150 t=10cm	m3	24.00		-
8	2.262/3	Kunete betoni M250	m3	32.00		-
9	3.158/5a	Transport dheu me auto deri 3km	m3	1,150.00		-
		Shuma B				-
	C	Punime ne trotuar				
1	2.25	Germim dheu themel muri	m3	50.00		-
2	2.11	Themel e xokol butobetoni C - 12/15	m3	60.00		-
3	2.88	Mur me blloqe betoni t=20cm deri 3m me llaç perzier M 15	m3	60.00		-
4	2.114	Beton per kollonetat dhe brezin mbi mur	m3	7.00		-
5	2.166	F.v. hekur beton periodik 6-10 mm	ton	0.80		-
		Shuma C				-
	D	Kanalizimet e ujrave te bardha				
1	3.104/a	Germim dheu me shkarkim ne mjet	m3	210.00		-
2	2.258	Mbushje me zhavor	m3	64.00		-
3	3An./1t	F.V. tub HDPE D=315mm	ml	335.00		-
4	2.575	F.V. puseta kontrolli 100x100 x150cm	cope	2.00		-
5	An.23	F.V. puseta b/a shiu kapak gize 40x60	cope	13.00		-
		Shuma D				-
	E	Kanalizimet e ujrave te zeza				
1	3.104/a	Germim dheu me shkarkim ne mjet	m3	178.00		-
2	2.258	Mbushje me zhavor	m3	58.00		-

3	3An./1t	F.V. tub HDPE D=315mm	ml	335.00		-
4	2.575	F.V. puseta kontrolli 100x100 x150 cm	cope	12.00		-
		Shuma E				-
		Shuma A+B+C+D+E				-
		TVSH		20%		-
		Shuma Totale				-

Preventivi u hartua ne baze te cmimit te manualit 2015

PUNOI

Ing. Valentina Zotkaj

Ing. Valentina Karabina

Ing. Anxhelo Dhimo

MIRATOI

KRYETARI I BASHKISE

PETRIT SINAJ