

PREVENTIVI I PUNIMEVE

**OBJEKTI
RIVITALIZIMI I SHESHIT KOZMA NASKA**

FAZA: PROJEKT ZBATIMI

Nr.	Analize	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vle
		PUNIME NDERTIMORE				
1	2.426/3	Prishje shtresa betoni	m3	159		
2	2.426/6	Prishje mure beton/arme	m3	7.5		
3	2.426/7	Prishje kollona, trare b/a	m3	2		
4	3.25/a	Germim me krahe, toke e zakonshme	m ³	80		
5	2.37/5a	Transport materiale ndertimi, me auto deri 5.0 km	m3	248.5		
6	2.114/1	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20 (themeli i mureve te shatervanit)	m3	5		
7	2.258	Nenshtrese zhavori (mbushja me zhavor t=10 cm nen themel + mbushja nen soleten e shatervanit+ t=10 cm zhavor nen bordura)	m3	30		
8	2.130/1a	Mure b/a t = 21-30cm, h ~ 4m C 20/25 (muret e basenit te shatervanit)	m3	15		
9	2.122/1a	Soleta te plota b/a C 20/25 t=25cm (soleta e shatervanit)	m3	10		
10	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.5		
11	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.8		
12	3.643	Mbjellje bari	m2	1,540		
13	3.619/a	Bordura betoni 6x20 cm (perreth trotuarit me pllaka guri)	m	57		
14	Analize	Trotuar, me 6 cm beton, me pllaka guri (50x50 50x40 sipas kerkeses se projektuesit)	m2	78		
15	Analize	Trotuar, me 6 cm beton, me zhavor lumi (mozaiku) (pjeset qe shtohen+riparimet e egzistuesit)	m2	43		
16	3.193/a	Shtrese zhavor lumi t=10cm, me cilindrim (nen siperfaqet qe trajtohen si trotuare)	m2	121		
17	3.620	Trotuar, me 6 cm beton, me pllaka (sipas kerkeses se projektuesit)	m2	31		
18	2.262/4	Shtrese betoni C 16/20 (riparimi I bazamenteve ku do te vendosen stolat+riparimi I vazove te luleve egzistuese)	m3	5		
19	3.An163	F.V. Fidane Lule dekorative	cope	1,200		

20	3.An165	F.V. Fidane shkurre dekorative (sipas kerkeses se projektuesit)	cope	125		
21	3.An167	F.V. bredha me d > 10 cm	cope	3		
22	3.An169	F.V mbjellje peme dekorative Bli	cope	4		
23	An164	F.V. Fidane Peme dekorative (sipas kerkeses se projektuesit)	cope	8		
24	2.An - 18	Pusete shkarkimi b/a, 50 x 50 cm, h = 100 cm(per shkarkimin e shatervanit)	cope	2		
25	2.520	Tub kanalizimi pvc Ø 110 mm	ml	35		
26	2.261	Shtrese rere	m3	1		
27	2.355/b	Veshje pllaka guri (per veshjen e shatervanit sipas kerkeses se projektuesit)	m2	121		
28	An	Kosha plehrash	cope	16		
29	2.404/1	Patinim granili si mermer artistik (patinimi I vazove egzistuese)	m2	70		
		Shuma -1				
		PUNIME PER SHATERVANIN				
Nr.	Analize	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vle
1	2.491/a	Tub PE 20 mm rregullimi i nivelit	ml	30		
2	2.491/d	Tub PE 40 mm shkarkimi I teperplotesit	ml	30		
3	oferte	Pusete me filter shporte tipi Drain 12/50, fil. 4" F	cope	2		
4	2.491/h	Tub PE 110 thithja nga shatervani	ml	30		
5	2.491/f	Tub PE 63 mm furnizimi I uje hedhesit kryesor	ml	30		
6	2.491/c	Tub PE 32 mm furnizimi I ujedhedhesve te rrethit	ml	480		
7	oferte	Pusete drenazhi Drain 10/20	cope	2		
8	2.491/g	Tub PE 75 mm shkarkimi I shatervanit	ml	30		
9	oferte	Kolektor dergimi çelik inox DN 100 mm (furnizon ujedhedhesit)	cope	2		
11	2.584	Pusete kontrolli 2x2x2m me kapak 1x1	cope	1		
12	oferte	F.V. Pompe centrifugale horizontale me prurje Q = 60 m3 dhe H = 30 m "WL 40-125/15"	cope	2		
13	oferte	F.V. Pompe drenazhi per puseten teknike te shatervanit "Dry 020"	cope	1		
14	oferte	Saraçineske hyrese (per pompat e shatervanit Ø110)	cope	4		
15	oferte	F.V. Ujedhedhes tivoli TI 50 me lartesi hedhje 1.5 m, me prurje 56 l/min me lidhje fileto femer F 1" inox brima 50 mm	cope	16		
16	oferte	F.V. Ujedhedhes tivoli TI 70 me lartesi hedhje 3.0 m, me prurje 152 l/min me lidhje fileto femer F 1 1/2" inox brima 75 mm	cope	1		
17	4.128/4	Valvol flutur (butterfly) moskthimi	cope	2		

18	2.494/3	F.V saracineska Ø 1 1/4 " = 32 mm per uje hedhesit	cope	16		
19	2.494/5	F.V saracineska Ø 2 " = 63 mm uje hedhesi kryesor	cope	1		
		Shuma -2				
		PUNIME PER NDERTIMIN E STOLAVE (24 COPE)				
Nr.	Analize	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vle
1	2.5	Germim e mbushje dheu me krah kategoria III per themele, h = 1.5m	m3	5.76		
2	2.116/1	Trare themeli monolit b/a C - 16/20	m3	4.32		
3	2.122/1a	Soleta te plota b/a C 20/25 t = 10 cm, h ~ 4m	m3	6.24		
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	1.44		
5	2.282	Shtrese derrasa FM 4.0cm	m2	25		
6	2.4	Boje vaji sipërfaqe druri	m2	510		
		Shuma -3				
		PUNIME NE RRJETIN E VADITJES				
Nr.	Analize	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vle
1	3.25/a	Germim me krahe, toke e zakonshme	m ³	20		
2	2.261	Mbushje me shtrese rere	m ³	10		
3	2.19	Mbushje me dhe te ngjeshur	m ³	8		
4	3.An -1	Ndertim pusete (rezervuar per sprucatorët e vaditjes 3m3)	cope	1		
5	2.491/c	F.V. Tubacione polietilene PEHD 100; Dj 32 mm perfshire rakorderite; PN10	ml	20		
6	oferte	Sprucator vaditë lidhje ½ rreze 5 m 210 l/ore dalja mbi toke 10 cmrregullimi I harkut nga 40-360 ° presioni I punes 1.4-6.9 bar sasia e reshje 15mm/ore kendi I hedhjes 14°	cope	27		
7	Analize	Shpim pusi deri 60 m	cope	1		
8	2.An - 17	F V pompe me pulmon 24 litra	cope	1		
		Shuma - 4				
		PUNIME NE RRJETIN ELEKTRIKE				
Nr.	Analize	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vle
		PUNIME ELEKTRIKE				
1	4.133/3.5	F.V ne toke kablllo Al fuqie +1000V,me izolim gome 4x16mm2	ml	50		
3	4.142/2.1	F.V kablllo CU pa armuar ,ne mure e konstruksioni 3x1.5mm2	ml	350		
4	4.142/2.2	F.V kablllo kontrolli CU te armuar ,ne toke 4x4mm2	m	250		

	9					
5	4.142/2.1 5	F.V kabllo CU pa armuar ,ne mure e konstruksioni 4x2.5mm2	ml	130		
6	3.654	F.V tub plasmasi ϕ 63mm	m	370		
7	3.An/pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	35		
8	2.481/2	F.V percjelles PV-500 \emptyset 4 mm2. per togezimin nga shtylla ne shtylle	ml	320		
9	An	F.V Kuader komandimi komplet me santeri +fotoelement	cope	1		
10	2.a-93	Percjelles togezimi bakrri Cu,S=35mm2 I shveshur	m	35		
11	3.An/et	F.V Elektrode togzimi te nxiguar L=150cm	cope	32		
12	2.490/1a	F.V Automat termo /el manj diferencial 220v, 10A	cope	32		
13	An	F.V. Ndricules Prozhektor LED Tipi A3 A=30w H=01m	cope	2		
14	An	F.V.Ndricules urban LED me shtylle metalike celiku Ndricules tek H=4ml D= \emptyset 16-25cm A = 40 W , Tipi A4	Cope	31		
15	An	F.V Ndricules tokesor asimetric LED P=15 -25 w . V=220 v.	cope	8		
16	An	F.V Ndricules tokesor asimetric LED P=10 -20 w . V=220 v.	cope	16		
17	3.25/a	Germim me krahe seksion detyruar me gjeresi b < 1 m, h=1.5 m, toke e zak.	m3	120		
18	2.553	F.V tub betoni ϕ 300ml	ml	31		
19	3.240.	Mbushje me beton marka 150 per ikastrim shtyllash	m3	9		
20	3.654	F.V. Tubap.v.c. fi ϕ 100mm per internetin	ml	220		
21	3.An-56	F.V Tuba Metalike D=140mm	ml	15		
22	3.182/a	Shtrese rere natyrore t=10cm	m2	35		
23	2.490/1a	F.V Automat termo 220v, 10A, {per Interneti Kamerat e sigurimit}	cope	1		
24	2.481/2	F.V percjelles PV-500 \emptyset 4 mm2 {per Interneti Kamerat e sigurimit}	ml	230		
25	3Anpp	Pusete kalimtare me kapak te forte 40x40x40{{per Interneti Kamerat e sigurimit}	cope	4		
		<i>Kamerat e sigurise</i>				
1	An	IP CAMERA 2mp	cope	4		
3	An	Switch POE 8 Porta rack mounted	cope	1		
4	2.481/1	F.V percjelles interneti FTP ,cat 6	ml	220		
		Shuma - 5				
		SHUMA 1-5				
		Fondi rezerve 3 %				
		SHUMA				7,583
		T.V.SH 20%				

		TOTALI PER ZBATIM OBJEKTI				
--	--	----------------------------------	--	--	--	--