



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ

Nr Prot.

Kamez me / /2019

PREVENTIV

Ndertim K.U.N. SKEJAVE + KUN MUSTAFA LITA , PASKUQAN 1 , Bashkia KAMEZ

Ndertim K.U.N. Kanali poshte Skejave deri ne Rrugen , Paskuqan 1 , Nj.Ad. Paskuqan , B. Kamez

NR	ANALIZ.	EMERTIMI I PUNIMIT	Njesi	Sasia	Çmimi	Vlefte
I. Punime ne Kanale , l=556 m						
Φ 1000 = 250ml , Φ800 = 256 ml ,						
1	3.139	Germim dheu me eskavator	m ³	2,274		-
2	3.158/5a	Transport dherash me auto 5 km	m ³	2,274		-
3	3.353	Mbushje me Çakull	m ³	1470.713		-
4	3.158/5a	Transport çakull me auto 5 km	m ³	1470.713		-
5	2.556	F.V. tub Betoni O 600 mm	ml	10		-
6	2.557	F.V. tub Betoni O 800 mm	ml	361		-
7	3.558	F.V. tub Betoni O 1000 mm	ml	250		-
9	2.576	Pusete Kontrolli 1.25x1.25x h	cope	6		-
10	2.576	Pusete Kontrolli 1.5x1.5x h	cope	5		-
11	An-8	Mbushje me cakell pas mureve	m ³	25		-
Shuma I						0

OBJEKTI: NDERTIM KUN RRUGEN " Rruga Mustafa LITA " , PASKUQAN 1

Lt= 300 m , Φ 315 mm = 100 m , Φ 400mm= 100 m , Φ 500mm = 100 m

Nr	An.	Emertimi I Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE KUN						
1	3.139	Germim dheu me eskavator(kanal)	m ³	240		0
2	3/158/5a	Transport dheu me auto 5km	m ³	240		0
3	3/353	Mbushje me cakull shkembor (kanal) Mbushje me cakull shkembor	m ³	144		0
4	3/158/5a	Transport cakull me auto 5km	m ³	144		0
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	100		-
6	3.An/2t	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	100		0
7	3.An/3t	F V tuba te brinjezuar HDPE SN8 d= 500 mm	ml	100		0
8	2.An - 21	Pusete shkarkimi b/a, 80 x 80 cm, h = 200 cm	cope	6		-
9	3.An-8	Mbushje me cakell te rruges t= 10 cm	m ³	42		0
SHUMA II						0
SHUMA I + II						0
T. V. SH.					20%	0
SHUMA						0

Shenim : Hartuar ne baze te VKM nr. 629 dt 15.07.2019

Preventives:

Ing. Hajredin MURGU

Ing. Flora MUÇA

Drejtori P.K.ZH.T-se

Ark. Erlend **BABALLEKU**

MIRATOI
Rakip S U L I

K R Y E T A R