EMERCENCYWORKS

TABLE B (Emergency works)

Road segments: Krumë-Prushi Pass(17.3 km), Golaj (K/Plepa) -Kam (23.1 km),

[TOTAL LENGTH 40.4 km]

No.	Work description	Total amount of routine maintenance	Emergency	Amount
		ALL	in %	ALL
1	Emergency works	0	3%	0
			SUM C:	0



MAY 2020

SUMMARY OF BILL OF QUANTITIES

OBJECT OF CONTRACT:

Performance-based routine maintenance, "Krumë-Prushi Pass, Golaj (K/Plepa) -Kam" road [TOTAL LENGTH 40.4 km]

SUMMARY TABLE

No.	CATEGORY OF WORKS	UNIT	AMOUNT	RATIO IN PERCENTAGE
1	ROUTINE MAINTENANCE	ALL		
2	PERIODIC AND REHABILITATION WORKS	ALL		
3	EMERGENCY WORKS	ALL		

REHABILITATIONWORKS

TABLE B (Rehabilitation works)

Road segments: Krumë-Prushi Pass(17.3 km), Golaj (K/Plepa) -Kam (23.1 km),

[TOTAL LENGTH 40.4 km]

Analysis No	Work description	Unit	Quantity	Price	Amount (ALL)
	EXCAVATION WORKS				
3.119/a	Excavation of rocks crushed by excavator 0.5 m³, with foundation width ~2 m, used for road track filling	m3	250		0
3.158/3a	Soil transportation by trucks in a distance up to 3.0 km	m3	10		0
3.161/2	Leveling of escarpments through excavation, excavator 0.25m ³	m2	120		0
An.164/1a	Filling of road track with excavated material, spread and compacted by machines	m3	8		0
	LAYER WORKS				
3.197	Removal of gravel layer t = 10 cm, by machines	m2	80		0
3.212/b	Stabilizing layer t=10cm	m2	2500		0
3.212/c	Stabilizing layer t=15cm	m2	100		0
3.212/d	Stabilizing layer t=20cm	m2	100		0
An	Scarifying of asphalt layers by machines	m2	4425.39		0
	ASPHALT WORKS				
3.222/2	Binder layer with crushed stones and quarry stones, 6cm, by machines	m2	2500		0
3.226/1	stones and quarry stones, 4cm, by machines	m2	4425.39		0
	CONCRETE WORKS				
3.244	Monolithic concrete construction C 20/2.	m3	210		0
3.268	Supply and installation of rectangular	m3	2.2		0
3.235	Monolithic b/concrete construction C 12/15 with 20% stone	m3	18		0
	REINFORCED CONCRETE WORKS				
3.287	Supply and installation of common rebars \emptyset 6 $^{\sim}$ 10mm	tons	0.25		0
3.288	Supply and installation of common rebars Ø > 12mm	tons	0.20		0
	CONSTRUCTION OF ART WORKS				
3.323	Stone retaining wall, M50 cement	m3	80		0
An-8	Filling the walls with gravel	m3	16		0

3.332	Gabion walls with galvanized wire mesh,	m3	15		0
J.JJZ	crushed stone 1x1x1.5 m	m	8	0	
3.366	Culverts with concrete pipes Ø 800,				0
3.367	above the concrete layer		<u> </u>		
	Culverts with concrete pipes Ø 1000,	m	8		0
	above the concrete layer				
	DIFFERENT WORKS				
3.618	Supply and installation of concrete	m	15		0
	ROAD SIGNS WORKS				
An48	Common rectangular sign board with A=	pcs	14		0
An106	Common triangular sign board with A = 9	pcs	38		0
An100	Common circular sign board indicating "prohibition" with D = 60	pcs	28		0
An97	Common octagonal sign board with A-B, 90-30	pcs	10		0
An116	Common side road marking lines with two senses (red + white)	pcs	8		0
An118	(Single) turn dotted marking lines	pcs	8		0
An119	(Double) turn dotted marking lines	pcs	8		0
An120	Mild or sharp (T-shaped) turn marking lines	pcs	8		0
An122	Road marking lines with bicomponent paint with a width of 12 cm	ml	100		0
An152	Road marking lines with bicomponent paint with a width of 15 cm	ml	50		0
An156	Supply and installation of road indication sign boards 150x40cm	pcs	6		0
An158	Supply and installation of different road sign boards D=60cm	pcs	20		0
An35	Single-sided concrete parapet (ø 60) + accessories (bridge)	ml	12		0
An4	H1 W3 single-sided guardrail with 2 wave beams + accessories (road)	ml	1100		0
				SUM B:	0

ROUTINEMAINTENANCE

TABLE A (Routine maintenance)

Road segments: Krumë-Prushi Pass(17.3 km), Golaj (K/Plepa) -Kam (23.1 km),

[TOTAL LENGTH 40.4 km]

Item No.	Work description	Length	Period	Price	Amount
		km month	month	ALL/km/month	ALL
1	Cleaning of roadside ditches and gutters	40.4	48		0
	Cleaning of existing circular and box				
2	culverts	40.4	48		0
3	Filling and leveling of shoulders	40.4	48		0
4	Removal of vegetation	40.4	48		0
	Cleaning of carriageway from alluvium				
5	and other materials	40.4	48		0
6	Repair of asphalt potholes	40.4	48		0
	Filling and profiling of subgrades in				
7	asphalt roads	40.4	48		0
	Repair and upgrade of horizontal road				
8	signs	40.4	48		0
9	Repair and upgrade of vertical road signs and road safety devices (guardrails barriers) and lighting	40.4	48		0
		_			_
10	Routine maintenance of art works	40.4	48		0
11	Winter maintenance	40.4	48		0
Sum A:				0	