

PREVENTIV I PUNIMEVE
Objekti: "STUDIM PROJEKTIM SISTEMIM ASFALTIM RRUGA BORSH - FTERRE

SEGMENTI BORSH - KALAJA E BORSHIT

Nr. Analiz.	Nr.	EMERTIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLEFTA
A. Punime ne Rruge						
2.426/2	1	Prishje mur blloqe betoni	m ³	62		
2.37/2a	2	Transport materjale ndertimi,dheu deri ne 2km	m ³	62		
An.	3	Skarifikim Shtrese asfalti me makineri	m ²	260		
3.158/e	4	Germim dheu kat l-re me makineri,l=100m,v6-6.5m3	m ³	5,414		
3.179	5	Germim T/F per kasonete me makineri + tr.auto	m ³	224		
An.164/1a	6	Mbushje dhe ngjeshje me material germimi	m ³	1,300		
3.211	7	Shtrese cakell minash + cilindrim 1 x 20 cm	m ²	7,850		
3.212/b	8	Shtrese stabilizanti 0/20mm t=10cm	m ²	15,240		
3.212/b	9	Shtrese stabilizanti 0/20mm t=10cm per bankinat	m ²	230		
3.222/1	10	Shtrese binderi 5cm + sperkatje me emulsion	m ²	5,480		
3.224/1	11	Shtrese asfaltobetoni 3cm + sperkatje me emulsion	m ²	5,425		
SHUMA A						
B.Punime ne Degezime						
3.158/e	1	Germim dheu kat l-re me skreper,l=100m,v6m3	m ³	47		
An.164/1a	2	Mbushje dhe ngjeshje me material germimi	m ³	117		
3.212/b	3	Shtrese stabilizanti 0/20mm t=10cm	m ²	62		
3.222/1	4	Shtrese binderi 5cm + sperkatje me emulsion	m ²	37		
3.224/1	5	Shtrese asfaltobetoni 3cm + sperkatje me emulsion	m ²	25		
SHUMA B						
C.Punime per Trotuare,Bordura, Kunete,Kanalizime,etj						
1. Ne zonen e banuar						
2.426/2	1	Prishje mur blloqe betoni	m ³	38		
2.37/2a	2	Transport materjale ndertimi,dheu deri ne 2km	m ³	38		
2.54/2	3	Ndertim mur guri i ri me llac cemento M 25	m ³	42		
3.620	4	Shtrese plaka betoni t=6 cm per trotuar	m ²	552		
3.182/a	5	Shtrese rere natyrore t=10 cm	m ²	552		
3.312/b	6	Shtese stabilizanti 0/20 mm per trotuar t=10 cm	m ²	552		
3.243	7	Bordure betoni monolite C 16/20, h=30cm	m ³	35		
3.243	8	Bordure betoni monolite C16/20 ne anen e jasht. trot. variabel	m ³	32		
3.242	9	Beton C12/15 per nivelimin e bordurave	m ³	68		
3.243	10	Beton C 16/20 ne kunete t=10cm, i=10%	m ³	180		
3.183/a	11	Shtrese zhavorri nen kunete me t=10cm	m ²	410		
3.243	12	Riparim shkallësh ekzistuese me beton C 16/20	m ³	2.10		
3.243	13	Beton C 16/20 per ndertimin e kanalit te ujerave te shiut	m ³	10.20		
3.183/a	14	Shtrese zhavorri nen themelin e kanalit t=10cm	m ³	2.55		
An. - 23	15	Puseta shiu + zgare gize 40x60 cm	cope	13		
An. - 7	16	F+V.tub PVC d=315mm per KUB	ml	310		
2.523	17	F.V Tuba PVC f=200 mm të brinjëzuar	ml	75		
An. - 8	18	F+V.tub PVC d=400mm per kuz	ml	510		
An. - 20	19	F+V puseta betoni ne linjen 315mm dhe 400mm	cope	14		

3.25/a	20	Germime dheu seksion I detyruar per puseta + tr.auto	m ³	9		
3.25/a	21	Germime dheu seksion I detyruar per kanalizime+tr.auto	m ³	568		
2.261	22	Mbushje me rere natyrore mbi tuba	m ³	154		
SHUMA 1						
2. Ne rruge						
3.243	1	Bordure betoni monolite C 16/20 me h variabel	m ³	530		
3.240	2	Beton C 12/15 per nivelimin e bordurave	m ³	330		
3.243	3	Beton C 16/20 per kunete t=10cm dhe i=10%.	m ³	390		
3.183/a	4	Shtrese zhavori nen kunete me t=10cm	m ²	3,950		
3.25/a	5	Germime dheu seksion I detyruar per puseta + tr.auto	m ³	110		
3.25/a	6	Germime dheu seksion I detyruar per kanalizime+tr.auto	m ³	6,600		
SHUMA 2						
SHUMA C=1+2						
D. Punime Vepra Arti (Tombino Ø 800mm,Ø1000mm,Ø 1500mm,Mure Mbajtes dhe Prites, Kanale, Drenazhe)						
3.89/a	1	Germim dheu makineri me shk ne mjet per (tomb+pus+port)	m ³	686		
2.557	2	F+V Tombino me tuba b/a mbi shtrese zhavori Ø 800mm	ml	32		
2.560	3	F+V Tombino me tuba b/a mbi shtrese zhavori Ø 1500mm	ml	8		
3.205/2	4	Shtrese zhavorri 20cm nen tuba + ngjeshje.	m ²	140		
3.243	5	Beton C 16/20 per puseta,portale plus kallep	m ³	74		
3.242	6	Beton C 12/15 per bashkimin e elementeve te tobinove	m ³	38		
3.25/a	7	Germim dheu T/F seksion I detyruar per muret	m ³	4,438		
3.243	8	Mure mbajtes dhe prites betoni C 16/20	m ³	1,754		
3.243	9	Beton C16/20 per kunete ne muret prites t=10cm	m ³	28		
3.183/a	10	Shtrese zhavori nen kunetat e mureve prites me t=10cm	m ²	160		
3.183/a	11	Shtrese zhavori nen muret prites dhe mbajtes me t=10cm	m ²	700		
An-10	12	Mbushja me material filtrant germimi ,mbrapa mureve.	m ³	1,954		
3.89/a	13	Germim dheu makineri me shk ne mjet per kanale anesore	m ³	1,266		
3.245	14	Beton C 25/30 per muret e armuar	m ³	47		
3.288	15	F+V hekur betoni per muret e armuar	ton	5		
SHUMA E						
F. Punime Ndricimi						
3.An/53	1	F.V. shtylle metalike H=7.8ml. 4 mm	cope	34		
3.An.	2	F.V.ndricues Sart VP CR1 CR M-S 250W,ME LLAMPE 250W 230V	cope	34		
3.An/ksh	3	F.V. krah shtylle metalike KRH-MSI	cope	34		
An.	4	F.V. kuader komandimi komplet me santeri+ fotoelement	cope	1		
193	5	F.V.morseteri shtylle 3P+sig.16A+kapak	cope	34		
2.a-73	6	Elektroda tokezimi profil zingato e bekerizuar	cope	34		
2.a-93	7	Percjelles tokezimi bakri,CU,S=35mm2 I zhveshur	ml	38		

4.131/3.5	8	F.V. Ne toke Kabelle Cu fuqie 1000V,me izolim gome e mbulese plastmasi,te armuar 4X10MM ²	ml	858		
4.133/3.5	9	F.V. Ne toke Kabelle Al fuqie 1000v,me izolim gome e mbulese plastmasi,te armuar 4X10MM ²	ml	350		
152	10	Kablo Kontrolli 7X4MM ²	ml	281		
161	11	Kablo Cu per ndricim,te izoluar me gome,3X2.5MM ²	ml	192		
3.An/pp	12	F.V.Puseta plastike 4x40x40 me Kapak te forte	cope	34		
209	13	Tub plastmasi te brinjezuar me mufta Ø 100	ml.	848		
An-56	14	F.V.Tub metalik D=100mm	ml.	20		
3.242	15	Beton per betonimin e shtylles ,C 12/15	m3	17		
207	16	Tub plastmasi te brinjezuar me mufta Ø 200	ml	34		
2.261	17	Shtrese rere mbi tubin fleksibel	m3	23		
SHUMA F						
G. Punime Sinjalistike						
An.7	1	F+V Guard Rails tip H2	ml	460		
An.159	2	F+V tabela te medha treguese	cope	14		
An.97	3	F+V tabela rrugore rreziku ne forme trekendore	cope	23		
An.94	4	F+V tabela rrugore rreziku ne forme katerkendore dhe gjashtekendore	cope	14		
SHUMA G						
SHUMA A+B+C+D+E+F=						
FONDI REZERVE 3%						
SHUMA						
T.V.SH 20%						
TOTALI						