

Nr	Nr. Analize	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
A Hidroizolim Tarace ADM2						
1	2.197 (60%)	Shkepje Hidroizolimi me karton katrama egzistues	m2	620		
2	2.264(60%)	Shkepje shtrese lluster çimento.2 cm	m2	620		
3	2.331 (60%)	Shkepje suva e zakonshme fasade mur tulle ~ 8m	m2	30		
4	2.197	Hidroizolim me emulsion bitumi dhe 2 k katrama (trashesia 4 mm)	m2	620		
5	2.264	Shtresë llustër çimento 1:2(trashesia 2 cm)	m2	620		
6	2.203/a	Veshje korrnize llamarine bakri t = 0.8 mm	m2	85		
7	2.206/b	Kasete shkarkimi me llamarine bakri 1.0mm	cope	6		
8	2.209/b	Ulluk shkarkimi vertikal me baker Ø 120	ml	50		

B Riparime Zyrat ADM2 Kati i Dyte

1	2.375 (60%)	Heqje/Dritare d/alumini tek xh.	m2	36.5		
2	2.388/1 (60%)	Heqje/ dyer te brendeshme tamburate te rimesuara	m2	18		
3	2.266 (60%)	Heqje/ Shtrese me pllaka granili te zakonshme, 30x30cm	m2	135		
4	2.267b	Shtrese me pllaka grez importi, 40x40cm	m2	135		
5	2.324a	Plintuse pllake grez	ml	122		
6	2.375/1	F V dritare d/alumini plastike me dopio xham	m2	33.5		
7	2.383/1	F V dyer te brendeshme druri importi cilesi e l-re.	m2	18		
8	2.395	Dyer d/alumini tek xham.	m2	4.5		
9	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier	m2	60		
10	2.328	Patinim muri allçi (stuko)	m2	60		
11	2.404/1	Boje hidroplastike importi cilesi e l-re	m2	1050		

C Riparime Zyrat e ADM3 Kati i Pare

1	2.297/b	F/V Veshje muri me kartonxhes	m2	76		
2	2.297/b	Prishje 60% e op se veshjes *60% e 278l	m2	44		
3	2.404/1	Boje hidroplastike cilesi e larte	m2	393		
4	2.297/b	F/V Tavan i varur me pllaka gipsi 60x60cm	m2	50		
5	2.383/1	F/V Dyer te brendeshme druri importi cilesi e l-re.	m2	15		
6	2.373	F/V Vetrato xhami i temperuar	m2	30		
7	2.284	Shtrese parketi laminat	m2	40		

D Punime elektrike 3 % (A+B)

Shuma (A+B+C+D)

Fondi Rezerve 3%

Vlera Totale (pa tvsh)