

TECHNICAL SPECIFICATIONS

Specifikimet teknike te mjeteve	SUV	EV/SUV or Crossover	Pick-Up	SUV PHEV	MINIVAN 8+1
Engine/Motori	Min 1.6 l	N/A	Min 2.4 l	Min 2.4 l	Min 2.0 l
Fuel/Lenda djegese	Diesel	Electric power	Diesel	Petrol	Diesel
Engine power max/Fuqia Motorike maksimale	Min 100 Kw	Min 100 Kw	Min 100 KW	Min 90 KW	Min 100 KW
Number of cylinders/Numri i Cilindrave	Min 4	N/A	Min 4	Min 4	Min 4
Consumption per 100 km combined/Konsumi i kombinuar per 100 km	Max 6 liters/100km	Max17 kWh	Max 10 liters/100km	Max 6 liters/100km - Max 17 Kwh	Max 8 l/100 km
Gear box/Kutia e shpejtesise (kamio)	Automatic	Automatic	Manual	Automatic	Automatic / Manual
Maximum speed / Shpejtesia Maksimale	Min 180 km/h.	Min 160 km/h	Min 160 km/h	Min 140 km/h	Min 140 km/h
Traction/Terheqja	2x4.	2x4.	4x4	4x4	2x4.
Length/Gjatesi	Min 4400 mm	Min 4600 mm	Min 5200 mm	Min 4500 mm	Min 5000 mm
Height/Lartesi	Min 1600 mm	Min 1700 mm	Min 1700 mm	Min 1600 mm	Min 1900 mm
Width/Gjeresi	Min 1800 mm	Min 1800 mm	Min 1700 mm	Min 1700 mm	Min 1800 mm

Wheelbase distance/Distanca Aksiale	Min 2600 mm	Min 2800 mm	Min 3000 mm	Min 2600 mm	
Number of doors/Numri i dyerve	5 (five)	5 (five)	5 (five)	5 (five)	4 (four)
Number of seats/Numri i vendeve	Min 4 + 1	Min 4 + 1	Min 4 + 1	Min 4+1	8 + 1
Tires size/Gomat	Min R 16	Min R 17	Min R 16	Min R 16	Min R 16
Minimum production year/Viti i prodhimit minimumi	2021	2021	2021	2021	2021
Delivery from signing of contract/Levrimi nga data e nenshkrimit te Kontrates	5(five) months	5(five) months	5(five) months	5(five) months	5(five) months
Load area/Siperfaqja e ngarkeses	N/A	N/A	Min 2 m3	N/A	N/A
Max payload/pesha	N/A	N/A	Min 900 kg	N/A	N/A
Electric motor / Motori Elektrik					
Energy class / Klasi i Energjise		Min A+		Min A+	
Power(rear and front)/Fuqia (para dhe prapa)				Min 60Kw	
Battery / Bateria		Lithium-Ion		Lithium-Ion	
Consumption		Max 17 Kwh/100 km		Max 17 Kwh/100 km	
Battery Capacity/ kapaciteti i baterise (KWh)		Min 60		Min 60	

Normal Charging Time /AC Koha e karikimit 0-100 % (6.6KW)		Max 10 h		Max 10 h	
Normal Charging Time /AC Koha e karikimit 0-100 % (7.4KW)		Max 8 h		Max 8 h	
Fast Charging Time / DC Karikimi i Shpejte 0- 80%		Max 40 min		Max 40 min	
Transmission / Transmisioni		Automatic		Automatic	
Max speed/Shpejtesia maksimale		Min 140 km/h		Min 140 km/h	
Fuel / Karburanti		Electric power		Electric power/Petrol	
Autonomy / Pavaresia		Min 400 km		Min 50 km	
Technical specifications for the chargers / Specifikime teknike per karikuesit					
Level 1 chargers 15 (fifteen) pieces		√		√	
Level 2 chargers 15 (fifteen) pieces		√		√	
IN-230 V, max 16 A, Max 50Hz		√		√	
OUT-32A in AC, 230/400 V,32A, Charging capacity max 22 kW		√		√	

DC Fast Charge 2(two) pieces					
IN-230/400 V, power max 44 KW, max 63 A, Max 50Hz		√		√	
OUT-32A in AC, 230 V,32A, Charging capacity max 22 kW		√		√	
Extra Accessories/Aksesore Extra:					
Hydraulic wheel in the left side / Me timon hidraulik ne krahun e majte.	√	√	√	√	√
ABS and ASR system / Sistem ABS dhe ASR.	√	√	√	√	√
Fog lights / Drita Mjegulle.	√	√	√	√	√
Airbags for driver and passenger / Airbag per Shoferin dhe pasagjerin.	√	√	√	√	√
Glass with nuance, green tinted 5% infrared protection / Xham me nuance, 5 % i lyster me te gjelber, mbrojtje nga rezet infrate kuqe.	√	√	√	√	√
Air conditioning / Clima.	√	√	√	√	√
12V electric system according to CE standards / Sistemi	√	√	√	√	√

elektrik 12 V sipas standartit te CE.					
Remote control for central locking system / Mbyllje e centralizuar e dyerve, komandim ne distance.	√	√	√	√	√
Radio with CD / MP3 player	√	√	√	√	√
The color negotiable upon contract sign / Ngjyra do diskutohet ne lidhjen e kontrates.	√	√	√	√	√
Set pint, warning triangle,tools for spare wheel change, First-aid boxes / Set kriko, xhiro makine trekendesh paralajmerues, kuti e ndihmes se shpejte.	√	√	√	√	√
Replacement tires must be performed every 30,000 km / Nderimi i gomave çdo 30.000 KM.	√	√	√	√	√
The expected amount of kilometers 120,000 per 3 years / Kilometrat e parashikuara do te jene 120.000 per tre vjet.	√	√	√	√	√
Penalty above the expected kilometers / Penaliteti per	0	0	0	0	0

kilometra mbi sasine e parashikuar					
---------------------------------------	--	--	--	--	--