

PREVENTIV

Objekti: Mirembajtje e godines se QSh Baks Rrjoll, Shkoder

Nr	An	Pershkrimi i punimeve	Njesi	Sasi	Çmimi	Vlefte
I		Punime Prishje				
1	2.426	Prishje mur tulle pa pastrim	m3	0.9		0
2	An 2.310	Kepje suvatimi i brendshem dhe tavani	m2	28		0
3	An	Prishje shtrese pllaka	m2	6		0
4	An	Prishje Veshje me pllake majolike	m2	5		0
5	2.426/3	Prishje shtresa betoni	m3	1.2		0
6	An	Heqje pajisje h/sanitare	cope	2		0
7	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m3	2		0
8	An	Heqje dere	m2	1.4		0
9	An 2.196 +2.200	Prishje shtrese hidroizolimi + Shtrese lluster cemento	m2	36		0
10	2.37/5a	Transport materiale ndertimi, dheu me auto deri ne 5.0 km	m3	7		0
		Shuma I				0
II		Punime Ndertimi				
1	2.86	Mur me tulle me 6 vrima, t=12cm, h~3m, llaç perzier M15	m3	0.4		0
2	2.310	Suva brenda mure tulle h~4m me krah, llaç perzier M 25	m2	17		0
3	An 2.310	Suva brenda mur tulle ~ 4m, me krah, llaç perzier M 25 (dore e pare, pa fino)	m2	15		0
4	2.300	Suva solete h ~ 4 m me drejtues, me krah	m2	6		0
5	An	Shtrese termoizoluese me polisterol t=5 cm	m2	36		0
6	2.200	Shtrese mbrojtese lluster cemento 1:2 me fuga cdo 2 m, me pjerrsi rreth 2%	m2	36		0
7	2.197	Hidroizolim me emulsion bitumi dhe 2 shtresa k katrama, spresor 4 mm e ngjitur me te nxehte me shkelje te shtresave rreth 8-10 cm (perfshire edhe parapetin)	m2	48		0
8	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	25		0
9	2.209/a	Ulluk shkarkimi vertikal me PVC Ø 120mm	ml	6		0
10	2.206	Kasete shkarkimi me llamarine xingat	cope	2		0
11	2.273/6	Veshje shkalle + parrak dere (4 cope) me pllake mermer t= 3 cm "Travertine"	m2	2.4		0
12	2.262/3	Shtrese betoni C 12/15	m3	1.2		0
13	2.267/1	Shtrese me pllaka gres porcelanato (koridor, banjo)	m ²	6		0
14	2.326	Veshje me pllake majolike	m2	15		0
15	2.395/a	Dyer d/alumini pa xham me mbushje d/a 1 dere per tualetin 80cm x 200cm)	m2	1.6		0
16	2.495	F.V lavaman porcelani importi me mishelator	cope	1		0

17	2.501	F.V WC allafrenga importi	cope	1		0
18	Oferte	F V rafte me pasqyre	cope	1		0
19	2.494	F.V saracineska bronzi Ø 1/2 " = 15 mm	cope	1		0
20	Oferte	F.V.Aksesore per banjo komplet	cope	1		0
21	An	FV Rrjete kunder insekteve ne dritare	m2	4		0
		Shuma II				0
III		Punime Bojatisje				
1	2.404	Boje hidroplastike per lysterje e ambjenteve te brendshme te godines.	m2	112		0
2	3 An 144	Boje akrilike per lysterje e pjese se poshtme te mureve te brendshme (deri ne lartesine 150 cm)	m2	45		0
3	2.401	Boje vaji sipërfaqe metalike per deren e hyrjes kryesore	m2	5		0
		Shuma III				0
IV		Punime sistemim oborri				
1	An55	Tabele katërkëndore "shërbimi" normal 60x90	cope	1		0
2	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m3	8		0
3	2.258/2	Shtrese zhavori ne teritorin e ndertesave	m3	8		0
4	3.620	Trotuar perimetral te godines, me 6 cm beton me pllaka	m2	40		0
5	2.37/5a	Transport materiale ndertimi, dheu me auto deri ne 5.0 km	m ³	8		0
		Shuma IV				0
V		Spostim i motorrines				
1	2.491/b	F.V Tuba e rakorderi ujesjellesi PE d=25mm, t = 2.0 mm, PN 10	ml	5		0
2	2.494/2	F.V saracineska bronzi Ø 1 " = 25 mm	Cope	1		0
3	M2.An - 16	F V bolier 12 liter, uje te ngrohete sanitar	cope	1		0
4	2.515	F.V pilete dyshemeje Ø 50 mm	Cope	1		0
5	2.494/1	F.V saracineska bronzi Ø 3/4 " = 20 mm	Cope	1		0
		Shuma V				0
VI		Punime elektrike				
1	2.490/d	F.V Kasete plastike KE me 12 modular (vende)	cope	1		0
2	2.490/1	F.V Automat termo/el.manj. diferencial 2P 220V, 32A, dl=0.03A	cope	1		0
3	2.490/1b	F.V Automat termo/el.manj. diferencial 2P 220V, 16A	cope	4		0
4	2.490/1a	F.V Automat termo/el.manj. diferencial 2P 220V, 10A	cope	3		0
5	2.485/g	F.V priza shuko brenda murit 2 fazore 25 A "Gevis"	cope	7		0
6	2.485/b	F.V priza bivalente 220V 10A 2P-T Gevis	cope	7		0
7	2.485/5	F.V Çeles 2 polar 220V 10A "Gevis"	cope	4		0

8	2.487/c	F.V kuti suport pllaket 2 modular Gevis	cope	4		0
9	2.487/d	F.V kuti suport pllaket 4 modular Gevis	cope	7		0
10	2. a-130	Ndricules tip plafoniere ,me llampe fluoreshente 40w,	cope	5		0
11	2.487	F.V Kutiderivacioni plastike	cope	3		0
12	480/2	F.V tub plastmasi Ø 18 ~ 21 mm	m	20		0
13	480/3	F.V tub plastmasi Ø 22 ~ 26 mm	m	50		0
14	2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	m	80		0
15	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	m	180		0
		Shuma VI				0
		SHUMA I + II + III + IV + V + VI				0
		Fond Rezerve 5%				0
		Shuma				0
		TVSH				0
		SHUMA TOTALE				0

Shënim: Çmimet e përdorura janë marrë nga manuali i MPPT me VKM nr.629, datë 15.07.2015