

**OBJEKTI : Rikonstrukcion i banesës te familjeve ne nevoje 2023-2024**

Nr	Nr.An.	Lloji i punimeve	Njësia	Sasia
<b>PUNIME NDERTIMI</b>				
1	2.1	Germim dheu me krah	m <sup>3</sup>	75.16
2	2.114/1	Betonim plinti	m <sup>3</sup>	40.66
3	2.52/2	Themel Mur guri	m <sup>3</sup>	7.00
4	2.117/1	Kollona b/a	m <sup>3</sup>	2.56
5	3.239	Strukture monolite betoni C7/10 nen plint	m <sup>3</sup>	6.00
6	2.167	F V hekur betoni periodik Ø > 10 mm	m <sup>3</sup>	10.94
7	2.70/2	Mur me tulle te lehtsuara dopio deri 3m me llaç perzier M25	m <sup>3</sup>	32.00
8	2.64/2	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 25	m <sup>3</sup>	30.00
9	2.426/2	Prishje Muri	m <sup>3</sup>	0.45
10	2.121/1	Brez b/a C 16/20, h ~ 8 m	m <sup>3</sup>	19.25
11	2.119/1	Arkitrare mbi hapësirat e dyer-dritareve	m <sup>3</sup>	13.80
12	2.130/1	Beton C16/20 per shkallet	m <sup>3</sup>	11.60
13	2.166	F V hekur betoni periodik 6-10	ton	1.62
14	2.219	Ndertim cati vendi me tjegulla marseleze	m <sup>2</sup>	2545.33
15	2.295	Tavane rrjet teli + suva	m <sup>2</sup>	1030.95
16	2.212/b	ulluk horizontal	ml	111.00
17	2.209	ulluk vertikal	ml	49.97
18	2.395/a	F.V Dere e madhe D/alumini	m <sup>2</sup>	22.76
19	2.375	F.V Dritare D/alumini tek xham	m <sup>2</sup>	39.55
20	2.375/a	F.V Dyer D/alumini dyfish xham	m <sup>2</sup>	38.19
21	2.395	Dyer d/alumini tek xham.	m <sup>2</sup>	43.10
22	2.395	F.V Dyer D/alumini	m <sup>2</sup>	45.40
23	2.262/1	Shtrese Betoni dysheme c7/10	m <sup>3</sup>	3.80
24	2.196/c	Hidroizolim dyshemeje me dy shtres mapej	m <sup>2</sup>	40.00
25	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m <sup>2</sup>	644.00
26	2.273	Shtrese pllaka mermeri t = 20 mm	m <sup>2</sup>	5.40
27	2.267/b	Shtrese me pllaka grez importi 40x40 cm per tualet	m <sup>2</sup>	38.30
28	2.324a	Plintuse pllake grez	ml	403.90
29	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m <sup>2</sup>	2169.88
30	2.331	Suva e zakonshme fasade mur tulle h ~ 8 m	m <sup>2</sup>	40.00
31	2.303	Suva solete h > 4 m me drejtues, me krah	m <sup>2</sup>	180.00
32	2.258	Nenshtrese Zhavorri	m <sup>3</sup>	45.60
33	2.399	Bojatisje me gelqere	m <sup>2</sup>	826.42
34	2.495	F.V Lavaman porcelan importi me mishelator	copë	3.00

35	2.501	F.V WC alla frenga	copë	2.00
36	2.515	F.V pilete dysHEMEJE d=50	copë	2.00
37	2.516	F.V Tubo plasmasi dhe rakorderi	ton	0.08
38	2.494/2	F.V saracineska bronzi Ø 1 " = 25 mm	copë	6.00
39	3.377	Ndertim drenazhi, mbushje me gure lumi	m <sup>3</sup>	11.00
40	An-55	F V tub drenazhi Ø 150 mm	ml	60.00
41	2.An - 20	Pusetë shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	1.00
42	An	Riparim catie me tjegulla vendi	m <sup>2</sup>	20.00
43	An	Prishje suva ekzistuese	m <sup>2</sup>	935.00
44	An	Prishje cati ekzistuese	m <sup>2</sup>	814.00
<b>SHUMA 1</b>				
<b>PUNIME ELEKTRIKE</b>				
1	2.480/2	F.V. Tub elektrik plastmasi 18-26	ml	720
2	2.481/3	F.V. Percjelles Ø 4mm	ml	245
3	2.481/2	F.V. Percjelles Ø 2.5mm	ml	650
4	2.485	F V Celesa dhe priza 10A me nulifikim	copë	60
5	2.486	F.V. Portollampa	copë	50
6	2.490/e	F.V. Automat kryesor me 24 vende	copë	9
7	2.490	F.V. Kuader ndricimi	copë	9
8	2.489	F.V. Siguresa 25A	copë	35
9	2.487	F.V. Kuti derivacioni plastike	copë	32
<b>SHUMA 2</b>				
<b>SHUMA 1+2</b>				
<b>T.V.SH 20%</b>				
<b>TOTAL NE LEKE</b>				

SHENIM: Preventivi është vlerësuar me cmimet e V.K.M Nr.629, date 15.07.2015