



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
GRAFIKU I PUNIMEVE

Ndertim rruget Blloku 2 Babrru Koder "Mihal Grameno", "Shtejfen Gjecovi", "Vojo Kusho", "Vicens Prenushi", "Pingul Konferenca e Mukjes" Ltot= 1131 ml				
Objekti: Ndertim Rruga Mihal Grameno" Babrru Koder e Kuqe" B=6m ,(basf= 4.5 ml+ 1x0.5 kub+ 1x1.0 trotuar)				
A		B=6 , asfalt 4.5+kunete 1x0.5 m + trotuare 1x1 m		
		B=5 , asfalt 4.5+kunete 1x0.5 m		
An.	Emertimi i Punimeve		Njesia	Sasia
I	PUNIME NE RRUGE			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	405
2	3.158/5a	Transport dheu me auto 5km	m ³	405
3	An. 8	Mbushje me çakell shkembor	m ³	202.5
4	3.211	Shtrese çakelli T=20cm	m ²	2025
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2025
6	3.222/2	Shtrese binderi 1x6 cm	m ²	2025
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	2025
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	225.0
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	6.75
10	An.	Ngritje pusete+kapak gize	cope	6
11	An.	Spostim shtyllash	cope	8
12	2/426/2	Prishje mure me blloqe + transport	m ³	240
13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	1200
14	An.96	Tabele sinjalistike 60-90cm	cope	6
		SHUMA I		
II	PUNIME NE KUB			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	180
2	3.158/5a	Transport çakelli me auto 5km	m ³	180
3	3 An. 8	Mbushje me çakell shkembor	m ³	90
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	450
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	45
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	18.00
		SHUMA II		
III	PUNIME NE KUN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	120
2	3.158/5a	Transport çakelli me auto 5km	m ³	120
3	3 An. 8	Mbushje me çakell shkembor	m ³	60
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	300
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	7.00
		SHUMA III		
IV	PUNIME TROTUARE(1x1 m)			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	40.50
2	3.158/5a	Transport dheu me auto 5km	m ³	40.50
3	3 An. 8	Mbushje me çakell shkembor	m ³	40.50
4	3.208	Shtrese çakelli T=10cm	m ²	270.0
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	255.0
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	600
7	2/262/4	Beton per fiksime bordure C16/20	m ³	18
8	2.109/2	Shtrese betoni trotuari	m ³	27
		SHUMA IV		
V	PUNIMET VEPRJA ARTI(MURE MBAJTESE)			

DITE PUNE 134

1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m3	60
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	60
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m3	120
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.60
	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.7
		SHUMA IIV		
VI		PUNIME PER NDRICIMIN		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	300
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	300
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	12
4	3.139	Germime dheu me ekskavator me goma	m ³	60
5	3.158/5a	Transport dheu me auto 5km	m ³	60
6	2.261	Mbushje me rere	m ³	24
7	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	36
		SHUMA VI		
		SHUMA A		
OBJEKTI : Ndertim Rruga "Rruga Shtjefen Gjecovi", " Babrru qender , Bashkia Kamez L=175 m , B=5m , (basf= 4.5 ml+ 1x0.5 kunet				
B				
	An.	Emertimi i Punimeve	Njesia	Sasia
I		PUNIME NE RRUGE		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	157.5
2	3.158/5a	Transport dheu me auto 5km	m ³	157.5
3	An. 8	Mbushje me çakell shkembor	m ³	78.75
4	3.211	Shtrese çakelli T=20cm	m ²	787.5
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	787.5
6	3.222/2	Shtrese binderi 1x6 cm	m ²	787.5
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	787.5
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	65.63
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.64
10	An.	Ngritje pusete+kapak gize	cope	3
11	An.	Spostim shtyllash	cope	4.38
12	2/426/2	Prishje mure me blloqe + transport	m ³	105
13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	525
14	An.96	Tabele sinjalistike 60-90cm	cope	4
		SHUMA I		
II		PUNIME NE KUB		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	70
2	3.158/5a	Transport çakelli me auto 5km	m ³	70
3	3 An. 8	Mbushje me çakell shkembor	m ³	35
4	3.an/1t	F.V. Tuba I brinjeluar Ø 315	ml	175
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	8.75
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	5.00
		SHUMA II		
III		PUNIME TROTUARE(0)		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	350
2	2/262/4	Beton per fiksime bordure C16/20	m ³	10.5
		SHUMA III		
IV		PUNIME VEPRA ARTI		
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m3	35
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	35
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m3	123
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.61
	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.7
		SHUMA IV		

PUNIME PER NDRICIMIN				
V				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	175
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	175
3	An.	F.V kasete shperndarese	cope	1
4	3.139	Germime dheu me ekskavator me goma	m ³	35
5	3.158/5a	Transport dheu me auto 5km	m ³	35
6	2.261	Mbushje me rere	m ³	14
7	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	21
SHUMA V				
SHUMA B				
OBJEKTI : Ndertim Rruga "Vojo Kushi " Fush-Kerçik , Bashkia Kamez B=6m , (basf= 4.5 ml+ 1x0.5 kunet+ 2x0.75 trotuar)				
C		B=6 , asfalt 4.5+kunete 1x0.5 m + trotuare 1x1 m		
		B=5 , asfalt 4.5+kunete 1x0.5 m		
	An.	Emertimi i Punimeve	Njesia	Sasia
I PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	351
2	3.158/5a	Transport dheu me auto 5km	m ³	351
3	An. 8	Mbushje me çakell shkembor	m ³	170.7
4	3.211	Shtrese çakelli T=20cm	m ²	1707
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1707
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1707
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1707
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	182.25
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	4.56
10	An.	Ngritje pusete+kapak gize	cope	7
11	An.	Spostim shtyllash	cope	5.75
12	2/426/2	Prishje mure me blloqe + transport	m ³	138
13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	1074
14	An.96	Tabele sinjalistike 60-90cm	cope	8
SHUMA I				
II PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	168.8
2	3.158/5a	Transport çakelli me auto 5km	m ³	168.8
3	3 An. 8	Mbushje me çakell shkembor	m ³	84.4
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	422
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	11.5
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	8.00
SHUMA II				
III PUNIME KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	274.3
2	3.158/5a	Transport çakelli me auto 5km	m ³	274.3
3	3 An. 8	Mbushje me çakell shkembor	m ³	137.15
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	422
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	5.00
SHUMA III				
IV PUNIME TROTUARE(1x1m)				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	57.50
2	3.158/5a	Transport dheu me auto 5km	m ³	57.50
3	3 An. 8	Mbushje me çakell shkembor	m ³	60.38
4	3.208	Shtrese çakelli T=10cm	m ²	230.0
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	402.50
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	844
7	2/262/4	Beton per fiksime bordure C16/20	m ³	25.32
8	2.109/2	Shtrese betoni trotuari	m ³	23
SHUMA IV				
V	PUNIME VEPRA ARTI (MURE MBAJTESE)		NJESIA	SASIA

1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	46
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	46
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	173
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	8.63
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	1.0
SHUMA V				
VI				
PUNIME PER NDRICIMIN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	422
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	422
3	3.an/1sh	F.V. Shtylla metalike konike ndricimi H-9m PAICC-3	cope	12
4	3.an/ksh	F.V. Krah shtylla metalike KRH-MSI 1500/1500/10	cope	12
5	An	F.V Ndricules Led 94W	cope	12
6	An	F.V. morsete tre fazore +siguresa+kapak per shtyllen	cope	12
7	An	F.V Elektroda tokezim komplet l=150m	cope	12
8	4.131/3.6	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mm)	ml	422
9	An	F.V kabell tokezimi 1x3.5mmk	ml	18
10	An	F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A	cope	1
11	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	12
12	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1
13	An.	F.V kuader komandimi per ndricim rrugor	cope	1
14	An.	F.V kasete shperndarese	cope	1
14	3.139	Germime dheu me ekskavator me goma	m ³	84.4
14	3.158/5a	Transport dheu me auto 5km	m ³	84.4
14	2.261	Mbushje me rere	m ³	33.76
14	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	50.64
SHUMA VI				
SHUMA C				
OBJEKTI : Ndertim Rruga " Vicens Prenushi " Fush-Kerçik , Bashkia Kamez B=6m , (basf= 4.5 ml+ 1x0.5 kunet+ 1x1 trotuar)				
D				
	An.	Emertimi i Punimeve	Njesia	Sasia
I	PUNIME NE RRUGE			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	99
2	3.158/5a	Transport dheu me auto 5km	m ³	99
3	An. 8	Mbushje me çakell shkembor	m ³	49.5
4	3.211	Shtrese çakelli T=20cm	m ²	495
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	495
6	3.222/2	Shtrese binderi 1x6 cm	m ²	495
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	495
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	49.50
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.24
10	An.	Ngritje pusete+kapak gize	cope	7
11	An.	Spostim shtyllash	cope	2.75
12	2/426/2	Prishje mure me blloqe + transport	m ³	66
13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	330
14	An.96	Tabele sinjalistike 60-90cm	cope	4
SHUMA I				
II	PUNIME NE KUB			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	44
2	3.158/5a	Transport çakelli me auto 5km	m ³	44
3	3 An. 8	Mbushje me çakell shkembor	m ³	22
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	110
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	5.5
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	3.14
SHUMA II				
III	PUNIME KUN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	71.5
2	3.158/5a	Transport çakelli me auto 5km	m ³	71.5

3	3 An. 8	Mbushje me çakell shkembor	m ³	42.9
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	110
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	5.00
SHUMA III				
IV	PUNIME TROTUARE(2x0.75 m)			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	19.25
2	3.158/5a	Transport dheu me auto 5km	m ³	19.25
3	3 An. 8	Mbushje me çakell shkembor	m ³	2.48
4	3.208	Shtrese çakelli T=10cm	m ²	192.50
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	16.50
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	220
7	2/262/4	Beton per fiksime bordure C16/20	m ³	6.6
8	2.109/2	Shtrese betoni trotuari	m ³	19.25
SHUMA IV				
V	PUNIME VEPRRA ARTI(Mure mbajtese)			
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	22
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	22
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	88
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.53
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.5
SHUMA 6				
VI	PUNIME PER NDRICIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	110
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	110
11	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	6
15	3.139	Germime dheu me ekskavator me goma	m ³	22
16	3.158/5a	Transport dheu me auto 5km	m ³	22
17	2.261	Mbushje me rere	m ³	8.8
18	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	13.2
SHUMA VI				
SHUMA D				
OBJEKTI : Ndertim Rruga "Pingul me Rrugen Koferenca e Mukjes " Babrru Koder e kuqe , Bashkia Kamez (L=150ml,basf= 7.5ml)				
E				
	An.	Emertimi i Punimeve	Njesia	Sasia
I	PUNIME NE RRUGE			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	45
2	3.158/5a	Transport dheu me auto 5km	m ³	45
3	An. 8	Mbushje me çakell shkembor	m ³	56.25
4	3.211	Shtrese çakelli T=20cm	m ²	1125
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1125
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1125
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1125
8	An.	Ngritje pusete+kapak gize	cope	3
9	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	300
10	An.96	Tabele sinjalistike 60-90cm	cope	4
SHUMA I				
SHUMA E				
SHUMA (A-E)				
TVSH 20%				
TVSH TOTALE				

Preventivues :

Ing. Hajredin MURGU