

OBJEKTI: Ndertim Rruget Blloku 3 Bathore 7					122 Dite pune
OBJEKTI : Ndertim Rruga "Lucie Miloti" Bathore7					
I	PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	86.8	
2	3.158/5a	Transport dheu me auto 5km	m ³	86.8	
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	86.8	
4	3.211	Shtrese çakelli T=20cm	m ²	868	
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	868	
6	3.222/1	Shtrese binderi 1x5 cm	m ²	868	
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	868	
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	484	
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	3	
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2	
OBJEKTI : Ndertim Rruga "Lek Dukagjini" Bathore7					
I	PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	88	
2	3.158/5a	Transport dheu me auto 5km	m ³	88	
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	88	
4	3.211	Shtrese çakelli T=20cm	m ²	880	
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	880	
6	3.222/1	Shtrese binderi 1x5 cm	m ²	880	
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	880	
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	490	
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2	
II	PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	211.2	
2	3.158/5a	Transport dheu me auto 5km	m ³	211.2	
3	3.396	Mbushje me cakell pas mureve	m ³	180	
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	217	
5	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	9	
OBJEKTI : Ndertim Rruga "Peqini" Bathore7					
I	PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	88	
2	3.158/5a	Transport dheu me auto 5km	m ³	88	
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	88	
4	3.211	Shtrese çakelli T=20cm	m ²	880	
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	880	
6	3.222/1	Shtrese binderi 1x5 cm	m ²	880	
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	880	

8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	490
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2
III		PUNIME NE KUZ		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	264
2	3.158/5a	Transport dheu me auto 5km	m ³	264
3	3.396	Mbushje me cakell pas mureve	m ³	236
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	217
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	4
OBJEKTI : Ndertim Rruga "Marie Logoreci" Bathore7				
I		PUNIME NE RRUGE		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	116
2	3.158/5a	Transport dheu me auto 5km	m ³	116
3	3.164/1b	Mbushje me cakell shkembor+bankine	m ³	116
4	3.211	Shtrese cakelli T=20cm	m ²	1160
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1160
6	3.222/1	Shtrese binderi 1x5 cm	m ²	1160
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me	m ²	1160
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	630
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2
II		PUNIME NE KUZ		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	278.4
2	3.158/5a	Transport dheu me auto 5km	m ³	278.4
3	3.396	Mbushje me cakell pas mureve	m ³	247
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	284
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	6
OBJEKTI : Ndertim Rruga "Paralel me Peqinin" Bathore7				
I		PUNIME NE RRUGE		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	60
2	3.158/5a	Transport dheu me auto 5km	m ³	60
3	3.164/1b	Mbushje me cakell shkembor+bankine	m ³	60
4	3.211	Shtrese cakelli T=20cm	m ²	600
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	600
6	3.222/1	Shtrese binderi 1x5 cm	m ²	600
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	600
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	350
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2
		SHUMA I		
II		PUNIME NE KUZ		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	144
2	3.158/5a	Transport dheu me auto 5km	m ³	144

122 Dite pune

3	3.396	Mbushje me cakell	m ³	127
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	147
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	3
SHUMA II				
SHUMA I-II				
OBJEKTI : Ndertim Rruga "Pingul me Azem Hajdari" Bathore7				
I	PUNIME NE RRUGE			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	66
2	3.158/5a	Transport dheu me auto 5km	m ³	66
3	3.164/1b	Mbushje me cakell shkembor+bankine	m ³	66
4	3.211	Shtrese cakelli T=20cm	m ²	660
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	660
6	3.222/1	Shtrese binderi 1x5 cm	m ²	660
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	660
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	380
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2
II	PUNIME NE KUZ			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	158.4
2	3.158/5a	Transport dheu me auto 5km	m ³	158.4
3	3.396	Mbushje me cakell pas mureve	m ³	140
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	162
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	3
OBJEKTI : Ndertim Rruga "Synej+seg.paralel me Synej" Bathore 7				
A	An.	Emertimi i Punimeve	Njesia	Sasia
I	PUNIME NE RRUGE			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	248
2	3.158/5a	Transport dheu me auto 5km	m ³	248
3	3.164/1b	Mbushje me cakell shkembor	m ³	248
4	3.211	Shtrese cakelli T=20cm	m ²	2790
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2790
6	3.222/1	Shtrese binderi 1x5 cm	m ²	2790
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri + 3 rampa	m ²	2830
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	294.6
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	3
10	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	14
11	2.426/2	Prishje mur me blloqe	m ³	196
12	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	1320
13	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	8
II	PUNIME NE KUB			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	248

2	3.158/5a	Transport dheu me auto 5km	m ³	248
3	3.396	Mbushje me cakell pas mureve	m ³	#REF!
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	#REF!
5	2.262/4	Shtrese betoni c 16/20 Kunete betoni M - 200	m ³	26.21
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	22
III	PUNIME TROTUARE(2x1 m)			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	124
2	3.158/5a	Transport dheu me auto 5km	m ³	124
3	3.164/1b	Mbushje me cakell shkembor	m ³	248
4	3.208	Shtrese cakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	806
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	806
6	3.616/9	FV Bordura betoni 15x25 cm	ml	1240
7	2.262/4	Beton per fiksime bordure C16/20	m ³	37.2
8	2.262/4	Shtrese betoni trotuari C 16/20	m ³	76.7
III	PUNIME NE KUZ			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	595.2
2	3.158/5a	Transport dheu me auto 5km	m ³	595.2
3	3.396	Mbushje me cakell pas mureve	m ³	510
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	655
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	13
IV	PUNIME PER NDRICIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	620
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	620
3	3.17	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	17
4	3.139	Germim dheu me eskavator	m ³	124
5	3.158/5a	Transport dheu me auto 5km	m ³	124
6	2.261	Mbushje me rere	m ³	49.6
7	3.353	Mbushje me shkemb te germuar me pare	m ³	74.4

Ing. Eglantina Disha