



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI: Ndertim Rruget Blloku 2 Bathore 7

Ndertim Rruget "Teuta Seg1 + Kacaniku ,+Teuta Seg2 + Kelmendi"

+Derlvina+Seg.Kaçaniku+Legjendaret+Jezerce ,Bathore7

OBJEKTI:Ndertim Rruga "Teuta Seg1 + Kacaniku ,+Teuta Seg2 + Kelmendi" Bathore7

**(L1 =600 ml, B =7m, basf= 4.2m, 2x0.4kunete,2x1 trotuar), (L2=330 basf= 4m, 2x0.5m bankine),
(L3= 330ml, basf= 4m, 2x0.5m bankine)**

	An.	Emertimi i Punimeve	Njesia	Sasia	KOHEZGJARJA E PUNIMEVE
I		PUNIME NE RRUGE			95 DFITE PUNE
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	95 ditë pune
1	3.969	Skarifikim shtrese asfalti ekzistues me makineri	m ²	3000	
2	3.139	Germim dheu me eskavator	m ³	648	
3	3.158/5a	Transport dheu me auto 5km	m ³	648	
4	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	660	
5	3.211	Shtrese çakelli T=20cm	m ²	5160	
6	3.212/b	Shtrese stabilizanti t=10cm	m ²	5160	
7	3.222/1	Shtrese binderi 1x5 cm	m ²	5160	
8	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	5160	
9	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	211.19	
10	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	5	
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	13	
12	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	10	
13	2.426/2	Prishje mure me blloqe + transport	m ³	472	
14	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vijejzime kembesoret	ml	2520	
15	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	10	
II		PUNIME NE KUB			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	480	
2	3.158/5a	Transport dheu me auto 5km	m ³	480	
3	3.396	Mbushje me cakell pas mureve	m ³	372	
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	1176	
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	278	
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	40	
III		PUNIME TROTUARE(2x1 m dy ane)			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	180	
2	3.158/5a	Transport dheu me auto 5km	m ³	180	
3	3.164/1b	Mbushje me çakell shkembor	m ³	240	

4	3.208	Shtrese çakelli t=10cm, makadam, përhapur e ngjeshur me makineri	m ²	1020
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	1020
6	3.616/9	FV Bordura betoni 15x25 cm	ml	1200
7	2.262/4	Beton per fiksime bordure C16/20	m ³	36
8	2.262/4	Shtrese betoni trotuari C 16/20	m ³	45
IV	PUNIME NE KUZ(L=335ml)			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	277.2
2	3.158/5a	Transport dheu me auto 5km	m ³	277.2
3	3.396	Mbushje me çakell pas mureve	m ³	237
5	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfishire reren per mbrojtjen e tubit)	ml	329
6	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	6
V	PUNIME PER NDRICIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	600
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	600
3	3.17	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	24
4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	3
5	3.139	Germime dheu me ekskavator me goma	m ³	90
6	3.158/5a	Transport dheu me auto 5km	m ³	90
7	2.261	Mbushje me rere	m ³	48
8	3.353	Mbushje me shkemb te germuar me pare	m ³	42
VI	PUNIME PER GJELBERIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.619/a	FV Bordura betoni 6x20 cm	ml	210
OBJEKTI: Ndertim Rruga "Seg.Kacaniku+Legjendaret" Bathore7				
(L =450ml, B=5ml, basf= 4m, 0.5m bankine ne dy anet)				
I	PUNIME NE RRUGE			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	225
2	3.158/5a	Transport dheu me auto 5km	m ³	225
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	225
4	3.211	Shtrese çakelli T=20cm	m ²	1800
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1800
6	3.222/1	Shtrese binderi 1x5 cm	m ²	1800
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	1800
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	900
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	4
OBJEKTI : Ndertim Rruga " Delvina " Bathore7				
(L =650ml, B=5ml, basf= 4m, 0.5m bankine ne dy anet)				
I	PUNIME NE RRUGE			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	325
2	3.158/5a	Transport dheu me auto 5km	m ³	325
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	487.5
4	3.211	Shtrese çakelli T=20cm	m ²	2600
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2600
6	3.222/1	Shtrese binderi 1x5 cm	m ²	2600

7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	2600
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	1300
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	6
SHUMA I				
OBJEKTI : Ndertim Rruga "Jezerce" Bathore7				
(L =147ml, B=5ml, basf= 4m, 0.5m bankine ne dy anet, KUZ -D=315mm)				
I PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	73.5
2	3.158/5a	Transport dheu me auto 5km	m ³	73.5
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	73.5
4	3.211	Shtrese çakelli T=20cm	m ²	588
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	588
6	3.222/1	Shtrese binderi 1x5 cm	m ²	588
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	588
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	344
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2
II PUNIME NE KUZ				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
1	3.139	Germim dheu me eskavator	m ³	88.2
2	3.158/5a	Transport dheu me auto 5km	m ³	88.2
3	3.396	Mbushje me cakell pas mureve	m ³	65
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	120
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	4

Ing. Eglantina Disha