

ANALIZAT E VECANTA TE ÇMIMEVE

Çpim e ndertimin e pilotave Fi 60 cm (analize per 1 ml) per st e pompimit Nr. 2 Hoxhenj

Nr	Nr An	ZERAT E PUNES	Njesia	Sasia	Cmimi
1	17(An)	Cpm me sonde per inkastrimin e pilotave Fi 60 cm(perfshi kemishe perforcuese)	ml	1	
2	3-244	Beton M 250 per pilen	m3	0.2826	
3	3-288	Hekur betoni per pilen	ton	0.05813292	
		Shuma			

Çpim e ndertimin e pilotave Fi 80 cm (analize per 1 ml) per st e pompimit Nr. 2 Hoxhenj

Nr	Nr An	ZERAT E PUNES	Njesia	Sasia	Cmimi
1	3-An SD6 (me interpolim)	Cpmi I pilotave Fi 80 cm (perfshi kemishim e perforcim)	ml	1	
2	3-244	Beton M 250 per pilen	m3	0.5024	
3	3-288	Hekur betoni per pilen	ton	0.066359747	
		Shuma			

Çpim e ndertimin e pilotave Fi 80 cm (analize per 1 ml) per st e pompimit Matke

Nr	Nr An	ZERAT E PUNES	Njesia	Sasia	Cmimi
1	3.464	Shpim me sonda ne toka te zakonshme Ø 800mm, thellesia (0-10m).	ml	1	
2	3-244	Beton M 250 per pilen	m3	0.5024	
3	3-288	Hekur betoni per pilen	ton	0.066359747	
		Shuma			

Ndertim rrethimi I objektit me tel me gjemba 6 fije teli (I perdredhur me dy fije teli e me gjemba ne çdo 10 cm gjatesi) tend 25 cm lartesi deri ne nje lartesi totale 1,75 cm i (analize per 1 m2 rrethim)

Nr	Nr. An	Emertimi i punimeve	Njesia	Sasia	Cmimi
1	An	Germim per nivelim dhe themelet e shtyllave	m3	0.55	
2	3-243	Beton M 200 , per plinta (0.3x0.3x0.5 ne çdo 2 ml)	m3	0.012857143	
3	3-243/1	Beton M 200 , per kolonetat (0,15 x0.1x 1.8 ml) ne çdo 2 ml	m3	0.007714286	
4	An	Rrethim me 6 fije teli dyfijesh ne lartesi 1,75 cm me gjemba ne çdo 10 cm gjatesi	m ²	1	
		Shuma			

1. Ure kalimi HD = 2 m, H=2m, L = 5 m

Nr	Nr An	ZERAT E PUNES	NJESIA	SASIA	Cmimi
1	3-59 b	Germim dheu per vepren	m3	65.00	
2	3-47/1b	Mbushje + ngjeshje	m3	23.00	
3	3-243	Beton M - 200 per mure e themele.	m3	31.90	
4	3-243	Beton M - 200 per jastek e bordura	m3	3.55	
5	3-243/1	Veshje me beton M-200 (H+D)	m3	1.20	
6	3-244/1	B/arme M - 250 soletone	m3	0.98	

7	2-264	Lluster çimento t = 1 cm	m ²	10.00	
8	2-195	Shtrese bitumi (tre duar)	m ²	10.30	
9	3-243	Beton M - 200 per mbishtrese 4-8 cm	m ³	0.86	
10	3-288	Hekur betoni per soletone	kg	285.20	
11	3-211	Shtrese çakulli t = 20 cm	m ²	15.00	
		Shuma			

2. Ure kalimi HD=1.5, H = 1.1 m ,L=5m

Nr	Nr An	Zerat e punes	Njesia	Sasia	Cmimi
1	3-59 b	Germim dheu per uren	m ³	26	
2	3-47/1b	Mbushje e ngjeshje dheu	m ³	10	
3	3-243	Beton M-200 per muret, themele e bordura	m ³	13.84	
4	3-243	Beton M-200 per jasteket	m ³	1.46	
5	3-244/1	B/arme M-250 per soletone	m ³	1.57	
6	2-264	Lluster çimento 1 cm (1:2)	m ³	0.224	
7	2-195	Tre duar bitumi	m ²	11.2	
8	3-243	Beton M-200 per mbishtrese 4-8 cm	m ³	0.68	
9		Parmake per uren (analize per 1 ml)	ml	9.2	
10	3-288	Hekur betoni per soletonet	kg	198.2	
		Shuma			

3. Ure kembesore HD = 4 m, B = 1 m

Nr	Nr An	ZERAT E PUNES	NJESIA	SASIA	Cmimi
1	3-59/c	Germim dheu per vepren	m ³	0.40	
2	3-47/c	Mbushje + ngjeshje me dhe	m ³	0.30	
3	3-243	Beton M - 200 per mure e themele	m ³	0.40	
4	3-249	B/arme M - 200 soletone	m ³	0.72	
5	3-288	Hekur betoni per soletone	kg	85.20	
		Shuma			

4. Ndertim prize me porte metalike 80x100 dhe me barazh 80x 100 cm (bxh)

Nr	Nr An	ZERAT E PUNES	NJESIA	SASIA	Cmimi
1	3-59/c	Germim dheu per vepren	m ³	10.50	
2	3-471/c	Mbushje + ngjeshje me dhe	m ³	4.50	
3	3-243/1	Beton M 200 per lidhje tubash e mbishtres	m ³	0.60	
4	3-243/1	Beton M 200 per veshje	m ³	1.58	
5	3-240	Beton M 150 per nenshtres	m ³	0.15	
6	3-650	Nenshtrese zhavorri	m ³	0.35	
7	3-644	F e Vendosje porte metalike 80 x 100 cm(me aks te gjate)	ton	0.16	
8	3-644	F. Vendosje porte metalike 100 x120 cm, (Bx H) , me aks te gjate	ton	0.28	
		Shuma			

5. Shkarkues tip Prize 60 x 80 cm

Nr	Nr An	ZERAT E PUNES	NJESIA	SASIA	Cmimi
1	3-59/c	Germim dheu per vepren	m3	4.40	
2	3-471/c	Mbushje + ngjeshje me dhe	m3	1.30	
3	3-243	Beton M - 200 per mure e themele	m3	1.35	
4	3-243/1	Beton M - 200 per veshje	m3	1.74	
5	3-650	Shtrese zhavorri	m3	0.75	
6	3-644	F e Vendosje porte metalike 60 x80 cm	ton	0.28	
		Shuma			

6. Riparime dhe F. Vendosje porte metalike per nenkalimn (lidhja e KK31 me KK 30)

Nr	Nr An	ZERAT E PUNES	NJESIA	SASIA	Cmimi
1	3-59-c-	Germim per pastrim e thellim per inkastrim te mekanizmit mbeshtetese te portes	m3	4.80	
2	2-426/5	Thyerje e hedhje copa betoni	m3	1.60	
3	3-243/1	Beton M 200 per mure , parapete e kanalatura te reja ne shpatullat e barazhit	m3	6.20	
4	3-644	F.Vendosje porte metalike 200x260 cm (BxH)	ton	1.5280	
5	4-112	Pastrim e lyerje me boje antiruxho mbi sip mertalike	m2	6.8	
		Shuma			

7. Rikonstrukcion i rruges ekzistuese per tek st.pompimit Matke (nje shtrese me cakell + stabilizant)

Nr	Nr An	ZERAT E PUNES	Njesia	Sasia	Cmimi
1	An	Germim e transport dheu per rrafshim e per kanale anesor	m3	27	
2	3-209	Mbushje me nje shtresa cakel t= 10 cm	m2	157.5	
3	3-201	Cilindrim me rul shtrese cakelli	m2	157.5	
4	An	shtrese stabilizanti t = 6 cm	m2	157.5	
		Shuma			

8. Rikonstrukcion i rruges ekzistuese per tek st.pompimit , Nr 2 - Suk Hoxhenj

Nr	Nr An	ZERAT E PUNES	Njesia	Sasia	Cmimi
1	An	Germim e transport dheu per rrafshim e per kanale anesor	m3	13.54	
2	3-209	Mbushje me nje shtresa cakel t= 10 cm	m2	73.35	
3	3-201	Cilindrim me rul shtrese cakelli	m2	73.35	
4	An	shtrese stabilizanti t = 6 cm	m2	73.35	
		Shuma			

9. Prishje vepra(kalime me tuba) te demtuara

Nr	Nr An	ZERAT E PUNES	NJESIA	SASIA	Cmimi
1	3-25/b +3-101/a	Germim dheu per riseksionim te kanalit 80 % me makineri	m3	6.46	

2	2-426	Thyerje + hedhje copa gure e beton	m3	1.40	
3	An	Nxjerrje + heqje tuba	ml	5.00	
		Shuma			