

Projektuesi: B.O.E "HYDRO-ENG
CONSULTING"sh.p.k & "ENGINEERING
CONSULTING GROUP"
sh.p.k&"SIRE-ALB"sh.p.k

Objekti: "Rikonstruksioni i rrugës së Bunecit"

Datë: 01-07-2026

PREVENTIV

NR.	KODI	EMËRTIMI I PUNIMEVE	NJËSIA	SASIA	ÇMIMI	VLEFTA
1. PUNIME GERMIMI						
1	3.104/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet >	m3	5500.0		
Shuma 1:						
2. PUNIME SHPYLLEZIMI						
2	3.3	Preje e sistemim pemesh ø 10 ~ 20 cm >	copë	120.0		
Shuma 2:						
3. PUNIME DHEU						
3	2.37/2b	Transport materiale ndertimi, dheu me auto deri 7.0 km >	m3	10900.0		
4	2.47/an	Germim shkambi mesatar me çekiq me ekskavator me zinxhir >	m3	4900.0		
Shuma 3:						
4. PUNIME SHTRESASH						
5	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri >	m3	902.0		
6	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri >	m2	8840.0		
7	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri >	m2	8840.0		
8	3.212/c	Shtrese stabilizant t=15cm >	m2	8840.0		
9	3.212/b	Shtrese stabilizant t=10cm >	m2	680.0		
10	3.210	Shtrese cakelli mbeturine kave t=15cm, perhapur e ngjeshur me makineri >	m2	2453.0		
11	3.198	Cilindrim kasonete me rul >	m2	8840.0		



Shuma 4:						
5. ANALIZA TEKNIKE						
12	3.222/2	Shtrese binderi me granil gur kave, 6cm, me makineri >	m2	6970.0		
13	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri >	m2	6970.0		
Shuma 5:						
6. PUNIME SHITESASH 2						
14	2.262/4	Shtrese betoni C 16/20 >	m3	65.0		
Shuma 6:						
7. PUNIME TE NDRYSHME						
15	3.616/a	F.V. Bordura betoni 15x25cm >	m	1502.0		
16	3.620	Trotuar, me 6 cm beton, me pllaka >	m2	2453.0		
17	3.653	F.V. Tuba plastmasi Ø 150 >	m	6008.0		
Shuma 7:						
8. PUNIME BETONIE BETONARMEJE						
18	3.243	Struktura monolite betoni C 16/20 >	m3	1027.9		
19	3.243	Struktura monolite betoni C 16/20 >	m3	139.0		
20	3.243	Struktura monolite betoni C 16/20 >	m3	36.0		
Shuma 8:						
9. NDERTIMI I VEPRAVE TE ARTIT+KANALIZIME						
21	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni >	m	24.0		
22	3.407	F.V. Tuba metalik D=140mm >	ml	15.0		
23	3.588	Ndertim Pusete kontrolli Elektrotelefoni, me kapak gize, 1.0x1.0x1.0 m >	copë	22.0		
24	3.401/1	Gjeotekstil me gramature 280 g/m2 >	m2	2200.0		
Shuma 9:						
10. D. SINJALET DHE PAJISJET SHITESH. NGADALESHITESH SHPEJTESISE						

25	3.955	F.V. Tabela te ndryshme rrugore D=60cm >	copë	12.0		
Shuma 10:						
11. B. SINJALET HORIZONTALE						
26	3.942	Vijezi shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponte (sprajt) >	ml	3004.0		
Shuma 11:						
12. TE NDRYSHME, ELEKTRIKE DHE SINJALISTIKA						
27	3.172	F.V. Kuader komandimi komplet me santeri+fotoelement >	copë	1.0		
28	3.164/lt	F.V. Tuba te brinjezuar HDPE SN8 d=315 mm >	ml	550.0		
29	3.170	F.V. Pusete elektrike kontrolli PVC 40x40x40cm >	copë	63.0		
30	3.169	F.V. Shtylla metalike per ndricim, H=7m, d=160mm >	copë	63.0		
31	3.168	F.V. Krah shtylla metalike KRH - MSI 1500/1500/10 >	copë	63.0		
32	3.182	F.V. Elektroda tokezimi te xingura 50x3mm L=150cm >	copë	63.0		
Shuma 12:						
13. UJESJELLES E KANALIZIM I JASHEM						
33	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize >	copë	22.0		
Shuma 13:						
14. NENSHTRESA DHE SHITRESA NE TERRITORIN E NDERTESAVE						
34	2.261/a	Nenshtrese rere >	m3	436.0		
Shuma 14:						
15. PUNIME HEKUR BETONI 3						
35	3.287	F.V. Hekur betoni i zakonshem Ø 6 ~ 10mm >	ton	0.45		
36	3.288	F.V. Hekur betoni i zakonshem Ø > 12mm >	ton	1.71		
Shuma 15:						

16. INSTALIME HIDRO-SANITARE DHE NGROHJE						
37	2.611	F.V. Tub PVC Ø 200mm >	ml	48.0		
Shuma 16:						
17. ANALIZA JASHTE LISTE						
38	An	FV ndriçues LED 82.4 W >	copë	63.0		
39	An	F.V Kablllo i tensionit te ulet multipolar bakri, me izolim gome tip G16, veshje PVC, Un = 0,6/1 kV, tip FG16OR16, S = 3x1.5 mm ² >	ml	408.0		
40	An	F.V. Kabell 0,6/1 KV ; tip RG7R ; 4x10mm ² >	ml	600.0		
41	An	F.V. Kabell 0,6/1 KV ; tip RG7R ; 5x10mm ² >	ml	901.0		
Shuma 17:						
Shuma Analiza						
Fondi Rezervë (5.0%)						
Shuma Analiza + Fondi Rezervë (5.0%)						
TVSH (20%)						
Shuma me TVSH						
Totali						

Preventivuesi:

B.O.E "HYDRO-ENG CONSULTING" sh.p.k &
"ENGINEERING CONSULTING GROUP"
sh.p.k & "SIRE-ALB" sh.p.k



Shënime:

Investitori:

Bashkia Himarë

