

PREVENTIVI
Prog 0 - Prog. 240

Nr	Nr. Analize	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vler a
1	Punime Germimi dhe Mbushje ne Rruge					
1	3.89/a	Germim seksion i lire per hapje traseje	m ³	2000		
2	3.158/5a	Transport dheu dhe mbetje urbane deri 5 km	m ³	2000		
3	An.164/1a	Mbushje ngjeshje me çakull mali per nivelim	m ³	500		
					Shuma 1	
2	Punime Shtresash ne Rruge					
1	3.211	Shtrese çakull gurore 10 / 40 t = 1 x 20 cm	m ²	1920		
					Shuma 2	
3	Punime ne trotuare dhe parmake					
1	3.89/a	Germim dheu per trotuaret t mes = 25 cm	m ²	700		
2	3.158/5a	Transport dheu dhe mbetje urbane deri 5 km	m ³	700		
3	An.164/1a	Mbushje ngjeshje me çakull mali per nivelim	m ³	200		
4	3.212/b	Shtrese stabilizanti 10 / 40 t = 10 cm	m ²	1200		
5	2.261	Shtrese rere t = 4 cm	m ³	70		
6	3.620	Shtrese pllakash betoni C 16/20	m ²	960		
7	3.618	Bordure betoni C 16/20 20 x 35 cm	ml	480		
7	3.617/2	Bordure betoni C 16/20 15 x 35 cm	ml	200		
8	3.243/1	Beton C 16/20 per fiksim bordure	m ³	27		
					Shuma 3	
4	Punime betoni ne rruge					
1	3.89/a	Germim dheu	m ³	220		
2	3.158/5a	Transport dheu deri 5 km	m ³	220		
3	An.164/1a	Mbushje me çakull mali	m ³	61.2775		
4	3.243/1	Mur betoni C 16/20	m ³	88		
5	3.288	Hekur betoni per armim	ton	5		
6	3.240	Beton C 12/15 per nenshtrese muri	m ³	14.48		
7	Anal	Mbingritje pusetash	cope	4		
					Shuma 4	

Shuma (1 ÷ 4)

Shuma A

Punime ne sistemin e K.U.B

1	3.89/a	Germim dheu me ekskavator 0.15 m ³ , ne kanale me gjeresi deri 2 m, toke zak, kategoria III, me shkarkim ne mjet	m ³	192		
2	3.46/1	Germim kanali ne toke te forte, me krahe, me seksion deri 0.75 m ²	m ³	48		
3	3.158/5a	Transport dheu 5 km	m ³	240		
4	2.258	Shtrese zhavori lumi t = 10 cm nen tubacion	m ³	26		
5	2.262/3	Shtrese betoni C 12/15 nen tubacion	m ³	28		
6	3.378	Mbushje ngjeshje me zhavorr	m ³	64		
7	2.552	F.v tub betoni Φ 200 mm per lidhjen me pusetat	ml	20		
8	2.553	F.v tub betoni Φ 300 mm	ml	320		
9	2.554	F.v tub betoni Φ 400 mm	ml	160		
10	An - 23	Puseta shiu 40 x 70 me kapak gize	cope	20		

Shuma B

Punime Ndrichimi dhe ne rrjetin e Telefonise

1	3.An/53	F V shtylla metalike per ndrachim, H=7m, d=160mm	cope	10		
2	Anal	F.V.krahe shtylle me 1 dege	cope	9		
3	Anal	F.V.krahe shtylle me 2 dege	cope	1		
4	Anal	F.V.ndraches led per ndrachim rrugor	cope	10		
5	Anal	F.V. morsete tre fazore= siguresa = kapak per shtyllat	cope	10		
6	3.An/pp	F.V.Puseta betoni me kapak gize ne trotuar 40x40x40cm	cope	10		
7	Anal	F.V. tub plastik fleksibel per shtrirje ne toke D = 75 mm	ml	240		
8	Anal	F.V.kuader komandimi me santeri + fotoelementt	cope	1		
9	2.a-73	F.v.elektroda tokezimi L= 50x50x5mm, L= 1.5m te xinguara	cope	10		
10	2.262/3	Betonim shtyllash dhe pusetash me beton C 12/15	m ³	8		
11	Anal	F.v tube P.V.C per rrjetin e Telefonise dhe Elektrik	ml	720		

1 2	2.553	F.v Tub betoni d = 300 mm per kalim rruge	ml	6		
1 3	3.89/a	Germim dheu per kanal	m ³	23		
1 4	2.261	Mbushje me rere nen dhe mbi tub	m ³	8		
1 5	3.378	Mbushje me zhavorr	m ³	6		
1 6	3.158/5a	Transport material i germuar deri 5 km	m ³	23		
Shuma C						

		SHUMA (A+B+C)		
		T.V.SH 20 %	20%	
		SHUMA TOTALE		

