

PREVENTIV PUNIMESH ME CMIME

Autoriteti Kontraktor: BASHKIA MALLAKASTER

Objekti: Rikonstruksioni I rrugeve ne fshatrat "Dukas , Visoke,Greshice, Mollaj "

Faza:Projekt zbatimi

KATEGORIA 1: PUNIME DHERASH						
		EMERTIMI	NJESIA	SASIA	CMIMI	VLERA
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	25 295,0		0,0
2	An	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri (30-50 cm)	m3	15 177,0		0,0
TOTAL Nr1						0,0
KATEGORIA 2: PUNIMET E SHTRESAVE						
		EMERTIMI	NJESIA	SASIA	CMIMI	VLERA
1	An	Shtrese stabilizant t=10cm i ngjeshur me makineri	m2	35 413,0		0,0
2	An	Shtrese stabilizant t=10cm (per bankinat)	m2	4 350,0		0,0
3	An	Shtrese binderi me granil gur kave,6cm,me makineri	m2	35 413,0		0,0
4	An	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m2	35 414,0		0,0
TOTAL Nr 2						0,0
KATEGORIA 3 : VEPRAT E ARTIT						
		EMERTIMI	NJESIA	SASIA	CMIMI	VLERA
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	1 250,0		0,0
2	3,243	Struktura monolite betoni C 16/20 (Veshje kanali)	m3	421,0		0,0
3	2.262/4a	Pllake themeli, trare e bazamente b/a C 20/25	m ³	246,0		0,0
4	An	Mure b/a t = 21-30cm, h ~ 4m C 20/25	m3	255,0		0,0
5	2,167	F V hekur betoni periodik Ø > 12 mm	ton	21,0		0,0
6	3,365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	432,0		0,0
7	3,366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	m	214,0		0,0
8	3,367	Tombino me tuba betoni Ø 1000, mbi shtrese betoni	m	256,0		0,0
TOTAL Nr 3						0,0
		SHUMA (1-3)				0,0
		T.V.SH 20%				0,0
		SHUMA ME TVSH				0,0