



## PREVENTIV PA CMIME

OBJEKTI : PUNIME MIREMBAJTJEJE RRUGA E FSHATIT ZHULAT

Nr. Analize	Nr.	Pershkrimi i punimeve	Njesia	Sasia	Çmimi leke	Vlera leke
<b>I - PUNIME RIPARIMI SHITESASH RRUGORE</b>						
3.197	1	Prishje shtrese cakelli 10 cm me makineri	m <sup>2</sup>	4200		
3.183/a	2	Shtrese zhavori 10 cm	m <sup>2</sup>	4200		
3.244	3	Shtrese betoni struktura monolite C 20/25	m <sup>3</sup>	504		
3.287	4	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	7.224		
3.211	5	Shtrese cakelli mbeturine kave t=20 cm per bankina mak.	m <sup>2</sup>	1000		
3.89/a	6	Germim dheu kanalekat. III eskavator me shkarkim ne mjet	m <sup>3</sup>	200		
3.1	7	Skarifikim bari me lopate	m <sup>2</sup>	2000		
					<b>Shuma I:</b>	
<b>II-PUNIME RIPARIMI TOMBINO</b>						
3.89/a	8	Germim dheu kanalekat. III eskavator me shkarkim ne mjet	m <sup>3</sup>	80		
3.367	9	Tombino me tuba betoni Ø 1000, mbi shtrese betoni	m	8		
3.244	10	Struktura monolite betoni C 20/25	m <sup>3</sup>	108.2		
An.164/1a	11	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m <sup>3</sup>	150		
					<b>Shuma II:</b>	
<b>III- PUNIME RIPARIMI MBROJTJE LUMORE</b>						
3.89/a	12	Germim dheu kanalekat. III eskavator me shkarkim ne mjet	m <sup>3</sup>	200		
3.353	13	Mbushje me shkemb te germuar me pare	m <sup>3</sup>	1000		
					<b>Shuma III:</b>	
					SHUMA	
					FOND REZERVE 3%	
					SHUMA	
					TVSH 20%	
					<b>SHUMA TOTALE</b>	

**OFERTUES**