

Nr	Nr.A n	PËRSHKRIMI PUNIMEVE	Njesi	Sasia	Cmim	Vlera
1		1. PUNIME BETONI + HEKURI				
2	2.166	F.V. Hekur Ø 6-10	ton	2		
3	2.167	F.V. Hekur Ø > 10	ton	6		
4	3.244	Struktura Monolite betoni (Kollona)	m3	25		
5						
6		2. PUNIME MURATURE				
7	2.71/2	Mur me tulle te lehtesuara dopio deri 8m me llaç perzier M25	m3	186		
8	2.84	Mur me tulle me 8 vrima, t=10cm, h~3m, llaç perzier M15	m3	40		
9	2.121/ 1	Brez b/a c 16/20, h~8m	m3	8.9		
10	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	2,623		
11	2.331	Suva e zakonshme fasade mur tulle h~8 m	m2	345		
12	2.399	Sherbetisje e bojatisje me gelqere	m2	2,623		
13	2.404	Boje hidroplastike	m2	680		
14						
15		3. PUNIME HIDRAULIKE				
16	2.494	F.V. Saracineska 1/2"	cope	24		
17	2.494/ 1	F.V. Saracineska 3/4"	cope	24		
18	2.494/ 2	F.V. Saracineska 1"	cope	1		
19	2.519	Tuba plastike 50 p	ml	120		
20	2.520	Tub kanalizimi pvc Ø 110 mm	ml	90		
21	2.515	Pileta dyshemeje Ø 50	cope	12		
22	2.495	F.V lavaman porcelani importi me mishelator	cope	12		
23	2.501	W.C. allafrenga komplet	cope	12		
24	2.508	F.V bolier 100 liter importi	cope	12		
25	2.491/ a	FV Tuba e rakorderi ujesjellesi PPR d=20~25mm, Pn 25	ml	400		
26						

27		4. PUNIME ELEKTRIKE				
28	2.481/ 1	Percjelles elektrik PV-500 Ø1.5mm2	ml	600		
29	2.481/ 2	Percjelles elektrik PV-500 Ø2.5mm2	ml	1,400		
30	2.481/ 3	Percjelles elektrik PV-500 Ø4mm2	ml	300		
31	2.481/ 4	Percjelles elektrik PV-500 Ø6mm2	ml	1,000		
32	2.482/ 1	Percjelles elektrik PV-500 Ø2x1.5mm2	ml	110		
33	480/1	F.V. tubo plastike Ø16mm	ml	300		
34	480/2	F.V. tubo plastike Ø20mm	ml	2,400		
35	480/3	F.V. tubo plastike Ø32mm	ml	700		
36	2.485/ 5	F.V Çeles 2 polar 220V 10A "Gevis" (<i>ose ekuivalent</i>)	cope	100		
37	2.485/ g	F.V priza shuko brenda murit 2 fazore 25 A "Gevis" (<i>ose ekuivalent</i>)	cope	240		
38	2.487	F.V Kutiderivacioni plastike	cope	24		
39	2.487/ d	F.V kuti suport pllaket 4 modular Gevis (<i>ose ekuivalent</i>)	cope	200		
40	2.486	Fv portollamba normale	cope	80		
41	2.490/ e	F.V. automat kryesor me 24 vende	cope	12		
42	2.489	Siguresa 25 A	cope	80		
43	2.490/ 1d	F v diferencial 220V 40A	cope	12		
44	2.a- 120	F v llamp sinjali 220 v	cope	12		
45						
46		5. PUNIME NIVELIMI				
47	2.262/ 3	Shtrese betoni c 12/15	m3	56		
48	2.267/ b	F.V. Pllaka gres	m2	730		
49	2.267/ 1	F.V. pllaka majolike ne WC	m2	190		
50	2.196/ b	Hidroizolim me nje shtrese mapej per tualetet	m2	100		
51						
52		6. PUNIME DYER + DRITARE				
53	2.386/ 1	Dyer te blinduara importi.	m2	24		

	2					
54	2.388/ 1	F.V. dyer te brendshme tamburate te rimesuara	m2	55.2		
55	2.375/ a	F.V. dritare d/alumin dyfish xham	m2	56.8		
56	2.395/ a	Dyer duralumini dopio xham	m2	36		
57	2.267/ a	F.V. davancial mermeri	m2	32		
58	2.209/ a	Ulluk shkarkimi vertikal pvc Ø 120 mm	ml	82.8		
59	2.212/ a	Ulluk shkarkimi horizontal me pvc 33 cm	ml	98.2		
60	2.218	Cati vendi H~ 8 m mbuluar me tjegulla vendi	m2	880		
61	2.297/ b	Tavan I varur me pllaka gipsi 60 x 60 cm	m2	660		
62						
63		7-MBROJTJE KUNDRA ZJARRIT				
64	2.510	FV hidrant me zore 1=40m	cope	1		
65	An	Sinja lizues automat ik	cope	1		
66	An	Fikse tavanore	cope	3		
67	An	Kasete Hidranti	cope	1		
68	An	FikseABC 6kg Powder	cope	3		
69	2.491/ e	F.V T uba e rakorderi ujesjellesi PE d=50mm, t = 3.7 mm, PN 10	ml	15		
70	480/2	F.V tub plastmasi 0 18-21 mm	ml	100		
71	2.487	F.V. kuti deviacioni plastike	cope	3		
72	An	F.V. kablllo izoluar me resin kundra zjarrit 2x1.5 mm	ml	100		
73	An	F.V. paneli optiko-akustik +aksesore	cope	3		
74	2.a- 116	F.V. sirene e brendshme audio vizive	cope	3		
75	An	F.V. centrali dallimit te tymrave+bateri+panel komandimi	cope	3		
76	2.493	F.V tub te zeze dhe rakorderi φ 2"	kg	95		
77	2.493	F.V tub te zeze dhe rakorderi φ 1 1/2"	kg	160		
78					SHUMA 6	
79		SHUMA 1+2+3+4+5+6				19,617,165
80		TVSH 20%				3,923,433
81		SHUMA TOTALE				23,540,598

