



REPUBLIKË E ALBANIË
BASHKIA KAMEZ
PREVENTIV

Objektet :Ndertim Rruga Sado Koshenko (Pjesa e pare) , BABRRU QENDER , PASKUQAN , BASHKIA KAMEZ

(Lt = 610 ml, L1 =410 m B = 6 m, basf= 4.5 m,(1 x 0.5) kunete, + (1x 1 m), Trotuare , L2 = 80 m basf= 3.0 m,(1 x 0.5) kunete L 3=120 m basf= 3.0 m,(1 x 0.5) k

A	An.	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
I		PUNIME GERMIMI				
1	3.139	Germim Dheu me Eskavator Kt III	m ³	529		0
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	529		0
3	An.	Spostim Shtyllash Elektrike (komplet me Kabllo)	cope	6		0
		SHUMA I				0
II		PUNIME NE RRUGE				
1	3/353	Mbushje me çakell shkembor t mes = 15 cm	m ³	386		0
2	3.212	ngjeshur makineri	m ²	2752.51		0
3	3.212/b	Shtrese stabilizanti t=10cm	m ²	2445		0
4	3.222/2	Shtrese binderi 1x6 cm	m ²	2445		0
5	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	2445		0
6	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	204		0
		SHUMA II				0
III		PUNIME BORDURE + KUNETE				
1	2.262/4	Shtrese betoni c 16/20 Kunete betoni	m ³	30		0
2	3.617	F V bordura betoni 15x25 cm	ml	1200		0
3	2.262/4	Shtrese betoni c 16/20 poshte bordures 0.03 m3/ml	m ³	36		0
		SHUMA III				0
IV		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	3.139	Germim dheu me eskavator	m ³	236		0
2	3.158/5a	Transport dheu me auto 5km	m ³	236		0
3	An-8	Mbushje me çakell shkembor	m ³	118		0
4	3.an/1t	F.V. Tuba i brinjezuar Ø 315	ml	590		0
5	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	32		0
		SHUMA IV				0
XI		PUNIME PRISHJE				

1	An-49	Prishje struktura prej betoni + transport	m ³	54.0		-
2	2.426/2	Prishje mur tulle , guri ose blloqe + transport	m ³	184.0		-
		Shuma XI	leke			-
		SHUMA A (I+II+ .. +XI				0
		TVSH 20%				0
		SHUMA TOTALE				0

V.O. Preventivi eshte hartuar ne baze te Vkm nr. 629 date 15.07.2015 + analizat perkatese

PREVENTIVUES :
Ing. Hajredin Murgu

Drejtores Projektive dhe Investimeve
Ing. Flora MUÇA

Drejtor i Pergjithshem
Elvis Gjika

MIRATOI
Rakip SULI
