

PREVENTIV PUNIMESH

OBJEKTI: " NDERTIMI I TREGUT TE GJESE SE GJALLE DHE FRUTA-PERIME " BASHKIA B

Nr	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA
I.Punime sistemimi te jashtem				
1	3.87/a	Germim dheu per sistemim me ekskavator kat.III (sistemim kuotash+muret mbajtese)	m3	3,327.0
2	3/158/5a	Transport dheu me auto deri 5.0 km	m3	3,327.0
3	3.211	Shtrese çakelli mbeturine kave, t=20 cm, e perhapur e ngjeshur me	m2	2,462.0
4	3.212/b	Shtrese stabilizanti t= 10 cm (parkimet)	m2	1,356.0
5	2.262/4	Shtrese betoni C 16/20 (trotuari+vendqendrimi pasagjer)	m3	110.6
6	3.229/1	Shtrese binder me granil guri kave, 5 cm, me makineri	m2	1,356.0
7	3.233/1	Shtrese asfalto-betoni me granil guri kave, 4 cm, me makineri	m2	1,356.0
SHUMA I				
II.Objekti me Konstruksion metalik me kapriate druri				
Ia-Punime dheu				
1	3.87/a	Germim themele e plinta b>2m, ekskavator me goma, kova 0.25m3	m3	1,472.0
2	2,37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	1,472.0
3	An.164/1a	Mbushje me cakell e gur gurore perhapur e ngjeshur me makineri(niv	m3	546.0
Ib-Punime themele betoni I armuar objekti metalik				
1	2.116/1	Beton C25/30 (muret ndermjet hojeve)	m3	39.7
2	2.258	Nenshtrese zhavori +mbushje me zhavor plinta	m3	16.2
3	2.262/1	Shtrese betoni C 7/10 (nen plintat e hojeve)	m3	6.0
4	2.116/1	Beton C25/30 per themele+brez b/a	m3	96.0
5	2.166	F V hekur betoni periodik Ø 6 - 10mm	ton	2.6
6	2.167	F V hekur betoni periodik Ø >10mm	ton	5.4
Ic-Punime konstruksioni metalik				
1	AN 4/1	F.V konstruksion metalik (klasa S-275) kollonat	ton	3.6
2	2.108/a	Kartonxhes per veshjen e kolonave metalike	m2	65.0
Id-Punime hidroizolimi dhe çatije				
1	2.196	Hidroizolim me emulsion bitumi dhe 1 shtrese k/katramaje	m2	882.0
2	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	882.0
3	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	44
4	2.206	Kasete shkarkimi me llamarine xingat	cope	14
SHUMA II				
III-Punime murature te brendshme				
1	2.71/2	Mur tulle i lehtesuar b=25cm	m3	28.0
2	2.86	Mur me tulle me 6 vrime, t=12cm, h~3m, llaç perzier M15	m3	3.0
SHUMA III				
IV-Punime shtresash				
1	3.211	Shtrese çakelli mbeturine kave, t=20 cm,	m2	824.0
2	3.244	Beton C20/25 per dysHEME (t=10 cm)	m3	59.0
3	2.166	F V hekur betoni periodik Ø 6 - 10mm (dysHEMEja e moduleve)	ton	3.2
4	2,326	F.V. Shtrese pllaka dysHEMEje porcelanati	m2	118.0

5	An.	F.V pllaka betoni me forma	m2	496.0
SHUMA IV				
V-Punime dyer dritare, vetrare interier				
1	2.395/a	Dere d/alumini pa xham, me mbushje d/a	m2	26.4
2	2.373/1	F V vetrare d/alumini plastike me dopio xham	m2	130.0
SHUMA V				
VI-Punime suvatimi dhe bojatisje				
1	2.404/1	Boje hidroplastike importi cilesi e I-re	m2	128.0
2	2.31	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	128.0
SHUMA VI				
VII- Sistemi I furnizimit me uje nga ukr				
1	2.491/e	F.V Tuba e rakorderi ujesjellesi PE d=50mm, t = 3.7 mm, PN 10	ml	50
2	2.491/d	F.V Tuba e rakorderi ujesjellesi PE d=40mm, t = 3.0 mm, PN 10	ml	6
3	2.491/c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 2.4 mm, PN 10	ml	35
4	2.491/b	F.V Tuba e rakorderi ujesjellesi PE d=25mm, t = 2.0 mm, PN 10	ml	20
5	An.	F.V. pompe 1.1kw Qmax=140l/min Hmax= 22m	cope	1
6	2.258	mbushje me zhavorr	m3	12
7	2.494/5	F.V saracineska bronzi Ø 2 " = 50 mm	cope	1
8	2.494/3	F.V saracineska bronzi Ø 1 1/4 " = 32 mm	cope	3
SHUMA VII				
VIII-PUNIME ELEKTRIKE				
Ndricimi Modulet				
1	3.497	Germim dheu kanal kablllo, shtyllat dhe pusetat	m3	34
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	34
3	2.261	Mbushje me rere	m3	7
4	An.	F.V.Shirit tregues per trase kablli	ml	60
5	An.	F.V.Kabell Cu me dy shtresa mbrojtese 4x35mm2	ml	60
6	An.	F.V.Percjelles i veshur Cu 1,5 mm2	ml	1680
7	An.	F.V.Percjelles i veshur Cu 2,5 mm2	ml	560
8	An.	F.V.Percjelles i veshur Cu 4 mm2	ml	520
9	An.	F.V. Tub plastik seri e rende D25 mm	ml	180
10	An.	F.V Panel elektrik 72 poste, plastik jashte murit	cope	1
11	An.	F.V . Automat magnetotermik 4x80A + salvavite 30mA	cope	1
12	An.	F.V. Automat magnetotermik 2x10A, 1 poste	cope	4
13	An.	F.V. Automat magnetotermik 2x16A, 1 poste	cope	3
14	An.	F.V. Automat magnetotermik 2x20A, 1 poste	cope	3
15	An.	F.V. Automat magnetotermik 4x20A, 4 poste	cope	1
16	An.	F.V. Automat magnetotermik 4x25A, 4 poste	cope	2
17	An.	F.V. Sinjalizues tensioni 1x220 V	cope	2
18	An.	F.V. Shkarkues TipII, 4 polar +Automat shoqerues 4x80A	cope	1
19	An.	F.V. Ndricues LED 35 W, plafon tavanor jashte murit	cope	76
20	2.483	F.V.Celesa elektrik te thjeshte 10A/220 V	cope	10
21	An.	F.V. Priza shuko jashte murit shuko 16A/220V	cope	56
22	An.	F.V. Kuti jashte murit per CP	cope	66
23	An.	F.V. Kuti shperndarese plastike jashte murit 100x100mm	cope	34
24	An.	F.V. Kuti shperndarese plastike jashte murit 150x100mm	cope	4
25	An.	F.V. Tub plastik D=20mm, per instalim jashte murit	ml	534

26	An.	F.V. Bashkues per Tub plastik D=20mm, per instalim jashte murit	cope	300
27	An.	F.V. Tub plastik D=20mm, per instalim jashte murit	ml	521.7
28	An.	F.V. Kthesa 90° per Tub plastik D=20mm, per instalim jashte murit	cope	140
29	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	2
30	An.	F.V. Shirit tokezimi xinkat 30x3 mm	ml	6
31	An.	F.V. Perejelec Cu/GV=16mm2	ml	2
		SHUMA VII		
		SHUMA		
		Fondi rezerve 3%		
		SHUMA		
		TVSH 20%		
		SHUMA ME TVSH		

PREVENTIVOI
"Novatech Studio" shpk

BELSH

CMIMI	SHUMA
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-
	-

