



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ

PREVENTIV

OBJEKTI : Ndertim Blloku i Pallateve ,Paskuqan1 Rruget Muhamet Prodani + Rruga Luigj Paliq Lt= 510 m ,
PASKUQAN

(Lt = 495 ml, B = 5 m, basf= 3.5 m,(1 x 0.5) kunete, (1x 1 m), Trotuare						
A	An.	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
I						
PUNIME GERMIMI						
1	3.139	Germim Dheu me Eskavator Kt III	m ³	340		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	340		
3	An.	Spostim Shtyllash Elektrike (komplet me Kabllo)	cope	6		
		SHUMA I				
II						
PUNIME NE RRUGE						
1	An-8	Mbushje me çakell shkembor	m ³	242.168		
2	3.211	Shtrese çakelli T=20cm	m ²	1700		
3	3.212/b	Shtrese stabilizanti t=10cm	m ²	1700		
4	3.222/2	Shtrese binderi 1x6 cm	m ²	1700		
5	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1700		
6	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	128		
7	An.	Ngritje pusete+kapak gize	cope	5		
		SHUMA II				
III						
PUNIME BORDURE + KUNETE						
1	2.262/4	Shtrese betoni c 16/20 Kunete betoni	m ³	24.5		
2	3.617	F.V. Bordura Betoni 15x25	ml	1000		
3	2.262/4	Shtrese betoni c 16/20 poshte bordures 0.03 m3/ml	m ³	30		
		SHUMA III				
IV						
PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	3.139	Germim dheu me eskavator	m ³	204		
2	3.158/5a	Transport dheu me auto 5km	m ³	204		
3	3/353	Mbushje me çakell shkembor	m ³	102		
5	3.an/1t	F.V. Tuba i brinjezuar Ø 315	ml	490		
7	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	16		
		SHUMA IV				
V						
PUNIME NE KANALIZIME TE UJRAVE TE ZEZA						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	3.89/1	Germim dheu me eskavator goma 0.25 m3 , ne kanale gjersi deri 2 m, toke e zakonshme e shkarkime ne mjet	m ³	150		

2	3.158/5a	Transport dheu me auto 5km	m ³	150		
3	An /21 Man 2	Pusete Shkarkimi b/a 80x80 cm , h deri 2 m me kapak gize	cope	5		
4	3.An/21t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	300		
5	3.652	F.V Tuba HDPE d=200 mm	ml	86		
6	an-8	Mbushje me çakell shkembor	m ³	112		
SHUMA V						
VI	PUNIME TROTUARE(1 X 1)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	3.139	Germim dheu me eskavator	m ³	382.5		
2	3.158/5a	Transport dheu me auto 5km	m ³	382.5		
3	3/353	Mbushje me çakell shkembor	m ³	85		
4	3.208	Shtrese çakelli T=10cm	m ²	300		
5	2.109/2	Beton C12/15 per trotuar	m ³	34.0		
SHUMA VI						
VIII	PUNIME PER NDRIÇIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	500		
2	3.An/53	F.V. Shtylla metalike konike ndriçimi H-7m PAICC-3	cope	13		
3	3.an/ksh	F.V. Krah shtylla metalike KRH-MSI 1500/1500/10	cope	13		
4	3.an	F.V Ndricules Smart VP CLI CR M-S 250W GG FAE44 (Led 100 W)	cope	13		
5	3.An/et	F.V. morsete tre fazore +siguresa+kapak per shtyllen h=9	cope	13		
6	3.an/ksh	F.V Elektroda tokezim 50x3 mm komplet l=150m	cope	13		
7	2.481/2	F.V Percjelles PV-500 O 2.5 mm ²	ml	105		
8	4.131/3.6	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mmk)	ml	490		
9	An	F.V kabell tokezimi 1x3.5mm	ml	13		
10	An	F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A	cope	13		
11	An-22/1	F.v puseta betoni me kapak gize 40x40 h=100cm	cope	13		
13	3.An.14	F.V kuader komandimi komplet me Santeri+ Fotoelement	cope	1.0		
14	2.109/2	Beton C12/15 per inkastrim shtylle	m ³	6.5		
15	An.	F.V kasete shperndarese	cope	1.0		
16	3.139	Germime dheu me ekskavator me goma	m ³	75		
17	3.158/5a	Transport dheu me auto 5km	m ³	75		
18	2.261	Mbushje me rere	m ³	20		
19	An-8	Mbushje me cakull shkembor (kanal)	m ³	35		
SHUMA VIII						
X	PUNIME PER SINJALISTIKEN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	An152	Vizime me boje bikomponente me gjeresi 15 cm	m ²	100		
2	An138	Vizime me boje bikomponente paste per kembesore	m ²	22		
3	An155	F.V. Tabela sinjalistike rrugore	cope	8		
Shuma X			leke			
XI	PUNIME PRISHJE					

1	An-49	Prishje struktura prej betoni + transport	m ³	56.0		
2	2.426/2	Prishje mur tulle , guri ose bloqe + transport	m ³	125.0		
		Shuma XI	leke			
		SHUMA A (I+II+ .. +XI				
		TVSH 20%				
		TVSH TOTALE				

V.O. Preventivi eshte hartuar ne baze te Vkm nr. 629 date 15.07.2015 + analizat perkatese

PREVENTIVUES :

Ing. Hajredin Murgu

Drejtore Projekteve dhe Investimeve

Ing. Flora MUÇA

Drejtor i Pergjithshem I.P.SH.P.

Elvis Gjika

MIRATOI
Rakip SULI

K R Y E T A R