



REPUBLIKA E SHQIPERISE
BASHKIA FIER
DREJTORIA E PROJEKTEVE TE INFRASTRUKTURES

Adresa: L. "Kastriot"; Rruga "Ramiz Arانيتasi"; Nr.15 Fier - SHQIPËRI Tel. + 355 34 410 650 website: bashkiafier.gov.al

MIRATOHET
KRYETARI I BASHKISE
ARMANDO SUBASHI

PREVENTIV

RIKONSTRUKSION I ARGJINATURES PER MBROJTJEN NGA LUMI VJOSA(BANKINA E
KRAHUT TE MAJTE DEGA MARTINES)ZONA KAFARAJ-CERVEN, L=1332m

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
1	3.3	Prerje e sistemim pemesh \varnothing 10 - 20 cm	cope	30		
2	3.161	Rrafshim skarpate ne germim, ekskavator 1 m3	m ²	9339.948		
3	An.164/1a	Mbushje me material te germuar ne trupin e vepres, perhapur e ngjeshur me makineri	m ³	20355		
4	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	20355		
5	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m ³	310		
6	2.37/2b	Transport materiale ndertimi, dheu me auto deri 7.0 km	m ³	20355		
7	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m ²	5850		
8	3.212/a	Shtrese stabilizanti t=5cm	m ²	5850		
				SHUMA		
				FONDI REZERVE 3%		
				SHUMA		
				T.V.SH. 20%		
				TOTALI		

SHENIM: Ky preventiv eshte hartuar sipas manualit te cmimeve sipas VKM.Nr.629 dat.15/07/2015