

PREVENTIVI

**Objekti: "REHABILITIMI I KANALIT TE UJRAVE TE LARTA NE LAGJEN KONGRESI"
SEGMENTI NGA RRUGA BESIM NURI DERI TEK REZERVUARI L=600ml**

KANALI I UJRAVE TE LARTA						
Nr.	Nr.An	Lloji i punimeve	Njesia	Sasia	Cmimi	Vlera
I.Punime trotuari L=245 ml						
1	2.262/3	Shtrese betoni C12/15 nen bordure 10cm	m ³	14.7		
2	2.258	Shtrese zhavorr trotuar 10 cm	m ³	61.5		
3	2.262/3	Shtrese betoni C12/15 10cm	m ³	61.5		
4	2.266/1	Shtrese pllaka granil me boje 30x30cm	m ²	615.0		
5	3.619/a	Bordure betoni trotuari 6x20	ml	490.0		
				SHUMA 1		
II.Punime trotuari L=310ml						
1	2.262/3	Shtrese betoni C12/15 nen bordure 10cm	m ³	18.6		
2	2.258	Shtrese zhavorr trotuar 10 cm	m ³	105.5		
3	2.262/3	Shtrese betoni C12/15 10cm	m ³	105.5		
4	2.266/1	Shtrese pllaka granil me boje 30x30cm	m ²	1,055.0		
5	3.619/a	Bordure betoni trotuari 6x20	ml	620.0		
				SHUMA 2		
III.Punime Pastrimi kanali						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet(pastrim seksioni)	m ³	2829		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet(sistemim bankinash)	m ³	3750		
3	2.37/4a	Transport dheu auto 4 Km	m ³	6579		
				SHUMA 3		
IV.Punime Sistemimi kanali						
1	3.643	Mbjellje bari ne skarpat	m ²	2500		
2	3.243	Struktura monolite betoni C 16/20	m ³	270		
3	2.182	Konstruksione metalike te thjeshta(portbarazh)	ton	0.6		
4	An164	F.V. Fidane Peme dekorative	cope	93		
5	An168	F.V. Fidane shkurre dekorative "JUNIPERUS"	cope	200		
				SHUMA 4		
V.Punime muri mbajtes (Butobeton)						
1	3.119/a	Germim shkemb i coptuar me ekskavator 0.5 m ³ , shkemb, ne themele gjeresi ~2 m, me shkarkim ne toke,	m ³	35		
2	2.37/4a	Transport dheu auto 5 Km	m ³	35		
3	2.258	Shtese zhavori nen murin mbajtes	m ³	6		
4	2.262	Shtrese betoni C 6/10	m ³	6		
5	2.110/2	Themel e xokel butobetoni C 12/15	m ³	23		
6	2.112/2	Mure buto betoni C 12/15	m ³	66.7		
7	2.521	Tub kanalizimi pvc Ø 140 mm	ml	10		
8	An-9	Mbushje me zhavorr pas mureve	m ³	9		
				SHUMA 5		

SHUMA 1+2+3+4+5	
Fond rez 2%	
SHUMA	
TVSH 20%	
TOTALI	

Punoi: Ing.Ariola Beqo

**Sektori i Projektimit
Ark. Alban Manoku**

**Drejtoria e Planifikimit dhe e Zhvillimit te Territorit
Ing.Mimoza Haxhiu**