

PREVENTIV

Objekti : “Sistemim asfaltim rruga e Lohes Faza 2”

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
Punime ne trup te rruges L= 920 ML						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , toke zak, kategoria III. me shk ne miet	m ³	520	-	-
2	3.158/1a	Transport dheu me auto deri 1.0 km	m3	520	-	-
3	3.183/c	Shtrese zhavor lumi t=20cm	m ²	3,680	-	-
4	3.212/b	Shtrese stabilizanti 10cm per rrugen	m ²	3,465	-	-
5	3.212/a	Shtrese stabilizanti 5 cm per bankine	m ²	320	-	-
6	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m2	3465	-	-
7	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	56	-	-
8	3.617/1	F V bordura betoni 15x30 cm	ml	257	-	-
9	3.239	N/shtr. bet. 10cm niv.e fiks.e bord C 7/10	m3	4	-	-
10	2.262/3	Shtrese betoni C 12/15 per kunetat	m3	12	-	-
					shuma 1	-
Punime per vepra arti						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , toke zak, kategoria III. me shk ne miet	m ³	112	-	-
	3.158/1a	Transport dheu me auto deri 1.0 km	m3	112	-	-
2	3.244/1	Struktura te holla monolite betoni C 20/25 per portal tombino	m3	3	-	-
3	2.258	Nenshtrese zhavori	m3	5	-	-
4	3.367	Tombino me tuba betoni Ø 1000, mbi shtrese betoni	ml	20	-	-
5	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	ml	14	-	-
6	An	zgare hekuri ne rruge me gjeresi 50cm	ml	5	-	-
7	2.112/2	Mure buto betoni C - 12/15	m3	10.979	-	-
8	2.575	Pusete kontrolli 1x1x1.5m	cope	1	-	-
					shuma 2	-
SHUMA						-
TVSH 20%						-
TOTAL						-

PREVENTIVOI
"Novatech Studio"shpk
Emil Nova