

**MIRATOI
KRYETARI
TONIN MARINAJ**

PREVENTIV

Objekti : Ndertim mur mbajtes Goraj (Faza I) L=100 ml

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	300	-	-
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	300	-	-
3	An	Prishje mure guri ekzistues I thate	m ³	132	-	-
4	An-8	Mbushje me cakell pas mureve	m ³	335.0	-	-
5	2.54/2	Mur guri ne lartesi deri 3m me llaç çimento M 25	m ³	310	-	-
6	3.243	Brez betoni C 16/20	m ³	6.9	-	-
7	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.35	-	-
8	An.	Tub kanalizimi pvc Ø 75 mm	ml	60	-	-
		SHUMA				-
		TVSH 20%				-
		TOTAL				-

**PREVENTIVOI
"Novatech Studio"shpk
Ing.Emil Nova**