

PREVENTIV

Objekti : Ndertim Ure ne fshatin Dom, NJA Gurre
BASHKIA KLOS

Nr.	NR.AN	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	VLERA
1		PUNIME TE NDRYSHME				
1	An-49	Prishje struktura prej betoni, ura egzistuese	m ³	150		
2	An_6	Prishje Ura druri, Shtrese me derrasa, 5 cm	m ²	180		
3	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	150		
		SHUMA 1				
2		PUNIME GERMIM-MBUSHJE				
1	3.128/b	Germim shkambi i coptuar me ekskavator 1.0 m ³ , shkemb, ne themele gjeresi >2 m, me shkarkim ne mjet	m ³	78		
2	3.124/1a	Germim shkambi mesatar me çekiç, per themele, me ekskavator me zinxhir	m ³	1,482		
3	3.109/b	Germim zhavorri me ekskavator zingjir 1.0 m ³ , ne kanale gjeresi > 2 m, prani uji ~ 2m, kategoria IV, me shk ne toke.(ne shtrat te lumit)	m ³	2,650		
4	3.456	Shpim me sonda Ø 1 m, ~ 20 m, toke zhavore.	ml	240		
5	3.457	Shpim me sonda "UKS" Ø 1 m, ~ 20 m, toke shkembor	ml	48		
6	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	1,560		
7	An-9	Mbushje, zhavorr per ballat, themelin e ballnave,themelin e pilave dhe soleten e perafimit, sipas profilave terthore	m ³	1,100		
8	3.193/c	Shtrese zhavor lumi t=30cm, me cilindrim	m ²	550		
9	3.212/c	Shtrese stabilizant t=15cm	m ²	550		
		SHUMA 2				
3		MBISTRUKTURA				
		Punime betoni				
1	An_01	F.V Trare gjatesore b/a C 35/45 L= 16.40 ml te parapergatitur, perfshire betoninin, hekurin, kallepin, sipas vizatimit	cope	20.00		
2	3.248	Trare terthore b/a te monolite C 30/37, perfshire kallepet, sipas vizatimit	m ³	28.80		
3	3.248	Beton / arme C 30/37 per soleten e ures t - 20-25 cm dhe trotuare, parapetin dhe trotuaret, perfshire kallepet, sipas vizatimit	m ³	111.97		
4	3.248	Beton / Arme C 30/37 per soleten e perafimit, perfshire kallepet, sipas vizatimit	m ³	7.13		
5	3.241	Nen-Shtrese betoni C 12/15 per soleten e perafimit, perfshire kallepet, sipas vizatimit	m ³	2.70		

		Punime hekuri			
1	3.288	F.V. hekur i zakonshem periodik per traret terthore Ø >12 mm, sipas vizatimit, si me poshte	ton	2.28	
2	3.288	F.V. hekur i zakonshem periodik per soleten e ures dhe trotuaret Ø >12 mm, sipas vizatimit, si me poshte	ton	11.82	
3	3.287	F.V. hekur i zakonshem periodik per soleten e perafimit Ø 6 ~ 12 mm, sipas vizatimit, si me poshte	ton	0.026	
4	3.288	F.V. hekur i zakonshem periodik per soleten e perafimit Ø >12 mm mm, sipas vizatimit, si me poshte	ton	1.170	
		SHUMA 3			
4	NEN-STRUKTURA				
		Punime betoni			
1	3.248	Beton / Arme C 30/37 per themelin e ballnave, ballnat, muret, perfshire kallepet, sipas vizatimit	m ³	304.92	
2	3.241	Nen-Shtrese betoni C 12/15 per themelin e ballnave, perfshire kallepet, sipas vizatimit	m ³	7.80	
3	3.248	Beton / Arme C 30/37 per themelin e pilave, perfshire kallepet, sipas vizatimit	m ³	192.94	
4	3.241	Nen-Shtrese betoni C 12/15 per themelin e pilave, perfshire kallepet, sipas vizatimit	m ³	12.86	
5	3.248	Beton / Arme C 30/37 per pilat, perfshire kallepet, sipas vizatimit	m ³	292.01	
6	3.248	Beton / Arme C 30/37 per jasteket e pilave, perfshire kallepet, sipas vizatimit	m ³	116.28	
7	3.245	Beton / Arme C 25/30 per pilotat e pilave, perfshire kallepet, sipas vizatimit	m ³	226.08	
		Punime hekuri			
1	3.287	F.V. hekur i zakonshem periodik ballnat dhe muret e shpatullave, sipas vizatimit, si me poshte Ø 6 ~ 12 mm	ton	0.011	
2	3.288	F.V. hekur i zakonshem periodik ballnat dhe muret e shpatullave, sipas vizatimit, si me poshte Ø >12 mm	ton	30.02	
3	3.288	F.V.hekur i zakonshem periodik per themelin e pilave, pilat, jasteket, sipas vizatimit, si me poshte Ø 6 ~ 12 mm	ton	0.204	
4	3.288	F.V.hekur i zakonshem periodik per themelin e pilave, pilat, jasteket, sipas vizatimit, si me poshte Ø >12 mm	ton	134.45	
5	3.287	F.V. hekur i zakonshem periodik per pilotat e pilave dhe ballnave, sipas vizatimit, si me poshte Ø 6 ~ 12 mm	ton	2.41	
6	3.288	F.V. hekur i zakonshem periodik per pilotat e pilave dhe ballnave, sipas vizatimit, si me poshte Ø >12 mm	ton	32.47	
		SHUMA 4			
5	PUNIME ASFALTIMI				
1	3.229/1	Shtrese binderi me zall lavatrice,5cm,me makineri	m ²	308	
2	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 3cm, me makineri	m ²	308	
		SHUMA 5			

6 SINJALISTIKA, FUGAT, KUSHINETAT, ETJ					
1	3.An/fg	F.V. Fuge me gome speciale me kanal te gjere ne ura	ml	21	
2	An_02	F.V. Mbeshtetje Neopreni 300x500x145	cope	40	
3	An_03	F.V. Mbeshtetje Neopreni 200x300x123	cope	40	
4	An.18	F.V - guardrail H2 anesore per ure me 2 valez. ne 1 ane ,W4	ml	160	
5	An.39	Fundore guardrail me 2 valez.	cope	4	
6	An_04	F.V. puseta drenazhi, sipas vizatimit	cope	2	
7	An_05	F.V. tuba plastike p.v.c. per largimin e ujrave f - 140	ml	120	
8	3.654	Furnizim, vendosje tuba PVC ø 100, per rrjetet inxhinierike	ml	150	
9	An158	FV tabela te ndryshme rrugore D=60cm	cope	6	
10	3.626	H / Izolim me emulsion, 2 K. Katr. + 3 duar bitum	m ²	308	
11	An126	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm, Termoplastike (paste)	ml	300	
SHUMA 6					
PERMBLEDHESE					
SHUMA 1-6					
Fondi Rezerve			5%		
SHUMA					
T.V.SH.			20%		
SHUMA TOTALE					

Shenime: Cmimet e preventivit jane ne baze manualit te cmimeve te vitit 2015.

Preventivues :
“ERALD-G”SH.P.K

Ing. Gezim Islami