



DREJTORIA E PERGJITHESHME E PLANIFIKIMIT DHE ZHVILLIMIT TE TERRITORIT
DREJTORIA E PROJEKTIMIT

PREVENTIV

**Emertimit: Rrethimi I pronës “Ish Reparti Ushtarak nr. 5011/45”, Surrel
Projekt-zbatim**

		B / 8 PUNIME PER MURIN RRETHUES L=235 ML	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1	3.89/a+ 3.158/5a	Germim dheu per themel te murit rrethues + Transport dheu me auto deri 5.0 km	m ³	164.50		
2	2.262/3	Shtrese betonit t=10 cm M-150	m ³	18.80		
3	2.116/1	Trare themeli monolit b/a C - 16/20	m ³	70.50		
4	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m	m ³	12.90		
5	2.166	F V hekur betoni periodik	ton	7.00		
6	2.258	Mbushje me zhavorr	m ³	37.60		
7	2.340	Suva xokoli me granil e çimento te bardhe	m ²	94.00		
8	2.64/2	Mur me tulle plota me llaç perzier M 25 t=12 cm	m ³	33.80		
9	2.408	Pllake b/a granili mbi mure rrethues dhe mbi kollone	m ²	19.50		
10	2.331	Suva e zakonshme mur tulle dhe kollonat h ~ 8 m	m ²	564.00		
11	2.404/1	Lyerje me boje hidroplastike	m ²	564.00		
12	An	F.V Kangjella dekorative hekuri me figuracion mesatare	m ²	176.00		
13	2.401	Boje vaji sipërfaqe metalik	m ²	141.00		
14	An	F.V porte metalike dekorative rreshqitese	m ²	8.00		
		Shuma	lek			
		5 % Fond rezerve	lek			
		Totali	lek			
		20% TVSH	lek			
		Vlera Totale	lek			